

Vinyl Fabric Specification

DESCRIPTION

This section specifies vinyl fabric.

SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturer's Literature and Data:
 - 1. Description of product.
 - 2. Material manufacturers recommendations for underlayment and fasteners.
 - 3. Application and installation instructions.
- C. Samples:
 - 1. 12 inches by 12 inches for each type, pattern and color.
- D. Test Reports:
 - 1. Abrasion resistance: Depth of wear for each tile type and color and volume loss of tile, certified by independent laboratory.

DELIVERY

- A. Deliver materials to the site in original sealed packages or containers, clearly marked with the manufacturer's name or brand, type and color, production run number and date of manufacture.
- B. Materials from containers which have been distorted, damaged or opened prior to installation will be rejected.

STORAGE

- A. Store materials in weathertight and dry storage facility.
- B. Protect from damage from handling, water, and temperature.

PRODUCT

Product: Upholstery Vinyl Fabric – Monaco – Honeydew
By All Vinyl Fabrics
(877) 618-4695

Width: 54 inch •Weight: 36 oz per linear yd •Abrasion: 1,800,000 Double Rubs
Lightfastness: 650 hrs UV •Mildew and Sulfide StainResistant •CAL 117E •UFAC Class
1 MVSS302 •Anti Microbial •Fitness, Exercise, Healthcare, Hospitality, Contract

BeautyGard® protective top coat finish is produced from environmentally friendly materials and processes and is technically formulated to achieve the highest performance standards on vinyl fabric.

Product Features:

- Superior tear strength

- Easily tailored
- Non-migratory plasticizers to retain a soft and supple feel
- -20° cold crack
- 54" wide
- Weight: 37.7 ounces per linear yard (+/-5%)
- Static dissipative slip finish
- Resistant to scuffs and scrapes
- Produced from environmentally friendly materials and processes
- Made with pride in the USA

Durability of Vinyl Fabric

When subjected to rigorous abrasion exposure using the industry accepted Wyzenbeek test standard, Naugahyde Vinyl Fabric with Advanced BeautyGard exceeds:

- Over 500,000 cycles (one million rubs) on 1.21 cotton/polyester sateen (standard clothing material).
- Over 50,000 cycles on #8 cotton duck (canvas/tent material).
- Over 15,000 cycles on #10 cotton duck (heavy canvas/tent material).

Serviceability of Vinyl Fabric

Naugahyde with Advanced BeautyGuard provides outstanding protection in difficult medical and health care environments. This product contains an agent to protect vinyl fabric against bacterial and fungal micro-organisms.

Disinfectability of Vinyl Fabrics

Naugahyde with advanced BeautyGuard has been formulated to achieve a superior level of disinfectability with disinfectant products containing sodium hypochlorite (common household bleach) diluted 1:10.

Flammability

Formulated to meet the small scale flammability* test requirements contained in the following specifications:

- BIFMA (Screen Test, Sec. 4.6. 1. 1)
- CID A-A-2950-A (Federal Standard 191A test method 5903) replaces CCC-A-680a
- Upholstery Requirements of FAR 25.853

Recommended Applications

Office, Truck seating, Hotel / Motel, RV / Van [vinyl upholstery](#), Restaurant, Auto trim, Lounge, Airports, Hospital, Family room, Nursing home, Living room, Dental clinic, Casual dining.

INSTALLATION

Install in accordance with manufacturer's instructions for application and installation unless specified otherwise.

CLEANING AND PROTECTION

Clean vinyl fabric in accordance with manufacturer's instructions.