



**GENERAL NOTES:**

1. MEDICAL GAS PIPING SHALL BE LABELED IN ACCORDANCE WITH NFPA 99-5.1.11.1.1. PIPING SHALL BE LABELED BY STENCILING OR ADHESIVE MARKERS. PIPING LABELS SHALL BE INSTALLED AT INTERVALS OF NOT MORE THAN 20 ft., AT LEAST ONCE IN OR ABOVE EVERY ROOM, ON BOTH SIDES OF WALLS OR PARTITIONS PENETRATED BY THE PIPING. PIPING SHALL NOT BE PAINTED.
2. MEDICAL SHUT OFF VALVES SHALL BE INSTALLED PER NFPA 99-5.1.11.2. SHUT OFF VALVES SHALL BE LABELED WITH THE SPECIFIC MEDICAL GAS OR VACUUM SYSTEM. THE ROOM OR AREA SERVED, A CAUTION TO NOT CLOSE OR OPEN THE VALVE EXCEPT IN AN EMERGENCY.
3. TUBES, VALVES FITTINGS, STATION OUTLETS AND OTHER PIPING COMPONENTS IN MEDICAL GAS SYSTEM SHALL BE CLEANED FOR OXYGEN SERVICE BY THE MANUFACTURER PRIOR TO INSTALLATION IN ACCORDANCE WITH CGA 6-4.1 "CLEANING EQUIPMENT FOR OXYGEN SERVICE", EXCEPT THAT SUPPLIES SHALL BE PRYED TO BE CLEANED BY MANUFACTURER AND KEPT SEALED UNTIL PREPARED FOR INSTALLATION. FITTINGS, VALVES AND OTHER COMPONENTS SHALL BE DELIVERED SEALED, LABELED AND KEPT SEALED UNTIL PREPARED FOR INSTALLATION.
4. VACUUM TUBING SHALL, PRIOR TO INSTALLATION, BE PROMINENTLY LABELED OR OTHERWISE IDENTIFIED TO PRECLUDE USING MATERIALS OR INSTALLATION PROCEDURES IN THE MEDICAL GAS SYSTEM THAT ARE NOT SUITABLE FOR OXYGEN SERVICE.
5. PROVIDE LOCAL ALARM.

## CONSULTANTS:

ARCHITECT/ENGINEERS

## MEDICAL GAS SYSTEMS

Project Title  
DESIGN OF BUILD BACK

Project Number	612-12-288
Building Number	

**Office of  
Facilities  
Management**



Department of  
Veterans Affairs