



<b>GENERAL NOTES:</b>	
A.	CONTRACTOR IS RESPONSIBLE FOR ALL INTERSTITIAL PATCHING AND PENETRATIONS REQUIRED.
B.	ALL SATELLITE SPD ROOMS TO BE BALANCED TO HAVE A POSITIVE PRESSURE TO ADJACENT ROOM.
C.	CONTRACTOR TO MEASURE AIRFLOW QUANTITIES AT ALL DIFFUSERS AND GRILLES IN SATELLITE SPD ROOMS BEFORE AND AFTER WORK. CONTRACTOR TO VERIFY CONSTRUCTION WORK OR BALANCING SHALL NOT IMPACT AIRFLOW QUANTITIES OF DIFFUSERS AND GRILLES IN ROOMS SERVED BY SAME VAV BOX.
D.	DIFFUSERS LABELED "CFM, EXISTING" DENOTE AN EXISTING DIFFUSER TO BE BALANCED TO CFM INDICATED.

Office of  
Facilities  
Management

 Department of  
Veterans Affairs