


- FOR TRENCH WIDTHS 4' [1219mm] OR LESS REFER TO VA STANDARD DETAIL 32 12 16-01 "TYPE 1 UTILITY TRENCH PATCH". FOR TRENCH WHERE PORTLAND CEMENT CONCRETE (PCC) PAVEMENT EXISTS, REFER TO 32 12 16-03 "TYPE 3 UTILITY TRENCH PATCH".
- ▣ 2" [50mm] MINIMUM OR THICKNESS OF EXISTING PAVEMENT WHICHEVER IS GREATER.
- BITUMINOUS SURFACE TREATMENT (CHIPSEAL) REQUIRED ONLY FOR LONGITUDINAL TRENCHES WITH WIDTHS GREATER THAN 6' [1829mm].
- 4" [100mm] MINIMUM ABC OR THICKNESS OF EXISTING GRANULAR BASE COURSE MATERIALS (E.G. ABC & SELECT MATERIAL) WHICHEVER IS GREATER.  
PORTLAND CEMENT CONCRETE (PCC) THICKNESS EQUAL TO EXISTING.

REFER TO VA STANDARD DETAIL 32 12 16-04 "UTILITY TRENCH PAVEMENT PATCH NOTES" FOR ADDITIONAL INFORMATION.



## TYPE 2 UTILITY TRENCH PATCH

NTS



Department of  
Veterans Affairs

DETAIL TITLE / TYPE 2 UTILITY TRENCH PATCH

SCALE :NONE

DATE ISSUED: DECEMBER 2008

CAD DETAIL NO.: SD321216-02.DWG