

**RFI(s) with Answers:**

**Q: I am currently looking at Solicitation Number VA25713B0114. I have been unable to locate any Technology Drawings for this project. Will there be any Telecommunication or Technology work on this project**

A: See sheet E-112

**Q: The asbestos survey shows streaked floor tile containing asbestos but not sure which streaked tile is asbestos. Any chance we can get a drawing showing the specific locations of asbestos containing material?**

A: "Both tiles (light green floor tile, streaked floor tile) contain asbestos. All floors in the work area have tile."

**Q: Do you know the lever design for the Arrow locksets , series Q?**

A: Arrow Q series office function satin finish lever lock sets, with 6-pin, 0-bitted 'H' keyway non-IC cores.

**Q: Is any med gas existing in the area to be demolished on this project?**

A: No

**Q: What exists on the 1st floor beneath the 2nd floor work area?**

A: Interstitial Space – it is accessible.

**Q: There are items on electrical, mechanical, & plumbing that overlap phases. How do we handle these areas?**

A: The mains of the services are not being demolished so the phases can be accommodated. Provide temporary connections of the mechanical, plumbing, and electrical systems so that the later phases remain in service. Provide temporary mechanical, plumbing, and electrical system connections required to serve the early phases.

**Q: Existing fire system will be demoed. Is the system zoned so that the system will maintain coverage while the various phases are under construction?**

A: The existing fire system must not be demoed. It should only be modified to meet the new layouts. The smoke detectors and sprinklers should stay functional during the entire project. This will limit the ILSM requirements and will eliminate the need to have a 24hr fire watch.

**Q: Has ample time been provided for the project considering the phasing and downtime between phases? Would additional time be considered?**

A: No additional time will be considered. Projected Time Line is as follows. Phase I; 150 days, Transition Time; 45 days, Phase II; 120 days, Transition Time 45 days, Phase III; 90 day.

**Q: Where will the existing vaults be moved to?**

A: If by existing vaults you mean safes, then there specified location is shown on sheet A-104. Hot Lab 234 and Hot Lab 215.

**Q: What kind of access for second level structural support? Why does room 201 "camera room" have no structural support like rooms 202,203 & 204 have?**

A: Install W14x43 23' long beneath centerline of room 201.

**Q: What type monitor is needed for airborne disease? Is a manometer needed for entire project?**

A: See added Infection Control Section.

**Q: Contractors is to move existing gamma cameras. What type training is required? Who is manufacturer & point of contact? What rooms are gamma cameras currently in? Are they in Phase I or where? How many are to be moved?**

A: Contractor will only have to ensure the gamma cameras are ready for removal. Which includes but not limited to power and data has been disconnected. All items have be removed or demoed that may be in the way.

**Q: What type classes are needed in the training for working with infection prevention?**

A: See added Infection Control Section.

**Q: Drawing A-102 demo plan for temp walls does not match with phasing plan. Need clarification of temp walls for each phase.**

A: See attached.

**Q: Drawing for A-103 shows doors 212.1 as double doors. Door schedule shows 1 3-0x7-0 door, and what phase would this door be replaced in?**

A: Change NO. of door at NO. 212.1 to 2, and Phase 1.

**Q: A-100 notes – which room 205 is supposed to be the temp camera room? Who is equipment supplier?**

A: The supplier is the VA Bio-Med and IT shops. General note #2 says “provide temporary camera reading room in room number 205 with temporary utility hookups IT, power and telephone control. Coordinate with owner.”

**Q: Room 212 shows GWB hard finish on A-105 reflected ceiling plan, and ACT Armstrong 581 on the finish room schedule, which is correct?**

A: GWB

**Q: Rooms 201, 202, 203 & 204 shows grids on A-105 reflected ceiling plan and GWB hard ceiling on room finish schedule A-602. Which is correct?**

A: ACT Armstrong 581

**Q: Is a professional photographer required for all phases project?**

A: Yes.

**Q: Infection Control: Note 3/GI003 states, "The ICRA shall be written into the contract.....to prevent cost discrepancies." Please provide a project-specific *Infection Control Risk Assessment (ICRA)* for this project (i.e. Class III, Class IV, etc).**

A: Class IV. Also see attached spec 028500.

**Q: Infection Control: Note 7/GI003 states, "Construction workers shall wear Dupont Tyvek coveralls or equivalent over clothing and shoe covers..." In the past, the VA has allowed contractor workers to HEPA vacuum their clothes before leaving the ante-room in lieu of wearing coveralls and shoe covers. Would that be acceptable on this project?**

A: It is acceptable to have the contractor's workers HEPA vacuum their clothes before leaving the ante-room in lieu of wearing coveralls and shoe covers. If the contractor workers fail to abide by this then they will be required to wear coveralls and shoe covers.

**Q: Statement of Work, paragraph 2.3.D.: Subject reference requires a CQCP. Is a full-time, sole responsibility contractor quality control manager required in addition to the project superintendent?**

A: A full-time, quality control manager is not required if the superintendent has experience as a quality control manager. A review of the superintendent resume is required if quality control manager and the superintendent is the same person.

**Q: Statement of Work, paragraph 2.2.A.ii.d.: Subject reference states, "Any ACM left out of this report is the contractor's responsibility to abate and remove." That statement is unreasonable and conflicts with Section 028211, para 1.2. and Section 028213, para 1.2. As best we can tell, neither the survey performed by PSI nor the plans/specifications detail ACM quantities to be abated. Please provide so we know what to bid.**

A: See attached drawing SK-1

**Q: Statement of Work, paragraph 2.2.A.ii.e.: Subject reference states, "Loads must be verified with a structural engineer for the new placement of nuclear storage safes In Room 234 Hot Lab. If additional supports are required, it is the contractor's responsibility to install." This is a design requirement and should be performed by the Designer of Record, not the contractor. Drawing 5- 101 identifies other structural modifications but does not include Room 234. Without engineering data, further site investigation and sufficient time to perform a design analysis, it is not reasonable to make structural design a contractor requirement. Please provide any structural modifications necessary to support the Hot Lab lead-line safes.**

*A: Are there actually 6 of these at 2,500 pounds each? It looks like maybe there are only 3? If there are actually 3 in hot lab 234 in addition to 3 in hot lab 215 structural will probably need to add another beam. **Yes there are 6 at 2,500 pounds each. 3 in each hot lab. Hot Lab 234 should utilized the same beam as hot lab 215 W16x36 44' long beneath centerline of proposed safe location in Room 234***

**Q: Statement of Work. paragraph 2.2.A.iv.f.: Please identify locations for expanded metal walk platforms that need to be installed for access. Also, please provide construction details.**

A: Answer, "Expanded metal walkways are only required if the equipment is not installed as indicated, and not accessible from the existing walkways. If required construction shall match existing with expanded metal spanning between existing structure."

**Q: Section 010000-2, paragraph 1.2.B.: Subject reference describes an 'Add Alternate No.2'. Standard Form 1442, Section B, makes no provision for an "Add Alternate No. 2". The Bid Schedule takes precedence. Please revise the Bid Schedule if "Add Alternate No. 2" pricing is required.**

A: Amendment A00005 has been issued to clarify. Their no Add Alternates.

**Q: Section 010000-9, paragraph 1.6.G.: Subject reference identifies an "Add Alternate No.1". Additive Alternate No.1 is also summarized on Drawing Gi-001. Standard Form 1442, Section B, makes no provision for an "Add Alternate No. 1". The Bid Schedule takes precedence. Please revise the Bid Schedule if "Add Alternate No. 1" pricing is required.**

A: Amendment A00005 has been issued to clarify. Their no Add Alternates.

**Q: Section 010000-22, paragraph 1.16.L.: The list of Contractor-provided field office FFE is quite lengthy (expensive) and Includes numerous duplications. Is that the intent? We ask because the field office is only 720 SF (say 12' x 60') subdivided to provide only one office and one toilet. Please clarify.**

A: No field offices are allowed.

**Q: Section 010000-22, paragraph 1.16.L.: Will utility services (water, fuel and electrical power) for the Resident Engineer's field office be provided by the Government at no expense to the contractor?**

A: No field offices are allowed.

**Q: Section 010000-26. paragraph 1.20.A.: Will electrical power and fuel, if any, required during construction be provided by the Government at no expense to the contractor?**

A: Electrical power will be provided by the government at no expense to the contractor. Any fuel needs will be the responsibility of the contractor.

**Q: Section 010000-32, paragraph 1.28: Please provide more information about the storage space to be provided by the contractor (i.e. specific location, size, proximity to existing utility services, finishes, etc.)**

A: Disregard section 010000-32 1.28 Storage for department of veterans affairs equipment.

**Q: Drawing A-100: In reference to the phasing plan, how much time will the VA need to occupy the newly constructed area between phases? This is important for schedule planning purposes.**

A: 45 days will be needed in order to transition to the new areas.

**Q: Drawing A105: What do the small solid black dots on the reflected ceiling plan represent? Those dots are not identified on the *Legend*.**

A: These are can lights.

**Q: Section 117300: What manufacturer is the basis of design for the ceiling mounted patient lift system?**

A: Basis of design was Medcare Products, model 625.

**Q: Notes 2&3, Drawing A-104: Are material data sheets available for the Owner-furnished fume hood and PPE cabinet?**

A: Attached.

**Q: Is any med gas existing in the area to be demolished on this project?**

A: No.

**Q: What exists on the 1st floor beneath the 2nd floor work area?**

A: Interstitial Space – it is accessible.

**Q: There are items on electrical, mechanical, & plumbing that overlap phases. How do we handle these areas?**

A: The mains of the services are not being demolished so the phases can be accommodated. Provide temporary connections of the mechanical, plumbing, and electrical systems so that the later phases remain in service. Provide temporary mechanical, plumbing, and electrical system connections required to serve the early phases.

**Q: Existing fire system will be demoed. Is the system zoned so that the system will maintain coverage while the various phases are under construction?**

A: The existing fire system must not be demoed. It should only be modified to meet the new layouts. The smoke detectors and sprinklers should stay functional during the entire project. This will limit the ILSM requirements and will eliminate the need to have a 24hr fire watch.

**Q: Has ample time been provided for the project considering the phasing and downtime between phases? Would additional time be considered?**

A: No additional time will be considered. Projected Time Line is as follows. Phase I; 150 days, Transition Time; 45 days, Phase II; 120 days, Transition Time 45 days, Phase III; 90 day.

**Q: Where will the existing vaults be moved to?**

A: If by existing vaults you mean safes, then their specified location is shown on sheet A-104. Hot Lab 234 and Hot Lab 215.

**Q: What kind of access for second level structural support? Why does room 201 “camera room” have no structural support like rooms 202, 203 & 204 have?**

A: Install W14x43 23’ long beneath centerline of room 201.

**Q: What type monitor is needed for airborne disease? Is a manometer needed for entire project?**

A: See added Infection Control Section.

**Q: Contractors is to move existing gamma cameras. What type training is required? Who is manufacturer & point of contact? What rooms are gamma cameras currently in? Are they in Phase I or where? How many are to be moved?**

A: Contractor will only have to ensure the gamma cameras are ready for removal. Which includes but not limited to power and data has been disconnected. All items have be removed or demoed that may be in the way.

**Q: What type classes are needed in the training for working with infection prevention?**

A: See added Infection Control Section.

**Q: Drawing A-102 demo plan for temp walls does not match with phasing plan. Need clarification of temp walls for each phase.**

A: See attached.

**Q: Drawing for A-103 shows doors212.1 as double doors. Door schedule shows 1 3-0x7-0 door, and what phase would this door be replaced in?**

A: Change NO. of door at NO. 212.1 to 2, and Phase 1.

**Q: A-100 notes – which room 205 is supposed to be the temp camera room? Who is equipment supplier?**

A: The supplier is the VA Bio-Med and IT shops. General note #2 says “provide temporary camera reading room in room number 205 with temporary utility hookups IT, power and telephone control. Coordinate with owner.”

**Q: Room 212 shows GWB hard finish on A-105 reflected ceiling plan, and ACT Armstrong 581 on the finish room schedule, which is correct?**

A: GWB

**Q: Rooms 201, 202, 203 & 204 shows grids on A-105 reflected ceiling plan and GWB hard ceiling on room finish schedule A-602. Which is correct?**

A: ACT Armstrong 581

**Q: Is a professional photographer required for all phases project?**

A: Yes.