

Philadelphia VA Medical Center, Philadelphia, PA
Renovations to Upgrade HVAC in SPD

Project No. 642-11-150
Final Documents Issue: 7/30/2012
Revised: 3/6/13

SECTION 09 06 00
SCHEDULE FOR FINISHES

SECTION 09 06 00-SCHEDULE FOR FINISHES

VAMC: Philadelphia
Location: Philadelphia, Pennsylvania
Project no. and Name: 642-11-150
Submission Final Documents
Date: July 30, 2012

SECTION 09 06 00
SCHEDULE FOR FINISHES

PART I - GENERAL

1.1 DESCRIPTION

This section contains a coordinated system in which requirements for materials specified in other sections shown are identified by abbreviated material names and finish codes in the room finish schedule or shown for other locations.

1.2 MANUFACTURERS

Manufacturer's trade names and numbers used herein are only to identify colors, finishes, textures and patterns. Products of other manufacturer's equivalent to colors, finishes, textures and patterns of manufacturers listed that meet requirements of technical specifications will be acceptable upon approval in writing by contracting officer for finish requirements.

1.3 SUBMITALS

Submit in accordance with SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES—provide quadruplicate samples for color approval of materials and finishes specified in this section.

1. DIGITAL COLOR PHOTOS-INTERIOR VIEWS:

Room Number and Name	Item/View to be Photographed
1.Exist Prep B2A116A	Perspective from Southeast
2.Sterile storage B2A117	Perspective from Southwest
3.Conference B2A120	Perspective from Northwest
4.	

1.4 APPLICABLE PUBLICATIONS

A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in text by basic designation only.

B. MASTER PAINTING INSTITUTE: (MPI)

2001.....Architectural Painting Specification Manual

PART 2- PRODUCTS

2.1 DIGITAL COLOR PHOTOS

A. Size 24 x 35 mm.

B. Labeled for:

1. Building name and Number.

2. Room Name and Number.

2.2 DIVISION 31 - EARTHWORK

2.3 DIVISION 06 WOOD, PLASTICS, AND COMPOSITES

A. SECTION 06 20 00, FINISH CARPENTRY

1. THROUGH - WALL COUNTER OR PASS THROUGH COUNTER (TYPE B)		
Room No. and Name	Component	Finish/Color
B2A116 - Exist. Sterile Storage	Countertop	Stainless Steel No 4
B2A113A - Scope Dry	Countertop	Cast Plastic Corian Series 'E' or equal. Color to be selected by VA.

2.4 DIVISION 07 - THERMAL AND MOISTURE PROTECTION

A. SECTION 07 92 00, JOINT SEALANTS

Location	Color	Manufacturer	Manufacturer Color
Masonry Expansion Joints	Match Adjacent		
CMU Control Joints	Match Adjacent		
New to Existing Walls	Match Adjacent		

2.5 DIVISION 08 - OPENINGS

A. SECTION 08 11 13, HOLLOW METAL DOORS AND FRAMES

Paint both sides of door and frames same color including ferrous metal louvers, and hardware attached to door	
Component	Color of Paint Type and Gloss
Door	Match Existing
Frame	Match Existing
Window frame	Match Existing

B. SECTION 08 31 13, ACCESS DOORS AND FRAMES

Material	Finish/Color
Steel	Match Existing
Stainless steel	No 4

C. SECTION 08 33 13, COILING COUNTER DOORS

Philadelphia VA Medical Center, Philadelphia, PA
Renovations to Upgrade HVAC in SPD

Project No. 642-11-150
Final Documents Issue: 7/30/2012
Revised: 3/6/13

Location	Material	Finish	Manufacturer	Manufacturer Color Name/No.
B2A116 - Exist. Sterile Storage	Stainless Steel	No 4	Cookson	NA

D. SECTION 08 56 19, PASS WINDOWS

Room No. and Name	Finish	Glazing	Manufacturer	Mfg. Color Name/No.
B2A116 - Exist. Sterile Storage	Alum	¼" Clear Tempered		

E. SECTION 08 71 00, BUILDERS HARDWARE

Item	Material	Finish
Hinges	Match Existing	Match Existing
Door Closers	Match Existing	Match Existing
Closer/ Holder	Match Existing	Match Existing
Floor Stops	Match Existing	Match Existing
Door Holders	Match Existing	Match Existing
Lock/ Latches	Match Existing	Match Existing
Key Cabinet	Steel	Match Existing
Armor Plates	Match Existing	Match Existing
Kick Mop Plates	Match Existing	Match Existing
Door Edging	Match Existing	Match Existing
Exit Device	Match Existing	Match Existing
Flush Bolts	Match Existing	Match Existing
Door Pulls	Match Existing	Match Existing

Push Plates	Match Existing	Match Existing
Combination Push Pull Plate	Match Existing	Match Existing
Coordinators	Match Existing	Match Existing
Threshold	Match Existing	Match Existing

F. SECTION 08 80 00, GLAZING

Glazing Type	Manufacturer	Mfg. Color Name/No.
G-1	Oldcastle	Clear Tempered Glass
G-2	Oldcastle	Clear Wired Glass

2.6 DIVISION 09 - FINISHES

A. SECTION 09 30 13, CERAMIC TILING

1. CERAMIC TILE					
Color	Size	Shape	Pattern	Manufacturer	Mfg. Color Name/No.
FT-1	2" x 2"	Square	N/A	American Olean	Costa Rei - CR82 Terra Marrone
WT-1	4" x 4"	Square	N/A	American Olean	Satinglo - OD12 Almond
3. SECTION 09 30 13, PORCELAIN PAVER TILE GROUT					
Finish Code		Manufacturer		Mfg. Color Name/No.	
GR-1		Hydroment or Eq.		To match tile	

--	--	--

4. SECTION 09 30 13, MARBLE THRESHOLDS		
Marble Type	Manufacturer	Mfg. Color Name/No.
Carerra Marble	T.B.D.	White

B. SECTION 09 51 00, ACOUSTICAL CEILINGS

Finish Code	Component	Color Pattern	Manufacturer	Mfg Name/No.
	Exposed Suspension System			
AT-1	Exposed Suspension System	White fine texture	Armstrong	Match Existing
AT-2	Exposed Suspension System	White fine texture	Armstrong	Style: Dune Size: 24" x 24" Tegular Grid: 15/16" Lay-in
AT-3	Exposed Suspension System	White mineral texture	Armstrong	Style: Clean Room Mylar Size: 24" x 48" Grid: 15/16" Lay-in

C. SECTION 09 65 19, RESILIENT TILE FLOORING

Finish Code	Size	Material/Component	Manufacturer	Mfg Name/No.
VCT	12" x 12"	VCT	Armstrong	Excelon Imperial 51858 Sand Drift

				White
Welded Sheet Vinyl	72" x 25'-0" min	WSF	Armstrong	Medintech 88432 Pumice Stone

L. SECTION 09 65 13, RESILIENT BASE STAIR TREADS AND ACCESSORIES

Finish Code	Item	Height	Manufacturer	Mfg Name/No.
RB	Rubber Base (RB)	4"	Roppe	To Match Existing

D. SECTION 09 67 23, EPOXY RESINOUS FLOORING (RES6)

Finish code	Manufacturer	Mfg. Color Name/No.
RES6	Stonhard	Stonclad UR Beechwood

E. SECTION 09 68 00, CARPETING

Finish Code	Size	Material/Component	Manufacturer	Mfg Name/No.
CP	24" x 24"	Carpet Tile	Bigelow	7873 Thinking Tawny

F. SECTION 09 91 00, PAINT AND COATINGS

1. MPI Gloss and Sheen Standards

		Gloss @60	Sheen @85
Gloss Level 1	a traditional matte finish-flat	max 5 units, and	max 10 units
Gloss Level 2	a high side sheen flat-"a velvet-like" finish	max 10 units, and	10-35 units
Gloss Level 3	a traditional "egg-shell like" finish	10-25 units, and	10-35 units

Philadelphia VA Medical Center, Philadelphia, PA
Renovations to Upgrade HVAC in SPD

Project No. 642-11-150
Final Documents Issue: 7/30/2012
Revised: 3/6/13

Gloss Level 4	a "satin-like" finish	20-35 units, and	min. 35 units
Gloss Level 5	a traditional semi-gloss	35-70 units	
Gloss Level 6	a traditional gloss	70-85 units	
Gloss level 7	a high gloss	more than 85 units	

2. Paint code	Gloss	Manufacturer	Mfg. Color Name/No.
P-1	Level 3	Sherwin Williams	Match Existing or SW6098 Pacer White
P-2	Level 5 - Epoxy	Sherwin Williams	Epoxy - Match P-1 Color
P-3	Level 3	Sherwin Williams	SW 0031 Dutch Tile Blue
P-4	Level 3	Sherwin Williams	Hollow Metal - Match Existing Typical all Hollow Metal
P-5	Level 3	Sherwin Williams	Ceiling White Typical all Gyp bd ceilings
P-6	Level 5 - Epoxy	Sherwin Williams	Epoxy Ceiling White Typical all Gyp bd ceilings in areas that receive P-2 walls

2.7 DIVISION 10 - SPECIALTIES

A. SECTION 10 11 13 / 10 11 23, CHALKBOARDS / TACKBOARDS

Room No. and Name	Component	Material	Manufacturer	Mfg. Color Name/No.

Philadelphia VA Medical Center, Philadelphia, PA
Renovations to Upgrade HVAC in SPD

Project No. 642-11-150
Final Documents Issue: 7/30/2012
Revised: 3/6/13

B. SECTION 10 26 00, WALL GUARDS AND CORNER GUARDS

Item	Material	Manufacturer	Mfg. Color Name/No.
Corner Guards	Vynil	Acrovyn	SSM-20/ Color to Match Existing

C. SECTION 10 28 00 / 10 14 00 / 11 17 36, MISCELLANEOUS SPECIALITIES

Room No. and Name	Item	Finish	Manufacturer	Mfg. Color Name/No.
SPD Office B2A116D, Existing Sterile Storage B2A116, Conference B2A120, Exist Prep B2A116A	Lobby Clock	To Be Determined	Peter Pepper	Mfr: Peter Pepper Products Style: PPP SynTech Time System Items: Master Clock and Receiver Clocks

D. SECTION 10 44 13, FIRE EXTNGUISHER CABINETS

Component	Material	Finish
Fire Extinguisher Cabinet	Painted Steel	White

E. SECTION 10 28 00, TOILET AND BATH ACCESSORIES

Item	Material	Manufacturer	Mfg. Color Name/No.
1	Toilet Tissue	Bobrick	B-667

	Dispenser		Stainless Steel, No. 4
2	Soap Dispenser	Bobrick	B-155 Stainless Steel, No. 4
3	Frameless Mirror	Bobrick	B-1556
4A, 4B, 4C,	Grab Bars	Bobrick	B-6106.99 Stainless Steel, No. 4
5	Paper Towel Dispenser	Bobrick	B-4262 Stainless Steel, No. 4
7	Sanitary Napkin Disposal	Bobrick	B-270 Stainless Steel, No. 4
10	Robe Hook	Bobrick	B-7672 Stainless Steel, No. 4
11	Shower Seat, Folding	Bobrick	B-5181, Stainless Steel, No. 4, White Phenolic
12	Mop Rack	Bobrick	B-239x34 Stainless Steel, No. 4
All exposed piping	Undercover Pipe Protection	TruBro	White

2.8 DIVISION II - EQUIPMENT

A. SECTION 11 71 01, STERILIZATION EQUIPMENT

Component	Manufacturer	Mfg. Color Name/No.
Cart Washer	By VA	
Scope Drying Cabinet	Stanley InnerSpace	3800 DA Large Diameter Scope Drying Cabinet
Steam Sterilizer	By VA	

Ethylene-Oxide Abator	Steris	TBD
-----------------------	--------	-----

2.9 DIVISION 12- FURNISHINGS

A. SECTION 12 31 00, METAL CASEWORK

Item/ Type	Finish	Manufacturer	Mfg. Color Name/No.
Scope Processing B2A112 - Countertop	Stainless Steel		No. 4
Exist Prep B2A116A - Countertop	Stainless Steel		No. 4
Lockers B2A115A & B2A115D - S1 - Guardian Double Tier Lockers	Painted Metal	Penco	Color TDB
Lockers B2A115A & B2A115D - F17 - ADA Bench 20"D x 17"H x Length Shown	Anodized Aluminum Pedastals w Solid Surface Top	Robinson Steel, Co	Color TDB

B. SECTION 12 32 00, WOOD CASEWORK

Item Type	Location	Finish/Color
Existing Sterile Storage B2A116	Solid Surface Countertop with P-Lam supports	TBD

C. SECTION 12 36 00, COUNTERTOPS AND ACCESSORIES

Type	Finish/Color
------	--------------

Philadelphia VA Medical Center, Philadelphia, PA
Renovations to Upgrade HVAC in SPD

Project No. 642-11-150
Final Documents Issue: 7/30/2012
Revised: 3/6/13

Solid Surface	Corian, Grade E, Color TBD
Stainless Steel	No. 4

2.10 DIVISION 22 - PLUMBING

A. SECTION 22 40 00, PLUMBING FIXTURES AND TRIM

Item	Color
Water Closet	White
Lavatories	White
Service Sink Corner	White
Service Sink	White

2.11 DIVISION 26 - ELECTRICAL

A. SECTION 26 51 00, BUILDING LIGHTING INTERIOR

Fixture Type	Exterior Finish	Color
All	Painted	White

PART III EXECUTION

3.1 FINISH SCHEDULES & MISCELLANEOUS ABBREVIATIONS

FINISH SCHEDULE & MISCELLANEOUS ABBREVIATIONS	
Term	Abbreviation
Access Flooring	AF
Accordion Folding Partition	AFP
Acoustical Ceiling	AT
Acoustical Ceiling, Special Faced	AT (SP)
Acoustical Metal Pan Ceiling	AMP
Acoustical Wall Panel	AWP
Acoustical Wall Treatment	AWT
Acoustical Wallcovering	AWF
Anodized Aluminum Colored	AAC
Anodized Aluminum Natural Finish	AA
Baked On Enamel	BE
Brick Face	BR
Brick Flooring	BF
Brick Paving	BP
Carpet	CP
Carpet Athletic Flooring	CAF
Carpet Module Tile	CPT
Ceramic Glazed Facing Brick	CGFB
Ceramic Mosaic Tile	FTCT
Concrete	C

Concrete Masonry Unit	CMU
Divider Strips Marble	DS MB
Epoxy Coating	EC
Epoxy Resin Flooring	ERF
Existing	E
Exposed Divider Strips	EXP
Exterior	EXT
Exterior Finish System	EFS
Exterior Paint	EXT-P
Exterior Stain	EXT-ST
Fabric Wallcovering	WF
Facing Tile	SCT
Feature Strips	FS
Floor Mats & Frames	FM
Floor Tile, Mosaic	FT
Fluorocarbon	FC
Folding Panel Partition	FP
Foot Grille	FG
Glass Masonry Unit	GUMU
Glazed Face CMU	GCMU
Glazed Structural Facing Tile	SFTU
Granite	GT
Gypsum Wallboard	GWB
High Glazed Coating	SC
Latex Mastic Flooring	LM
Linear Metal Ceiling	LMC
Linear Wood Ceiling	LWC
Marble	MB
Material	MAT
Mortar	M

Multi-Color Coating	MC
Natural Finish	NF
Paint	P
Paver Tile	PVT
Perforated Metal Facing (Tile or Panels)	PMF
Plaster	PL
Plaster High Strength	HSPL
Plaster Keene Cement	KC
Plastic Laminate	HPDL
Polypropylene Fabric Wallcovering	PFW
Porcelain Paver Tile	PPT
Quarry Tile	QT
Radiant Ceiling Panel System	RCP
Resilient Stair Tread	RST
Rubber Base	RB
Rubber Tile Flooring	RT
Spandrel Glass	SLG
Stain	ST
Stone Flooring	SF
Structural Clay	SC

Suspension Decorative Grids	SDG
Terrazzo Portland Cement	PCT
Terrazzo Tile	TT
Terrazzo, Thin Set	
Textured Gypsum Ceiling Panel	TGC
Textured Metal Ceiling Panel	TMC
Thin set Terrazzo	TST
Veneer Plaster	VP
Vinyl Base	VB
Vinyl Coated Fabric Wallcovering	W
Vinyl Composition Tile	VCT
Vinyl Sheet Flooring	VSF
Vinyl Sheet Flooring (Welded Seams)	WSF
Wall Border	WB
Wood	WD

3.2 FINISH SCHEDULE SYMBOLS

Symbol Definition

- ** Same finish as adjoining walls
- No color required
- E Existing
- XX To match existing
- EFTR Existing finish to remain
- RM Remove

3.3 ROOM FINISH SCHEDULE

INTERIOR COLOR AND ROOM FINISH SCHEDULE (New Construction and Renovation)												DATE: July 30, 2012	
ROOM NO.	ROOM NAME	FLOOR			BASE		WALL		WAINSCOT		CEILING		REMARKS
		MAT	C C		MAT	C C	MAT	C C	MAT	C C	MAT	CC	
CB2-4	Exist Corridor	VCT		N	RB		P-1		-		XX		
				E	RB		P-1		-				
				S	RB		P-1		-				
				W	RB		P-1		-				
B2A108	Exist Vestibule	XX		N	QT		P-2		-		XX		
				E	QT		P-2		-				
				S	QT		P-2		-				
				W	QT		P-2		-				
B2A109	Exist Decontamination	XX		N	XX		P-2		-		GWB		
				E	XX		P-2		-				
				S	XX		P-2		-				
				W	XX		P-2		-				
B2A109B	Exist Manual Eq Wash	XX		N	WT1		WT1		-		GWB		Patch as required to match existing

INTERIOR COLOR AND ROOM FINISH SCHEDULE (New Construction and Renovation)										DATE: July 30, 2012
				E	WT1		WT1		-	
				S	WT1		WT1		-	Patch as required to match existing
				W	WT1		WT1		-	Match Existing
B2A109C	H.A.C.	QT		N	QT		P-2		-	GWB
				E	QT		P-2		-	
				S	QT		P-2		-	
				W	QT		P-2		-	
B2A109J	Exist Ante Room	XX		N	QT		P-2		-	GWB
				E	QT		P-2		-	
				S	QT		P-2		-	
				W	QT		P-2		-	
B2A110	Exist Vestibule	XX		N	QT		P-2		-	XX
				E	QT		P-2		-	
				S	QT		P-2		-	
				W	QT		P-2		-	
B2A112	Existing Prep / Sterilization	RES6		N	RES		P-2		-	GWB
				E	RES		P-2		-	

INTERIOR COLOR AND ROOM FINISH SCHEDULE (New Construction and Renovation)											DATE: July 30, 2012
	Existing floor	QT		S	RES		P-2		-		
				W	RES		P-2		-		
B2A112A	ETO	RES6		N	RES		P-2		-	GWB	
				E	RES		P-2		-		
	Existing floor	QT		S	RES		P-2		-		
				W	RES		P-2		-		
B2A112B	Surgical Cart Packing & Storage	WSF		N	RB		P-2		-	AT-3	
				E	RB		P-2		-		
				S	RB		P-2		-		
				W	RB		P-2		-		
B2A112C	Surgical Storage	WSF		N	RB		P-2		-	AT-3	
				E	RB		P-2		-		
				S	RB		P-2		-		
				W	RB		P-2		-		
B2A113	Scope Processing	RES6		N	RES		P-2		-	GWB	
				E	RES		P-2		-		
				S	RES		P-2		-		

INTERIOR COLOR AND ROOM FINISH SCHEDULE (New Construction and Renovation)											DATE: July 30, 2012
				W	RES		P-2		-		
B2A113A	Scope Dry	RES6		N	RES		P-2		-	GWB	
				E	RES		P-2		-		
				S	RES		P-2		-		
				W	RES		P-2		-		
B2A114	Clerical	CP		N	RB		P-1		-	AT-2	
				E	RB		P-1		-		
				S	RB		P-1		-		
				W	RB		P-3		-		
B2A114A	SPD Office	CP		N	RB		P-1		-	AT-2	
				E	RB		P-1		-		
				S	RB		P-3		-		
				W	RB		P-1		-		
B2A114B	SPD Chief Office	CP		N	RB		P-1		-	AT-2	
				E	RB		P-1		-		
				S	RB		P-3		-		
				W	RB		P-1		-		
B2A114C	SPD Office	CP		N	RB		P-1		-	AT-2	

INTERIOR COLOR AND ROOM FINISH SCHEDULE (New Construction and Renovation)										DATE: July 30, 2012	
				E	RB		P-3	-			
				S	RB		P-1	-			
				W	RB		P-1	-			
B2A115	Hall	VCT		N	RB		P-1	-	AT-2		
				E	RB		P-1	-			
				S	RB		P-1	-			
				W	RB		P-1	-			
B2A115A	Men's Locker	VCT		N	RB		P-2	-	AT-3		
				E	RB		P-2	-			
				S	RB		P-2	-			
				W	RB		P-2	-			
B2A115B	Men's Toilet	FT-1		N	PT1		P-2	WT1, 4'-0"	GWB		
				E	PT1		P-2	WT1, 4'-0"			
				S	PT1		P-2	WT1, 4'-0"			
				W	PT1		P-2	WT1, 4'-0"			
B2A115C	Women's Toilet	FT-1		N	PT1		P-2	WT1, 4'-0"	GWB		

INTERIOR COLOR AND ROOM FINISH SCHEDULE (New Construction and Renovation)										DATE: July 30, 2012	
				E	PT1		P-2	WT1, 4'-0"			
				S	PT1		P-2	WT1, 4'-0"			
				W	PT1		P-2	WT1, 4'-0"			
B2A115D	Women's Locker	VCT		N	RB		P-2	-		AT-3	
				E	RB		P-2	-			
				S	RB		P-2	-			
				W	RB		P-2	-			
B2A118	Existing Sterile Storage	WSF		N	RB		P-2	-		AT-3	
				E	RB		P-2	-			
				S	RB		P-2	-			
				W	RB		P-2	-			
B2A118A	Breakdown / Bulk Storage	VCT		N	RB		P-2	-		AT-1	
				E	RB		P-2	-			
				S	RB		P-2	-			
				W	RB		P-2	-			
B2A119	Hall	CP		N	RB		P-1	-		AT-2	

Philadelphia VA Medical Center, Philadelphia, PA
Renovations to Upgrade HVAC in SPD

Project No. 642-11-150
Final Documents Issue: 7/30/2012
Revised: 3/6/13

INTERIOR COLOR AND ROOM FINISH SCHEDULE (New Construction and Renovation)										DATE: July 30, 2012	
				E	RB		P-1	-			
				S	RB		P-1	-			
				W	RB		P-1	-			
B2A119A	Conference	CP		N	RB		P-1	-	AT-2		
				E	RB		P-1	-			
				S	RB		P-3	-			
				W	RB		P-1	-			
B2A119B	Office	CP		N	RB		P-1	-	AT-2		
				E	RB		P-1	-			
				S	RB		P-3	-			
				W	RB		P-1	-			
B2A119C	Clerical	CP		N	RB		P-1	-	AT-2		
				E	RB		P-1	-			
				S	RB		P-3	-			
				W	RB		P-1	-			
B2A121	Forms Room	XX		N	XX		P-2	-	XX		
				E	XX		P-2	-			
				S	XX		P-2	-			

Philadelphia VA Medical Center, Philadelphia, PA
Renovations to Upgrade HVAC in SPD

Project No. 642-11-150
Final Documents Issue: 7/30/2012
Revised: 3/6/13

INTERIOR COLOR AND ROOM FINISH SCHEDULE (New Construction and Renovation)											DATE: July 30, 2012
				W	XX		P-2		-		
B2A122	Mail Room	XX		N	XX		P-2		-	XX	
				E	XX		P-2		-		
				S	XX		P-2		-		
				W	XX		P-2		-		

--- E N D---