

Environmental Liabilities Dayton VAMC

Thursday, February 28, 2013

Estimated Cost: \$875

Building: 119 Catholic Chapel

Material Location: 101

Material Description	Friability	Sample Results	Sample Comments	Quantity	Units	\$/unit	Est. Cost
9x9" Floor tile and underlying black mastic-gray	Cat I-NF	ACM		200	sf	\$2.00	\$400

Material Location: 102

Material Description	Friability	Sample Results	Sample Comments	Quantity	Units	\$/unit	Est. Cost
----------------------	------------	----------------	-----------------	----------	-------	---------	-----------

Material Location: 103

Material Description	Friability	Sample Results	Sample Comments	Quantity	Units	\$/unit	Est. Cost
9x9" Floor tile and underlying black mastic-tan/orange/fleshtone	Cat I-NF	ACM		5	sf	\$5.00	\$25

Material Location: 207

Material Description	Friability	Sample Results	Sample Comments	Quantity	Units	\$/unit	Est. Cost
9x9" Floor tile and underlying black mastic-brown with white streak pattern	Cat I-NF	ACM		225	sf	\$2.00	\$450