



NEW WORK NOTES:

1	NOT USED
2	NOT USED
3	PROVIDE AND INSTALL NEW IT OULET, WIRING
4	PROVIDE AND INSTALL NEW SCHEDULE 40 BLACK PIPE, WITH DROPS AND NEW HEADS (white eschutcheons), MEET CURRENT CODE AND PROVIDE INSPECTION UPON COMPLETION
5	PROVIDE AND INSTALL WALL MOUNTED SINK, ADA COMPLIANT WITH SENSOR, CHROME FAUCET, GRID DRAIN, ALL PLUMBING MATERIALS
6	PROVIDE AND INSTALL NEW MIRROR, STAINLESS STEEL FRAME, 24"x36", COMMERCIAL QUALITY
7	PROVIDE AND INSTALL NEW HIGH EFFICIENCY TOILET SYSTEM, TYPE: SLOAN, WEIS 2002.1201, SOLAR POWERED SENSOR AND ASSOCIATED PLUMBING
8	PROVIDE AND INSTALL ADA RESTROOM PARTITIONS, CLASS A OR B FIRE RATING,SOLID PLASTIC, STAINLESS STEEL HARDWARE (NETPAR, FT700PY OR EQUAL), WITH 36" DOOR
9	PROVIDE AND INSTALL 42" ADA GRAB BARS, BRUSHED STAINLESS STEEL
10	PROVIDE AND INSTALL TROWEL APPLIED EPOXY FLOOR, 1/4" THICK, TYPE: BASF, SELBATWED 71, WITH A 6" WALL BASE
11	PROVIDE AND INSTALL NEW FLOOR DRAINS, CLEAN OUTS AND COVER (TIE INTO EXISTING DRAINS)
12	PROVIDE AND INSTAL BATHROOM EXHAUST, TIE INTO EXIST EXHAUST DUCT AND ALL ASSOCIATED ELECTRICAL
13	PROVIDE AND INSTALL AUTOMATIC DOORS, WITH PUSH PLATE INSIDE AND IN CORRIDOR, ALL MATERIALS
14	PROVIDE AND INSTALL LIGHT SWITCH, STAINLESS STEEL FACE PLATE, WIRING
15	PREP AND PAINT CEILING AND WALLS WITH SHERWIN WILLIAMS, HARMONY, SEMI-GLOSS
16	PROVIDE AND INSTAL, 2'x4', COOPER LIGHTING, ACCORD SERIES, 215 LAMPS, QTY. 2
17	PROVIDE AND INSTALL NEW 24"x24" STAINLESS STEEL MAINTENANCE ACCESS PANEL
18	PROVIDE AND INSTALL CEILING TILE AND GRID, BAROQUE, BET-157, 24"x24"x5/8"
19	PROVIDE AND INSTALL WALL TILE FROM THE TOP OF THE 6" EPOXY WALL BASE TO THE CEILING. AMERICAN OLEEN, TORRE VENATO, SABRIA TN 86, 12"x12"

DEMO NOTES:

1D	NOT USED
2D	ABATE VCT FLOOR AND MASTIC
3D	REMOVE EXISTING LIGHTS AND WIRING BACK TO THE NEAREST J-BOX
4D	DEMO WALL TILE FROM FLOOR TO CEILING AND REPAIR WALL AS NEEDED
5D	DEMO VINYL WALL COVERING
6D	DEMO EXISTING SPRINKLER PIPE, HEADS, DROPS
7D	NOT USED
8D	DEMO EXISTING TOILETS, PLUMBING AND SEAL CONCRETE FLOOR
9D	NOT USED
10D	DEMO EXISTING SINK AND PLUMBING AND REPAIR WALL
11D	REMOVE AND STORE ALL WALL ITEMS (RETAIN FOR THE VA)
12D	NOT USED
13D	REMOVE FLOOR TILE AND PREP FOR NEW FLOORING
14D	DEMO ALL BATHROOM PARTITIONS
15D	DEMO 24"x24" MAINTENANCE ACCESS PANEL
16D	DEMO EXISTING PLASTER CEILING, ELECTRICAL LIGHTS, SURFACE MOUNTED OUTLET, EXHAUST, EXISTING FIRE DEVICES TO BE INSTALLED
	BACK.

WOMEN'S RESTROOM, 111
148.27 SQFT

13D 4 12 16
10 11 14D 6D
15 3D 11D
16D 18 19

RELOCATE LOCATION OF SINK FOR
ADA FLOOR, KNEE, TOE SPACE
CLEARANCE REQUIREMENTS

