

FUTURE

PIPE NECK SIZE
SIZES SHALL

RELATION
SHIP (UNLESS
CONTRACTOR.

WALLS AND

ACCESS
INSTALLATION.

STRUCTURE

THIS SHALL BE

PIPE, ETC.,

RELATION
SHIP, WITH

HEATING
SYSTEMS. ALL
LIVES AT

UNDERSIDE
RED IN

FLANGES

JJ.- PROVIDE ACCESS DOORS IN DUCTWORK FOR ACCESS TO ALL SMOKE DETECTORS, FIRE DAMPERS, SMOKE DAMPERS, VOLUME DAMPERS, COILS AND OTHER ITEMS LOCATED IN THE DUCTWORK WHICH REQUIRE SERVICE AND/OR INSPECTION.

KK.- SMOKE DETECTORS SHALL BE FURNISHED AND WIRED BY THIS CONTRACTOR. THIS CONTRACTOR SHALL BE RESPONSIBLE FOR MOUNTING THE SMOKE DETECTOR IN THE DUCTWORK AS SHOWN ON THE DRAWINGS AND IN ACCORDANCE WITH MANUFACTURER'S PRINTED INSTRUCTIONS.

LL.- CONTRACTOR TO PROVIDE FIRE STOPPING AT ALL RATED HORIZONTAL AND VERTICAL ASSEMBLIES. CONTRACTOR SHALL NOT LEAVE OPENINGS UNPROTECTED DURING THE CONSTRUCTION PERIOD EXCEPT FOR SHORT DURATIONS WHILE ITEMS ARE BEING INSTALLED THROUGH OPENINGS

MM.-SMOKE DETECTORS SHALL BE LISTED FOR USE IN AIR DISTRIBUTION SYSTEMS AND IN ACCORDANCE WITH UL 268A.

NN.-FIRE DAMPERS SHALL BE LISTED IN ACCORDANCE WITH UL 555 AND HAVE A MINIMUM OF 1-1/2 HR. FIRE RATING. FUSIBLE LINKS FOR FIRE DAMPERS SHALL NOT BE RATED FOR TEMPERATURES LESS THAN 160 DEG. F.

OO.-FUSIBLE LINKS FOR FIRE DAMPERS SHALL BE NOT RATED FOR TEMPERATURES LESS THAN 160 DEG. F.

PP.-FIRE DAMPERS SHALL BE INSTALLED, INSPECTED, AND TESTED IN ACCORDANCE WITH CHAPTER 19 OF NFPA 80.

QQ.-FIRE DAMPERS WITH FUSIBLE LINKS, INTERNAL OPERATORS, OR BOTH SHALL BE PROVIDED WITH AN ACCESS DOOR THAT IS NOT LESS THAN 12" SQUARE.

RR.-FIRE DAMPERS SHALL BE LABELED WITH THE WORDS "FIRE DAMPER" IN LETTERS NOT LESS THAN 1" IN HEIGHT.

1

1 DEL Bulletin #1
RFI Date: 03-15-13



DATE: 03-15-13
PROJECT NO.: 120050
DWN BY: SWH

MODERNIZE HVAC B115
DAYTON VAMC
BUILDING 115

Dynamix
Engineering Ltd.
Facility Engineering Consultants
COPYRIGHT
DYNAMIX ENGINEERING LTD. ALL RIGHTS RESERVED

REVISES SHEET
M00

SK1-M00