

---

For the purposes of this inspection lead-based paint is defined as greater than or equal to 1.0 mg/cm<sup>2</sup>. The NITON XL instrument (model XLp-303A) used in this survey have published threshold values of 1.0 mg/cm<sup>2</sup> on all substrates and do not require substrate correction. Paint chip confirmation of inconclusive samples was not necessary since no inconclusive surfaces were identified during sampling with this X-ray Fluorescence Analyzer. Lastly, this report detailing the findings of the inspection report was written to document the inspection and provide a permanent record of the evaluation.

## **Qualifications**

The inspection was conducted by Robin H. Liebal, Licensed Lead Inspector #3355-000213. The inspection was conducted in accordance with applicable Local, State, and Federal regulations.

## **Methodologies**

This inspection was conducted in accordance with accepted industry standards and applicable regulations established by OSHA and the EPA. This inspection only identifies lead-based paint that is accessible through non-destructive methods. It does not identify lead-based paint materials located within walls, concrete decks, subfloors, or other generally inaccessible areas.

## **Disclaimer**

This inspection report is written for and intended for the use of the Owner and its representatives only. HDHT is not responsible nor will be held liable for any interpretation made, opinions formed, or conclusions drawn by any third party as a result of examining the lab results, inspection results or this report. Any interpretations, opinions, and conclusions will be those made, formed, and drawn solely by that third party.

A lead inspector/risk assessor properly trained by a training institution utilizing an approved HUD curriculum and subsequently licensed to perform inspections by the Commonwealth of Virginia performed the inspection of this structure. HDHT accepts no liability nor makes any claims regarding lead based painted surfaces which were not tested and lead -based painted surfaces which were not accessible during the inspection process if such material was located behind or within walls, concrete decks, sub-floors, chases, or was otherwise generally inaccessible without destructive sampling.