



1. EXISTING 3" ROOF DRAIN.
2. REMOVE EXISTING ROOF INSULATION, ROOFING, ETC. COMPLETELY FOR NEW BUILDING ADDITION. PROTECT EXISTING ROOF SLAB STRUCTURE AND OTHER ELEMENTS TO REMAIN DURING CONSTRUCTION. REFER TO THE STRUCTURAL DRAWINGS FOR ADDITIONAL DETAIL INFORMATION.
3. REMOVE EXISTING PARAPET WALL COMPLETELY. PROTECT EXISTING ELEMENTS TO REMAIN DURING DESTRUCTION.
4. EXISTING EXHAUST FANS TO BE RELOCATED.
5. MODIFIED BITUMEN ROOFING ON INSULATING LIGHT WEIGHT CONCRETE ROOF. REFER TO STRUCTURAL DRAWINGS AND SPECIFICATIONS.
6. NEW CAST STONE COPING TO MATCH EXISTING COPING TOP OF NEW PARAPET WALL IS TO MATCH TOP OF EXISTING PARAPET WALL.
7. CRICKET
8. REMOVE A PORTION OF PARAPET WALL TO RECEIVE NEW SOUPPER. REFER TO STRUCTURAL DRAWINGS FOR NEW Lintel.
9. SOUPPER PROVIDE FLASHING AND COUNTER FLASHING. PREPARE SURFACES AS REQUIRED FOR EXPANSION JOINT AT NEW ADDITION. REFER TO DETAIL 03.
10. NEW EXPANSION JOINT. REFER TO DETAIL 05.
11. RELOCATED EXHAUST FAN. REFER TO MEP DRAWINGS.
12. JOINT SEALANT BETWEEN CAST STONE AND EXISTING MASONRY WALL.
13. EXISTING LIGHTING PROTECTION TO REMAIN. PROTECT DURING CONSTRUCTION.
14. EXTERIOR SERVICE/MAINTENANCE STAIRS SECURED TO ADJACENT WALL AND ROOF BELOW.
15. PROVIDE NEW ROOF MAINTENANCE WALK PAD FROM LADDER TO AND AROUND NEW AHU. CONFIRM EXACT LOCATION WITH COR.

[illegible]

The Estopinal Group
Architecture Engineering Interior

lan Street, Suite 507 tel. 313
ort, LA 71101 fax 313



TNF A VETERAN
OWNED COMPANY

3 EXECUTIVE COURT, UNIT 4
SOUTH BARRINGTON, IL 60010

Dwg. 23 of 112

 Department of
Veterans Affairs