



1. ALL NEW HORIZONTAL COLD WATER AND HOT WATER PIPING SANITARY PIPING SHOWN IN THIS PLAN ARE ROUTED IN FIRST FLOOR CEILING UNLESS NOTED OTHERWISE.
2. REFER TO SHEET P3.1 AND P3.2 FOR PLUMBING FIXTURE ROUTING IN SUITE.

PLUMBING KEY NOTES

1. 2" SAN DOWN TO BASEMENT CEILING.
2. 4" SAN DOWN TO BASEMENT CEILING.
3. RECONNECT 4" SAN BACK TO EXISTING 4" SAN ABOVE BASEMENT CEILING. CONTRACTOR TO FIELD VERIFY LOCATION OF EXISTING 4" SAN PIPING IN FIELD BEFORE RECONNECTION TO NEW.
4. EXTEND MEDICAL GAS INTO ROOMS AND DROP 1/2" OXYGEN, 1/2" AIR AND 3/4" VACUUM DOWN TO HEAD WALL PANELS. REFER TO HEAD WALL PANEL DETAILS IN ARCHITECTURAL SHEETS FOR MORE INFORMATION.
5. NEW MEDICAL GAS ZONE CONTROL VALVES AND ALARM PANEL.
6. EXTEND NEW MEDICAL GAS PIPING AND CONNECT TO EXISTING MEDICAL GAS PIPING IN LAUNDRY CLOSET AND SIZES IN FIELD.
7. EXTEND AND CONNECT NEW 3/4" OXYGEN LINE AND CONNECT TO EXISTING OXYGEN RISER LOCATED IN THE LAUNDRY CHUTE. CONTRACTOR TO VERIFY SIZE AND LOCATION BEFORE CONNECTING TO NEW.

- ① 2" SAN DOWN TO BASEMENT CEILING.
- ② 4" SAN DOWN TO BASEMENT CEILING.
- ③ RECONNECT 4" SAN BACK TO EXISTING 4" SAN ABOVE BASEMENT CEILING. CONTRACTOR TO FIELD VERIFY LOCATION OF EXISTING 4" SAN PIPING IN FIELD BEFORE RECONNECTION TO NEW.
- ④ EXTEND MEDICAL GAS INTO ROOMS AND DROP 1/2" OXYGEN, 1/2" AIR AND 3/4" VACUUM DOWN TO HEAD WALL PANELS. REFER TO HEAD WALL PANEL DETAILS IN ARCHITECTURAL SHEETS FOR MORE INFORMATION.
- ⑤ NEW MEDICAL GAS ZONE CONTROL VALVES AND ALARM PANEL.
- ⑥ EXTEND NEW MEDICAL GAS PIPING AND CONNECT TO EXISTING MEDICAL GAS PIPING. VERIFY LOCATION AND SIZES IN FIELD.
- ⑦ EXTEND AND CONNECT NEW 3/4" OXYGEN LINE AND CONNECT TO EXISTING OXYGEN RISER LOCATED IN THE LAUNDRY CHUTE. CONTRACTOR TO VERIFY SIZE AND LOCATION BEFORE RECONNECTING TO NEW.

ROOM NAME SCHEDULE	
ROOM NUMBER	ROOM NAME
1N2	TELEPHONE SWITCHROOM
1N3	TLT-PUB
1N4	TLT-PUB
1N5	STORAGE
1N6	WAITING
1N7	REGISTRATION
1N8	LIFE SUPPORT
1N9	LIFE SUPPORT
1N10	CAST LIFE SUPPLY-4
1N11	LIFE SUPPORT 5
1N11A	TLT-PT
1N12	LIFE SUPPORT-4
1N13	LIFE SUPPORT-3
1N14	LIFE SUPPORT-2
1N15	LIFE SUPPORT-1
1N16	CLEAN SUPPLY
1N17	LIFE SUPPORT-9
1N18	LIFE SUPPORT-10
1N19	NURS STATION
1N20	MEDS
1N21	TRIAGE-1
1N22	TRIAGE-2
1N24	FAST TRACK
1N23	SOILED UTILITY
1N24A	ELEC.
1N24B	TLT-MALE
1N24C	TLT-FEMALE
1N24D	WORK
1N24E	BREAK
1N25	HISKP.
1W26D	POLICE
1W27A	OFFICE/STORAGE
1W27B	STORAGE
1W27C	NURSE MANAGER
1W27D	MEDICAL DIRECTO
1N100	CORRIDOR
1N100A	VESTIBULE
1N200	CORRIDOR

Scale: AS NOTED

		CONSULTANTS:  The Estopinal Group <small>Architectural Engineering Interiors</small> 820 Jordan Street, Suite 507 tel. 318.424.3700 Shreveport, LA 71101 fax 318.424.3764				PROJECT MANAGERS AND ENGINEERS:  A VETERAN OWNED COMPANY 3 EXECUTIVE COURT, UNIT 4 SOUTH BARRINGTON, L. 60010		Drawing Title FIRST FLOOR-NORTH WATER DISTRIBUTION PLUMBING PLAN Approved Project Director		Project Title RENOVATE ED + PRIMARY CARE Building Number 1N, 1E Location SHREVEPORT VAMC 510 EAST STONER AVE Date 01/09/13		Project Number 667-10-100 Drawing Number P1.N2 Dwg. 78 of 112 Checked RM Drawn SL		Office of Construction and Facilities Management  Department of Veterans Affairs	
--	--	---	--	---	--	---	--	---	--	--	--	---	--	--	--