

GENERAL NOTES

1. CONTRACTOR TO INSTALL NURSE CALL SYSTEM AND MAKE OPERATIONAL. TIE NEW DEVICES INTO EXISTING HOSPITAL SYSTEM. MATCH NEW DEVICES WITH EXISTING DEVICES.

KEY NOTES

1. PROVIDE JUNCTION BOX FOR NEW NURSE CALL CORRIDOR LIGHT ABOVE DOOR TO LIFE SUPPORT ROOM. MOUNT AT 4" ABOVE DOOR FRAME FOR WALL MOUNTED APPLICATIONS. CEILING MOUNT MAY BE REQUIRED. CONNECT TO EXISTING NURSE CALL SYSTEM.
2. PROVIDE JUNCTION BOX FOR NEW NURSE CALL MONITORING STATION. VERIFY ELECTRICAL CONNECTION WITH NURSE CALL VENDOR.
3. PROVIDE NEW EMERGENCY CALL STATION AT TOILET IN NEW RESTROOM. MOUNT AT 48" AFF.
4. PROVIDE NEW CODE BLUE STATION IN TRIAGE. MOUNT AT 48" AFF.
5. PROVIDE NEW CARD READER FOR ACCESS INTO THE PATIENT AREA. COORDINATE LOCATION WITH HOSPITAL ENGINEER. REFER TO SHEET E4.1 FOR LOCATION OF HIRSCH SYSTEM CARD READER CONTROL PANEL.
6. PROVIDE NURSE CALL PATIENT STATION AND CODE BLUE STATION AT HEAD OF EXAM BED. MOUNT AT 48" AFF.
7. NEW LOCATION OF EXISTING NURSE CALL CONTROL CABINET. CONTRACTOR TO RELOCATE EXISTING CABINET AND PROVIDE NEW WIRING FROM MAIN SYSTEM TO EXISTING CABINET.
8. EXISTING SECURITY CAMERA TO BE RELOCATED TO THIS LOCATION.
9. CONTRACTOR TO PROVIDE NEW SECURITY CAMERAS. MATCH EXISTING. EXISTING CAMERAS ARE PELCO SARIX FIXED VANDAL MINI DOME, 1M14-V, INDOOR, 1.3 MEGAPIXEL HD DIGITAL CAMERA. TIE NEW CAMERAS INTO EXISTING HOSPITAL CAMERA SYSTEM LOCATED IN 1W5B.


KEYPLAN: FIRST FLOOR



FIRST FLOOR PLAN - EAST

SCALE: 1/8"=1'-0"

Scale: AS NOTED

<div>Revisions</div> <div>Date</div>		<div>CONSULTANTS:</div> <div> The Estopinal Group ARCHITECTURE ENGINEERING INTERIORS 820 Jordan Street, Suite 507 tel. 318.424.3700 Shreveport, LA 71101 fax 318.424.3764</div>		<div>PROJECT MANAGERS AND ENGINEERS:</div> <div> A VETERAN OWNED COMPANY 3 EXECUTIVE COURT, UNIT 4 SOUTH BARRINGTON, IL 60010</div>		<div>Drawing Title</div> <div>FIRST FLOOR - EAST SECURITY/NURSE CALL PLAN</div> <div>Approved Project Director</div>		<div>Project Title</div> <div>RENOVATE ED + PRIMARY CARE</div> <div>Location SHREVEPORT VAMC 510 EAST STONER AVE</div> <div>Date 01/09/13</div> <div>Checked RM</div> <div>Drawn TJH</div>		<div>Project Number</div> <div>667-10-100</div> <div>Building Number</div> <div>1N, 1E</div> <div>Drawing Number</div> <div>E1.E3</div> <div>Dwg. 98 of 112</div>		<div>Office of Construction and Facilities Management</div> <div> Department of Veterans Affairs</div>	
--------------------------------------	--	--	--	--	--	--	--	--	--	---	--	---	--