

FLOOR/WALL SCHEDULE:

- [A] TERRAZZO FRITZ 3000 SERIES OR EQUIVALENT
- [B] SLIP RESISTANCE TILE
- [C] SKIM COAT APPLICATION FOR WALLS
- [CA] ABOVE EPOXY PAINT WALLS OFF-WHITE
COORDINATE WITH COR.
-HIGH BOND STRENGTH AND SMOOTH FINISH
- [D] EPOXY APPLICATION (INDUSTRIAL GRADE)
-TWO COMPONENT RESIN RICH EPOXY SYSTEM
- [E] EPOXY WALL APPLICATION
-SUBMIT FOR GOVT. APPROVAL SIMILAR TO FLOOR APPLICATION
- [F] STEEL/METAL PROTECTION SYSTEM
-POLYAMINE EPOXY (BASE)
-POURABLE POLYAMINE EPOXY (TOP)
- [G] BOILERS TO BE PAINTED SAFETY BLUE
-PAINT SYSTEM SUBMITTED TO GOVT FOR APPROVAL THAT MEET REQUIREMENTS FOR BOILER PAINT APPLICATION AS PER VA DESIGN REQUIREMENTS.
- [H] VA EMBLEM TO BE INSTALLED WITH LETTERING AS NOTED.
- [I] NEW STEEL LOCKERS 12" X 18" X 12' COLOR TO BLUE AND WHITE
CONTRACTOR TO SUBMIT GOVT. APPROVAL.



ALL PAINT SYSTEM TO BE SUBMITTED FOR APPROVAL AND TO BE APPLIED AS PER RECOMMENDATIONS OF THE MANUFACTURER.
USE A POLYMER TYPE CEMENT FOR ANY CONCRETE FLOOR REPAIRS PRIOR TO ANY EPOXY APPLICATION.
FOR FLOOR PREPARATIONS SHALL BE SANDED AND/OR SCARIFIED WITH INDUSTRIAL EQUIPMENT TO OPEN PORES OF THE FLOOR, BUT DOES NOT PROFILE IT. ONCE FLOOR SANDED AND/OR SCARIFIED HOLES AND CRACKS ARE TO BE FILLED WITH A TROWELABLE EPOXY
ALL METAL RAILING AND CATWALKS ARE TO INSPECTED AND ANY REPAIRS REQUIRED SHALL BE PERFORMED (10%) OF EXISTING CATWALK TO BE REPLACED.
COLD GALVANIZATION PAINT SYSTEM IS TO BE APPLIED. CONTRACTOR TO SUBMIT PAINT COLD GALVANIZATION SYSTEM FOR APPROVAL.
ALL RAILING IS TO BE PAINTED SAFETY YELLOW.
ALL BOILERS TO BE PAINTED BLUE AS PER VA DESIGN GUIDE

KEY NOTES:

- ① DRILL THROUGH FLOOR AND INSTALL FLOOR DRAIN
- ② CORE DRILL THROUGH CONCRETE
- ③ INSTALL UNDERGROUND AS PER SPECIFICATIONS
- ④ CONNECT TO EXISTING DRAIN; IF REQUIRED INSTALL NEW AND/OR LARGER DRAIN. SUBMIT TO THE GOVT FOR APPROVAL.
- ⑤ INSTALL SINK
- ⑥ INSTALL CASEWORK
- ⑦ INSTALL REFRIGERATOR (STAINLESS STEEL PROVIDE CONTRACTOR. COORDINATE WITH COR.
- ⑧ INSTALL WALL LOCKERS
- ⑨ NEW FLOOR, WALL, AND CEILING APPLICATION
SEE FLOOR/WALLSCHEDULE
- ⑩ CUT TRENCH IN EXISTING FLOOR TO INSTALL NEW DRAIN FOR SINK
- ⑪ BRICK WORK TO BE RED RANGE WIRE CUT AS PER ASTM C-216 GRADE SW TYPE FBS.
BRICK WORK TO BE INTERLOCKING WITH EXISTING AND MORTAR TO MATCH IN COLOR AND THICKNESS.
COORDINATE WITH COR.
- ⑫ DRILL THROUGH FLOOR/WALL AND CONNECT TO EXISTING PLUMBING FOR SINK INSTALLATION CONNECTION.

REVISION: NEW LOCATION OF CORE DRILL		29 MAR 2013						RECOMMEND APPROVAL				Drawing Title NEW WORK & PAINT SCHEDULE		Project Title BOILER PLANT MODIFICATIONS		Date 15 JAN 13	
								REQUESTER				Date		Building Number BUILDING #15		Checked	
								CHIEF OF SERVICE				Date		CHIEF OF STAFF		Date	
								ASSOC. DIR. PATIENT CARE SVC.				Date		ASSOC. DIR. for OPERATIONS		Date	
								APPROVAL BY:				Date		Approved:Chief of Facilities Management Svr.		Location W.G.(Bill) Hefner Medical Center 1601 Brenner Ave. Salisbury NC 28144	
Revision		Date						MEDICAL CENTER DIRECTOR								DRAWING NO. A-102 DWG. 6 OF 10	



Department of
Veterans Affairs