



**BASEMENT PLAN LEGEND**

(E) FULL HEIGHT STRUCTURAL CONCRETE WALL

(E) METAL STUD WALL WITH SOUND BATT INSULATION, WALL AND FINISHES FULL HEIGHT FROM FINISH FLOOR TO DECK ABOVE.

**BASEMENT FLOOR PLAN - REMODEL KEYNOTES**

1 EXISTING ELEVATOR EQUIPMENT.

2 EXISTING ELEVATOR CONTROL PANEL.

3 EXISTING ELEVATOR DISCONNECT.

4 EXISTING IDU ABOVE (SHOWN DASHED).

5 ELEVATOR EQUIPMENT. (OMIT ELEVATOR EQUIPMENT AT DEDUCTIVE ALTERNATE 1)

6 ELEVATOR CONTROL PANEL. (OMIT ELEVATOR CONTROL PANEL AT DEDUCTIVE ALTERNATE 1)

7 ELEVATOR DISCONNECT. (OMIT ELEVATOR DISCONNECT AT DEDUCTIVE ALTERNATE 1)

8 42" x 42" CLEAR FLOOR SPACE.

9 PROPOSED ROUTE OF ELEVATOR HYDRAULIC LINES. MANUFACTURER TO VERIFY. (OMIT HYDRAULIC LINES AT DEDUCTIVE ALTERNATE NO. 1)

<b>CONSULTANTS:</b>			<b>ARCHITECT/ENGINEERS:</b>		<b>Drawing Title</b> BASEMENT FLOOR PLAN	<b>Project Title</b> BUILDING 24 SEISMIC CORRECTION AND ADDITION	<b>Project Number</b> 570-215	<b>Office of Construction and Facilities Management</b>	
			<b>HMC Architects</b> 1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720 T 559 322 2444 / www.hmcarchitects.com		<b>Approved Project Director</b>	<b>Location</b> VAMC FRESNO, CA	<b>Building Number</b> 24		<b>Drawing Number</b> AS200 Dwg. 45 of 180
<b>Revisions:</b>						<b>Date</b> March 12, 2013	<b>Checked</b> BB	<b>Drawn</b> CLO/JH	
<b>Date</b>									