



BUILDING SECTION - REMODEL KEYNOTES

- 1 REPLACE BELOW-DECK INSULATION WITH NEW R-30 BATT. INSULATION SUPPORTED BY IMPALING PINS, TYPICAL AT THIRD FLOOR ROOFS. REMOVE SPRAY-ON FIREPROOFING AS REQUIRED TO MOUNT IMPALING PINS.
- 2 R-30 BATT. INSULATION, PROVIDE IMPALING PINS AS SPECIFIED. REMOVE SPRAY-ON FIREPROOFING AS REQUIRED TO MOUNT IMPALING PINS.
- 3 CEILING, TYPICAL. REFER TO REFLECTED CEILING PLAN
- 4 CEMENT PLASTER SOFFIT. REFER TO 1ST FLOOR REFLECTED CEILING PLAN
- 5 GYPSUM WALLBOARD & BASE OVER 2" RIGID INSULATION OVER EXISTING INSULATION FROM FLOOR TO DECK TYPICAL ALL EXTERIOR WALLS, ALL 3 FLOORS.
- 6 ALUMINUM WINDOW SYSTEM. REFER TO SCHEDULE. (OMIT WINDOWS AT DEDUCTIVE ALTERNATE 2)
- 7 (E) CEILING TO REMAIN.
- 8 (E) SUNSCREEN TO REMAIN, U.N.O. REMOVE DEBRIS AND CLEAN VIA POWERWASH.
- 9 NOT USED
- 10 (E) SKYLIGHT TO REMAIN.
- 11 SLOPING FLOOR SLAB AND AUDITORIUM SEATING
- 12 NOT USED
- 13 CONCRETE FLOOR