


GENERAL FIRE ALARM SYSTEM NOTES:

- EXISTING BLDG CURRENTLY HAS A MANUAL FIRE ALARM SYSTEM. SCOPE OF FIRE ALARM DEMO INCLUDES DEMOLITION OF EXISTING MANUAL FIRE ALARM PER CURRENT NFPA 101 AND ADA REQUIREMENT.
- EXISTING FIRE ALARM SYSTEM CONSISTS OF A SIMPLEX #4100 ADDRESSABLE FIRE ALARM CONTROL PANEL WITH SIMPLEX ADDRESSABLE INITIATION DEVICES AND NAC DEVICES. ALL NEW DEVICES SHALL BE AS MANUFACTURED BY SIMPLEX, COMPATIBLE WITH THE EXISTING #4100 FIRE ALARM SYSTEM.
- FIRE ALARM SYSTEM SUPPLIER SHALL ASSIST ELECTRICAL CONTRACTOR IN THE DEMO FIRE ALARM WORK AND NEW FIRE ALARM WORK TO ACCOMMODATE PHASING OF THE PROJECT.
- ALL PROGRAMMING AND TESTING AS REQUIRED FOR A COMPLETE OPERABLE MANUAL FIRE ALARM SYSTEM SHALL BE PROVIDED BY THE FIRE ALARM SYSTEM SUPPLIER. CONTRACTOR SHALL PROVIDE NEW SUPPORT PER CODE FOR ALL EXISTING FIRE ALARM CONDUITS THAT REMAIN, IN ATTIC OR SURFACE MOUNTED ON CEILINGS AND WALLS.

SECOND FLOOR FIRE ALARM DEMO NOTES:

- EXISTING FACP TO REMAIN. RELABEL PER FIRE ALARM PLAN.
- EXISTING ADDRESSABLE SMOKE DETECTOR AT EXISTING ELEVATOR LOBBY, PROGRAMMED FOR ELEVATOR RECALL FUNCTION, TO REMAIN.
- REMOVE EXISTING PULL STATION, CONDUIT AND WIRING.
- EXISTING ADDRESSABLE DUCT SMOKE DETECTOR TO REMAIN.
- EXISTING HORN/STROBE TO BE REMOVED OR REPLACED. REMOVE EXISTING DEVICE, CONDUITS AND WIRING. BLANK OFF OUTLET.
- EXISTING FIRE ALARM DEVICES IN AUDITORIUM FIRST FLOOR. REMOVE EXISTING CONDUIT AND WIRING.
- EXISTING FIRE ALARM CONDUIT WITH ONE 1/2" CABLE, 2#12 (2 NAC) + 2#12 (2NAC) FROM EXISTING FIRE ALARM DEVICES IN FIRST FLOOR EQUIPMENT ROOM. REMOVE EXISTING CONDUIT AND WIRING.
- EXISTING FIRE ALARM CONDUIT WITH ONE 1/2" CABLE, 2#12 (NAC) + 2#12 (2NAC) TO EXISTING FACP #2 ON THIRD FLOOR. REMOVE EXISTING CONDUIT AND WIRING.
- EXISTING FIRE ALARM CONDUIT AND WIRING FROM EXISTING FACP #4 IN FIRST FLOOR EQUIPMENT ROOM. PROVIDE NEW SUPPORT PER CODE FOR EXISTING CONDUIT.
- EXISTING FIRE ALARM CONDUIT AND WIRING TO EXISTING FACP #6 ON THIRD FLOOR. REMOVE EXISTING WIRING. PROVIDE NEW SUPPORT PER CODE FOR EXISTING CONDUIT.
- EXISTING FIRE ALARM CONDUIT WITH ONE 1/2" CABLE + 2#12 (2NAC), TO REMAIN.
- REMOVE EXISTING FIRE ALARM CONDUITS AND WIRING.

1 DEMOLITION SECOND FLOOR FIRE ALARM PLAN



CONSULTANTS:

LP Consulting Engineers, Inc.
885 W. Ashlan Ave, Suite 101, Clovis, CA 93612
P 559-425-1248 • F 559-425-1625
www.lpe.com
JDO # 10-1006



ARCHITECT/ENGINEERS:

HMC Architects
1827 E. 8th Avenue, Suite 103, Fresno, CA 93720
T 559 322 2444 | www.hmcarchitects.com

Drawing Title
**DEMOLITION SECOND FLOOR
FIRE ALARM PLAN**

Project Title
**BUILDING 24
SEISMIC CORRECTION
AND ADDITION**

Approved Project Director

Location
VAMC FRESNO, CA

Date
March 12, 2018

PK

PK/L/S

Project Number
570-215

Building Number
24

Drawing Number
ED203

Dwg. 1st of 180

Office of Construction and Facilities Management
Department of Veterans Affairs