



THIRD FLOOR LIGHTING DEMO NOTES:

- 1 REMOVE EXISTING LIGHTS AND RELATED CONDUITS AND WIRING IN ROOM. VERIFY WORK REQUIRED IN FIELD.
- 2 REMOVE EXISTING PARAFET MOUNTED EXTERIOR LIGHTS AND RELATED CONDUITS AND WIRING. RETURN LIGHTS TO OWNER.
- 3 EXISTING LIGHT TO BE REPLACED. REMOVE EXISTING LIGHT AND RELATED CONDUITS AND WIRING.
- 4 EXISTING SWITCHES TO BE REPLACED. REMOVE EXISTING SWITCHES AND WIRING.
- 5 REMOVE EXISTING SWITCHES AND RELATED OUTLETS, CONDUITS AND WIRING.
- 6 TYPICAL: EXISTING EXIT SIGNS CONNECTED TO EXISTING 120V EAC PANEL. "E" VIA 120V/277V TRANSFORMER. REMOVE EXISTING SIGNS, CONDUITS AND WIRING.
- 7 EXISTING LIGHTS CONNECTED TO EXISTING 120V EAC PANEL. "E" VIA 120V/277V TRANSFORMER. REMOVE EXISTING LIGHTS, CONDUITS AND WIRING.
- 8 EXISTING EMERGENCY LIGHTING CIRCUIT TO EXISTING 120V EAC PANEL. "E" VIA 120V/277V TRANSFORMER. EXISTING TRANSFORMER AND HOMERUN TO PANEL. "E" TO REMAIN.
- 9 REMOVE EXISTING CEILING MOUNTED PUBLIC ADDRESS SPEAKER AND RELATED BACKBOX, CONDUITS AND CABLEING.
- 10 VERIFY EXISTING LIGHTING HOMERUN IN FIELD. REMOVE EXISTING CONDUITS AND WIRING.
- 11 EXISTING STAR LIGHTS CONNECTED ON EXISTING 120V EAC PANEL. "E" TO REMAIN.
- 12 EXISTING LOW VOLTAGE IS TO BE REMOVED. REMOVE EXISTING LIGHT AND RELATED CONDUITS AND WIRING.

CONSULTANTS:		ARCHITECT/ENGINEERS:	
 LP Consulting Engineers, Inc. 895 W. Ashland Ave., Suite 101, Chico, CA 95922 P: 530-425-1243, F: 530-425-1025 www.lpe.com JDE # 10-1006		 HMC Architects 1827 E. 97th Avenue, Suite 103, Fresno, CA 93720 T: 559-322-2444 / www.hmcarchitects.com	
Project Title DEMOLITION THIRD FLOOR LIGHTING PLAN		Project Title BUILDING 24 SEISMIC CORRECTION AND ADDITION	
Approved Project Director Date: March 12, 2018 PK		Location VAMC FRESNO, CA	
Drawing Number ED301		Building Number 24	
Office of Construction and Facilities Management Department of Veterans Affairs			