



DEMOLITION THIRD FLOOR FIRE ALARM PLAN

- GENERAL FIRE ALARM SYSTEM NOTES:**

 - EXISTING BLDG CURRENTLY HAS A MANUAL FIRE ALARM SYSTEM. SCOPE OF FIRE ALARM WORK IS TO EXTEND THE EXISTING MANUAL FIRE ALARM PER CURRENT NFPA 101 AND ADA REQUIREMENT.
 - EXISTING FIRE ALARM SYSTEM CONSISTS OF A SIMPLEX #4100 ADDRESSABLE FIRE ALARM CONTROL PANEL WITH SIMPLEX ADDRESSABLE INITIATION DEVICES AND MANUAL ALARM DEVICES. THE EXISTING #4100 FIRE ALARM SYSTEM, COMPATIBLE WITH THE EXISTING #4100 FIRE ALARM SYSTEM.
 - FIRE ALARM SYSTEM SUPPLIER SHALL ASSIST ELECTRICAL CONTRACTOR IN THE PROJECT.
 - ALL PROGRAMMING AND TESTING AS REQUIRED FOR A COMPLETE OPERABLE MANUAL FIRE ALARM SYSTEM SHALL BE DONE BY EXISTING FIRE ALARM SYSTEM SUPPLIER AND ALL COST SHALL BE INCLUDED IN THE CONTRACT.
 - CONTRACTOR SHALL PROVIDE NEW SUPPORT PER CODE FOR ALL EXISTING FIRE ALARM CONDUITS THAT REMAIN IN ATTIC OR SURFACE MOUNTED ON CEILING AND WALLS.
- THIRD FLOOR FIRE ALARM DEMO NOTES:**

 - EXISTING FACP TO REMAIN. RELABEL PER FIRE ALARM PLAN.
 - EXISTING ADDRESSABLE SMOKE DETECTOR AT EXISTING ELEVATOR LOBBY, PROGRAMMED FOR ELEVATOR RECALL FUNCTION, TO REMAIN.
 - REMOVE EXISTING MANUAL PULL STATION, OUTLET, CONDUIT AND WIRING. EXISTING HORN/STROBE TO BE REMOVED OR REPLACED. REMOVE EXISTING DEVICE, CONDUITS AND WIRING, BLANK OFF OUTLET.
 - REMOVE EXISTING FACP #1 ON SECOND FLOOR. REMOVE EXISTING CONDUIT AND WIRING.
 - EXISTING FIRE ALARM CONDUIT AND WIRING FROM EXISTING FACP #4 TO FACP ON SECOND FLOOR. REMOVE EXISTING WIRING. PROVIDE NEW SUPPORT PER CODE FOR EXISTING CONDUIT.
 - EXISTING FIRE ALARM CONDUIT AND WIRING TO EXISTING FIRE ALARM DEVICES IN PENHOUSE MECHANICAL ROOM. REMOVE EXISTING CONDUIT AND WIRING.
 - REMOVE EXISTING SMOKE DETECTOR FOR FIRE CURTAIN CONTROL. VERIFY LOCATION AND WORK REQUIRED IN FIELD.

CONSULTANTS:		ARCHITECT/ENGINEERS:	
<div><div><div>REGISTERED PROFESSIONAL ENGINEER E. 10411 ELECTRICAL 0630-14 KINDRED</div><div>895 W. Ashland Ave., Suite 101 Chico, CA 95926 p 530.424.2424 • f 530.424.1625 www.lpe-engineers.com JDE # 10-1008</div></div><div><div>LP Engineers, Inc.</div></div></div>		<div><div><div>REGISTERED ARCHITECT W. C. 24697 STATE OF CALIFORNIA</div><div>1827 E. 8th Avenue, Suite 103 Fresno, CA 93720 T 559.322.2444 / www.hmcarchitects.com</div></div><div><div>HMC Architects</div></div></div>	
Drawing Title DEMOLITION THIRD FLOOR FIRE ALARM PLAN		Project Title BUILDING 24 SEISMIC CORRECTION AND ADDITION	
Approved Project Director		Location VAMC FRESNO, CA	
Date March 12, 2018		Checked PK	
Date		Drawn PK/LJS	
Project Number 570-215		Building Number 24	
Drawing Number ED303		Dwg. 164 of 160	
Office of Construction and Facilities Management		Department of Veterans Affairs	