



- SECOND FLOOR ELECTRICAL PLAN NOTES:**
- EXISTING ELECTRICAL TO REMAIN.
  - PROVIDE NEW GFI RECEPTACLE FOR NEW ELECTRIC DRINKING FOUNTAIN. VERIFY FOUNTAIN IS PROPERLY GROUNDED. PROVIDE NEW CONDUITS AND WIRING AS REQUIRED TO CONNECT NEW AND EXISTING CIRCUIT.
  - RUN NEW HOMERUN TO EXISTING PANEL, #P2A. PROVIDE NEW 20A/1P BREAKER IN EXISTING SPACE, WITH NEW LABEL.
  - RECONNECT EXISTING WORK STATION TO EXISTING POWER AND TEL/DATA WIRING AS REQUIRED. PROVIDE NEW CONDUITS AND WIRING AS REQUIRED.
  - RECONNECT EXISTING OUTLET AND SERVICES IN NEW WALL. PROVIDE NEW CONDUITS AND WIRING AS REQUIRED.
  - PROVIDE NEW OUTLET IN NEW WALL. RUN NEW CONDUITS AND WIRING TO CONNECT TO EXISTING BRANCH CIRCUIT.
  - PROVIDE NEW TEL/DATA OUTLET IN WALL WITH JACKS. RUN ONE 1-1/4" INTO EXISTING SPACE. PROVIDE NEW CONDUITS TO EXISTING 1P AND ONE TEL CABLE TO EXISTING TEL BACKBOARD.
  - PROVIDE NEW HOMERUN TO EXISTING PANEL. CONNECT TO EXISTING RECEPTACLE CIRCUIT.
  - PREPARE NEW OUTLET IN EXISTING WALL. RUN NEW CONDUITS AND WIRING TO CONNECT TO EXISTING BRANCH CIRCUIT.
  - RUN NEW CONDUITS AND WIRING TO CONNECT EXISTING AND NEW RECEPTACLES. REFER TO ELECTRICAL DEMO PLANS FOR DEMO AND NEW WORK ON EXISTING OUTLETS IN ROOMS.
  - PROVIDE POWER AND CONTROL CONNECTION FOR MOTORIZED LOUVERS, AS DIRECTED BY SUPPLIER.
  - 3/4" - #12 + #12 GROUND TO EXISTING PANEL, #P2A. PROVIDE TWO NEW 20A/1P BREAKERS IN EXISTING SPACE, WITH NEW LABEL.
  - PROVIDE GFI RECEPTACLE IN NEW WALL. RUN NEW WIRING TO CONNECT TO EXISTING RECEPTACLE CIRCUIT.

<b>CONSULTANTS:</b>		<b>ARCHITECT/ENGINEERS:</b>	
 LP Consulting Engineers, Inc. 885 W. Ashland Ave., Suite 101, Chico, CA 95912 P 530-425-1243, F 530-425-1025 www.lpe.com JDE # 10-1008		 HMC Architects 1827 E. 17th Avenue, Suite 103, Fresno, CA 93720 T 559-322-2444 / www.hmcarchitects.com	
<b>Project Title</b> SECOND FLOOR ELECTRICAL PLAN		<b>Project Title</b> BUILDING 24 SEISMIC CORRECTION AND ADDITION	
<b>Approved Project Director</b>		<b>Location</b> VAMC FRESNO, CA	
<b>Date</b> March 12, 2018		<b>Checked</b> PK	
<b>Drawn</b> PK/L/S		<b>Dwg. Title</b> ES202	
<b>Dwg. No.</b> 172 of 180		<b>Office of Construction and Facilities Management</b>	