



**Building 5 - Specific Survey Findings**  
**Project No. VAMC:10013.00-IN**

1511 Route 22, Suite C24, Brewster, NY 10509  
 Phone: 845.278.7710 Fax: 845.278.7750

**Project:** **Building No. 5**  
 VA Medical Center  
 Wilkes-Barre, PA

**Inspector(s):** James Reber  
 Thomas Ferro  
**Date(s):** 2/2010-3/2010

**NOTES:** Building #5 Apartment B has been completely abated during a renovation project; Apartment A has not changed and all materials previously noted still remain.

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
<b>Apartment B, 1<sup>st</sup> floor, living room</b>						
Floor	Rug over plywood	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock/ joints	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	12' x12" ceiling tile (white w/crater-like worm markings)	N/A	Good	5-151	N/A	None detected
<b>Apartment B, 1<sup>st</sup> floor, kitchen</b>						
Floor	12" X 12" floor tile (off-white brick design)	236 ft <sup>2</sup>	N/A	5-123	N/A	None detected
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	12: X 12" ceiling tile (off-white, worm markings)	N/A	N/A	5-152	N/A	None detected
Comment: Inspector was unable to collect a sample of the floor tile mastic in this area.						
<b>Apartment B, attic</b>						
Attic	Insulation (perlite fill)	N/A	N/A	5-154	N/A	None detected
<b>Apartment B, 2<sup>nd</sup> floor, all areas</b>						
Floor	Rug over wood	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	5-156	N/A	None detected
Ceilings	12" X 12" ceiling tile (white w/pock markings)	N/A	N/A	5-155	N/A	None detected

**VA Medical Center, Building No. 5**

Adelaide Environmental Health Services, Inc. – Project No. VAMC:10013.00-IN



<b>Apartment B, 1<sup>st</sup> floor bathroom</b>						
Floor-Removed	Linoleum (green)-Removed	N/A	N/A	19	N/A	<b>5% Chrysotile</b>
Walls	Plaster	N/A	N/A	012-B 013-F	N/A	None detected in either sample

**NOTE:** No suspect asbestos-containing materials were observed within the basement crawlspace area.

<b>Apartment A, veranda</b>						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock /brick	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	12' X 12" ceiling tile	N/A	N/A	N/A	N/A	Non-
<b>Apartment A, living/dining room</b>						
Floor	Rug over wood	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
<b>Apartment A, kitchen/laundry area</b>						
Floor	Linoleum (yellow/ white/ tan – pebbles)	150 ft <sup>2</sup>	N/A	5A-01	N/A	<b>15% Chrysotile</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect



**Building 5 - Specific Survey Findings**  
**Project No. VAMC:10013.00-IN**

<b>Apartment A, 2<sup>nd</sup> floor – all areas</b>						
Floor	Rug over wood	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster (sampled in SE bedroom and 2 <sup>nd</sup> floor bathroom -2005)	N/A	N/A	02, 07 (base) 03, 08 (finish)	N/A	None detected in either sample
Ceilings	Plaster (sampled in NE bedroom – 2005)	N/A	V	04 (base) 05 (finish)	N/A	None detected in either sample
<b>Apartment A, front entrance vestibule</b>						
Floor	Rug over wood	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	15	N/A	None detected
	Glue pucks	N/A	N/A	16	N/A	None detected
	Perlite insulation above ceiling/ in attic	N/A	N/A	N/A	5-153	None detected