



DEMOLITION KEYED NOTES:

- A REMOVE WALL, BASE, AND ALL RELATED ITEMS
- B REMOVE DOOR, FRAME, AND ALL RELATED ITEMS
- C REMOVE DOOR, FRAME, AND ALL RELATED ITEMS - INFILL WALL TO MATCH EXIST. CONSTRUCTION
- D REMOVE GYM WALL, PARTITION, FURNING, AND ALL RELATED ITEMS FROM FINISH FLOOR TO DECK ABOVE
- E REMOVE COUNTERTOPS, CABINETS, AND ALL RELATED ITEMS
- F REMOVE SINK, ACCESSORIES AND ALL RELATED ITEMS - CAP AND/OR RELOCATED PLUMB AS REQ'D - SEE MED101 FOR ADDITIONAL INFORMATION
- G REMOVE FLOORING, BASE, AND WALL FINISH AND PREPARE SURFACE AS REQUIRED FOR INSTALLATION OF NEW SCHEDULED FINISHES - SEE MED101 FOR ADDITIONAL INFORMATION FOR FURTHER INFORMATION ON REMOVING FLOORING
- H REMOVE WINDOW SILL AND CLEAN EXISTING WINDOW.
- I REMOVE MEDICAL GAS OUTLETS-CAP AND REPAIR WALL AS REQUIRED. - SEE MED101 FOR ADDITIONAL INFORMATION
- J REMOVE ALL CEILING TILE
- K REMOVE ALL CEILING SUSPENSION GRID AND ALL RELATED ITEMS.
- L REMOVE ALL LIGHT FIXTURES-REUSE WIRING AS REQUIRED - SEE MED101 FOR ADDITIONAL INFORMATION
- M REMOVE ALL HANG SUPPLY AND RETURN DIFFUSERS-REUSE INFORMATION - SEE MED101 FOR ADDITIONAL INFORMATION
- N REMOVE GYPSUM BOARD CEILING
- O REMOVE WALL SLOT AND CHUTE FROM F.F. TO DECK ABOVE - REPAIR WALL SLOT AND RETURN TO OWNER - PATCH FLOOR AS REQUIRED
- P REMOVE GRP, BD, AND FURNING AROUND COLUMNS

DEMOLITION GENERAL NOTES:

1. MECHANICAL, ELECTRICAL, AND PLUMBING CONTRACTORS ARE TO DISCONNECT AND/OR CAP ITEMS WHICH ARE CONCEALED WITHIN ALL AREAS WHERE DEMOLITION WORK OCCURS.
2. PATCH AND REPAIR ANY DAMAGED FLOOR AND WALL AREAS AS REQUIRED-PREPARE FOR NEW SCHEDULED FINISHES.
3. REVISE SPRINKLER HEADS AS REQUIRED TO COMPLY WITH NFPA 13.

■ HATCH INDICATES EXISTING WALLS TO REMAIN.

F1 1/4"=1'-0" DEMOLITION FLOOR PLAN

F4 1/4"=1'-0" DEMOLITION REFLECTED CEILING PLAN

CONSULTANTS:

Provider	Date

ARCHITECT/ENGINEERS:



3616 Masonic Drive
Alexandria, VA 71301
Ph: 318-445-3151
Fk: 318-445-3988
Em: adg@adgllc.net



Project Title
DEMOLITION FLOOR PLAN, DEMOLITION REFLECTED CEILING PLAN

Approved Project Director

Project Title	WOUND HEALING CENTER OF EXCELLENCE VETERAN AFFAIRS MEDICAL CENTER
Location	ALEXANDRIA
Date	06/02/12
Checked	AVD
Drawn	DH
Project Number	W209-C-107-C464
Sheet Number	7
Drawing Number	A101
	Dwg 2 of 13

