LIGHTING FIXTURE SCHEDULE

MARK	TYPE	MOUNTING	MANUFACTURER CATALOG NO.	LAMPS QTY & TYPE	DESCRIPTION	ALTERNATE MANUFACTURER
D1F	8" APERTURE FLUORESCENT DOWNLIGHT	CEILING RECESSED	CAPRI CM8F226/32/42U H65SL	(2) CFQ26W/G24q	LOW IRIDESCENT CLEAR REFLECTOR; ELECTRONIC BALLAST SELF-FLANGED	PRESCOLITE: LF8CFH226 EB6CFHWTB24 GOTHAM: AF226DTT8AR MVOLTTRW COOPER: PD8H226E6HC
D1L	8" APERTURE FLUORESCENT DOWNLIGHT	CEILING RECESSED	CAPRI CM8F126/32/42U HW65SL	(1) CFQ26W/G24q	LOW IRIDESCENT CLEAR REFLECTOR; ELECTRONIC BALLAST SELF-FLANGED	PRESCOLITE: LF8CFH126 EB6CFHWTB24 GOTHAM: AF126DTT8AR MVOLTTRW COOPER: PD8H126E6HC
D1W	"WALL WASHER" 8" APERTURE FLUORESCENT DOWNLIGHT	CEILING RECESSED	CAPRI CM8F126/32/42U HW65SL	(1) CFQ26W/G24q	LOW IRIDESCENT CLEAR REFLECTOR; ELECTRONIC BALLAST SELF-FLANGED	PRESCOLITE: LF8CFH126 EB6CFHWTB24 GOTHAM: AF126DTT8AR MVOLTTRW COOPER: PD8H126E6HC
D2F	8" APERTURE FLUORESCENT DOWNLIGHT	CEILING RECESSED	CAPRI CM8F226/32/42U H85SL	(2) CFM32W/GX24q	LOW IRIDESCENT CLEAR REFLECTOR; ELECTRONIC BALLAST SELF-FLANGED	HUBBELL: LF8CFH232EB WTLP LITHONIA: AF232TRT8AR MVOLTTRW COOPER: C8232E8251LI HB26
P1	PENDENT	CEILING PENDENT	TECH LIGHTING 700THCBOGP HXCF	(1) 26W CFL	VERIFY FINISH WITH ARCHITECT	
X1	EXIT SIGN-DIE CAST SINGLE FACE	CEILING/ WALL	MCPHILBEN ER55L1WR	LED	NICAD BATTERY; FRONT DIFFUSER PLATE ARROWS AS REQUIRED DIE CAST HOUSING	DUALITE: SESRWE LITHONIA: LESW1RELNSD COOPER: CX7170RWSD

ELECTRICAL LEGEND

SYMBOL	DESCRIPTION
———	CONDUIT IN WALL OR ABOVE CEILING
- - - - -	CONDUIT UNDER FLOOR OR UNDERGROUND
	ARROW INDICATES HOMERUN, TICKMARKS: NEUTRAL, PHASE, GROUND
—T—	TELEPHONE CONDUIT
—E—	EMERGENCY CIRCUIT CONDUIT
	TELEPHONE BOARD
	LIGHTING & APPLIANCE PANEL
	POWER PANEL
	SPECIAL PANEL
● ; ◉	JUNCTION BOX; FLUSH FLOOR JUNCTION BOX
F ; F	DISCONNECT SWITCH; FUSED; NONFUSED
▽ ; ▼	TELEPHONE/DATA OUTLET ; ABOVE COUNTER
▼W	WALL MOUNTED TELEPHONE
⊙	FLUSH FLOOR RECEPTACLE
▽	FLUSH FLOOR TELEPHONE/DATA OUTLET
Y	SPECIAL RECEPT; VERIFY TYPE
	2 POLE; 3 WIRE RECEPTACLE
⊕ ; ⊕E ; E	DUPLEX RECEPT; ABOVE COUNTER; EMERGENCY
WP ; GFI	WEATHERPROOF; GROUND FAULT
	QUAD PLEX RECEPTACLE
	FLOOR MOUNTED RECEPTACLE
$; $3 ; $4	SINGLE POLE SWITCH; 3-WAY; 4-WAY
$P ; $D ; $K	PILOT LIGHT; DIMMER; KEYED SWITCH
AFF ; C	ABOVE FINISHED FLOOR; CEILING MOUNTED
	PULL STATION
	FIRE ALARM SYSTEM AUDIO/VISUAL SIGNAL
	FIRE ALARM SYSTEM VISUAL SIGNAL
	SMOKE DETECTOR
	HEAT DETECTOR
D	DUCT MOUNTED SMOKE DETECTOR
D	DOOR HOLDER
	PUSH BUTTON
S	CEILING SPEAKER
	CLOCK
	TV/CTV OUTLET
	MOTOR
S	MOTOR TOGGLE SWITCH
	NURSE CALL TOILET STATION
	NURSE CALL DOME LIGHT
CR	CARD READER JUNCTION BOX



TELEPHONE/DATA/CATV RISER
NO SCALE

three inches = one foot 6 1
one and one half inches = one foot 1 0 6
one inch = one foot 0 6
three quarters inch = one foot 2 0 6
one half inch = one foot 4 0
three eighths inch = one foot 4 0
one quarter inch = one foot 8 4 0
one eighth inch = one foot 16 8 4 0
G:\2222\2222-E201.dwg 8-03-12 12:34:05 PM rthompson

Revisions	Date

VA FORM 08-6231

CONSULTANTS:

P+A
PURTLE + ASSOCIATES CONSULTING ENGINEERS
701 TEXAS STREET
SHREVEPORT, LA 71101

318 425 4500 • fax 318 222 6564
purtle@purtle.net • PA-12222
Louisiana Registered Engineering Firm #F-2354

COPYRIGHT
THESE DOCUMENTS ARE PROTECTED BY UNITED STATES COPYRIGHT LAW. THEY HAVE BEEN PREPARED SPECIFICALLY FOR THE PROJECT IDENTIFIED AND ARE NOT SUITABLE FOR USE ON ANY OTHER PROJECT OR AT ANY OTHER LOCATION WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF PURTLE AND ASSOCIATES, LC. REPRODUCTION OF THESE DOCUMENTS OR ANY PART, PARTS, DETAILS, ETC, MUST BE AUTHORIZED BY PURTLE AND ASSOCIATES, LC. ALL RIGHTS ARE RESERVED TO PURTLE AND ASSOCIATES, LC.

STATE OF LOUISIANA
RICKEY L. WATSON
License No. 30744
PROFESSIONAL ENGINEER
8/9/12
ELECTRICAL ENGINEERING

ARCHITECT/ENGINEERS:

3616 Masonic Drive
Alexandria, LA 71301
Ph: 318.445.3151
Fx: 318.445.3988
Em: adg@adgllc.net

Alliance DESIGN GROUP LLC

Drawing Title
ELECTRICAL SCHEDULES & RISER

Approved: Project Director

Project Title
WOUND HEALING CENTER OF EXCELLENCE
VETERAN AFFAIRS MEDICAL CENTER

Location: ALEXANDRIA LA

Date: 08.03.12 | Checked: TGS | Drawn: RAT

Project Number: VA256-C-1137-C24154
Building Number: 7
Drawing Number: E201
Dwg. of

Office of Construction and Facilities Management
Department of Veterans Affairs