



- HVAC DEMOLITION NOTES:**
- EXISTING TO BE REMOVED
 - EXISTING TO REMAIN
 - (H01) CONTRACTOR SHALL FIELD VERIFY EXACT LOCATION OF ALL EXISTING DUCTWORK, AIR DEVICES, EQUIPMENT, ETC. PRIOR TO START OF WORK.
 - (H02) REMOVE AND DISCARD EXISTING DIFFUSER/GRILLE AND ASSOCIATED DUCT AS INDICATED. CAP AT TRUNK DUCT WHERE SHOWN.
 - (H03) DISCONNECT EXISTING THERMOSTAT AND RETAIN FOR RELOCATION. RE: HVAC PLAN - SHEET M101.
 - (H04) REMOVE EXISTING E/A GRILLE AND ASSOCIATED DUCTWORK AS INDICATED. CAP AT TRUNK DUCT WHERE INDICATED.
 - (H05) EXISTING DUCT-MOUNTED HEATING WATER COIL AND ASSOCIATED PIPING, INLET DUCTWORK AND CONTROLS TO REMAIN. PROTECT DURING DEMOLITION AND NEW CONSTRUCTION.
 - (H06) EXISTING CWS/R AND HWS/R PIPING TO REMAIN. PROTECT DURING DEMOLITION AND NEW CONSTRUCTION.
 - (H07) EXISTING FAN-COIL UNIT AND ASSOCIATED PIPING AND CONTROLS TO REMAIN. WHERE REQUIRED BY NEW CONSTRUCTION, DISCONNECT AND REMOVE EXISTING FAN-COIL UNIT AND ASSOCIATED PIPING, POWER AND CONTROLS. RETAIN EXISTING O/A DUCT AND CWS/R AND HWS/R RUNOUTS FOR RECONNECTION TO NEW FCU. RE: SHEET M101.
 - (H08) REMOVE EXISTING CONDENSATE DRAIN PIPING FROM EXISTING FAN-COIL UNITS. SEE SHEET M101 FOR NEW CONDENSATE DRAIN PIPING ROUTING.
 - (H09) DISCONNECT AND REMOVE EXISTING WALL-MOUNTED HUMIDITY SENSORS AND RETAIN FOR RELOCATION.
 - (H10) DISCONNECT AND REMOVE EXISTING FAN-COIL UNIT AND ASSOCIATED PIPING, POWER AND CONTROLS. RETAIN EXISTING O/A DUCT AND CWS/R AND HWS/R RUNOUTS FOR RECONNECTION TO NEW FCU. RE: SHEET M101.
 - (H11) REMOVE EXISTING CONDENSATE DRAIN PIPING FROM EXISTING FAN-COIL UNITS. SEE SHEET M101 FOR NEW CONDENSATE DRAIN PIPING ROUTING.
- ELECTRICAL DEMOLITION NOTES:**
- EXISTING TO BE REMOVED
 - EXISTING TO REMAIN
 - (E01) PROVIDE ELECTRICAL DEMOLITION ASSOCIATED WITH MECHANICAL DEMOLITION. DISCONNECT AND REMOVE EXISTING ELECTRICAL DEVICES, SPECIAL SYSTEMS, ETC. AND ALL ASSOCIATED CONDUITS AND CONDUCTORS TO SOURCE FOR ALL DEVICES ASSOCIATED WITH DEMOLITION. RETAIN SPECIAL SYSTEM DEVICES AND CIRCUITS FOR RE-USE.
 - (E02) CONTRACTOR SHALL REPAIR/REPLACE ANY FEED THRU BRANCH CIRCUIT WIRING DAMAGED OR INTERRUPTED BY DEMOLITION.
 - (E03) REMOVE EXISTING DEVICES, SPECIAL SYSTEMS, ETC. AND ALL ASSOCIATED CONDUITS AND CONDUCTORS TO SOURCE FOR RE-USE.
 - (E04) DISCONNECT AND REMOVE EXISTING LIGHTING FIXTURES NOTED FOR DEMOLITION. RETAIN BRANCH CIRCUIT FOR RE-USE.
 - (E05) CONTRACTOR SHALL RE-USE EXISTING CONDUITS AS REQUIRED. COORDINATE WITH NEW WORK.
 - (E06) REMOVE ALL SPECIAL SYSTEM DEVICES IN CEILING OF LOBBY AND RE-INSTALL IN NEW CEILING.

CONSULTANTS:		ARCHITECT/ENGINEERS:		Project Title		Project Number		Office of Construction and Facilities Management	
P+A PURPLE + ASSOCIATES CONSULTING ENGINEERS 701 TEXAS STREET SHREVEPORT, LA 71101		Alliance DESIGN GROUP, LLC 3616 Masonic Drive Alexandria, LA 71301 Ph: 318.445.3151 Fx: 318.445.3988 Em: adg@adgllc.net		WOUND HEALING CENTER OF EXCELLENCE VETERAN AFFAIRS MEDICAL CENTER		VA256-C-187-C24154		Office of Construction and Facilities Management	
Revisions		Professional Engineer 8/13/12		Location ALEXANDRIA		Building Number 7		Department of Veterans Affairs	
Date		Checked TCS		Date 08/03/12		Drawing Number MED101		Drawn BAT	
								Dwg of	