

PROVIDE SOLID BARRIER WALLS BETWEEN RENOVATION AREAS AND OCCUPIED AREAS AS REQUIRED.

REMOVE ALL MOVABLE OBJECTS WITHIN SCHEDULED ABATEMENT AREAS PRIOR TO COMMENCEMENT OF ABATEMENT ACTIVITIES.

PROVIDE TEMPORARY HOSE CONNECTIONS, APPROPRIATE DRAIN CONNECTIONS AND ELECTRICAL PANEL FOR ABATEMENT CONTRACTOR. (ENSURE PANEL IS CONNECTED TO EMERGENCY GENERATOR.)


COORDINATE LOCKOUT OF AIR HANDLING UNITS AND EXHAUST FANS WITH THE VA AND MECHANICAL CONTRACTOR PRIOR TO CONDUCTING ABATEMENT ACTIVITIES.

REMOVE AND DISPOSE OF ALL VINYL COMPOSITE TILE, MASTIC AND/OR CARPET AS NOTED ON DRAWINGS AS REGULATED WASTE MATERIAL.

ALL TEMPORARY WATER SERVICE CONNECTIONS MUST BE COORDINATED WITH GENERAL CONTRACTOR AND MET WITH VA APPROVAL.

CONTRACTOR WILL ABATE ALL ACM IN SPECIFIED AREAS IN ACCORDANCE WITH SPECIFICATION SECTIONS 02-82-11AND 02-82-13.19.

- 1 FLOOR TILE MASTIC UNDER CARPET & FLOOR TILE (290 SQUARE FEET)
- 2 CONVECTOR INSULATION (3 EACH)

APPROVED SERVICE LINE DIRECTOR	DATE:	APPROVED INFECTION CONTROL NURSE	DATE:	DRAWING TITLE	PROJECT TITLE	DATE: FEBRUARY 20, 2013	 <b>VAMC</b> SAINT CLOUD MN
				ASBESTOS ABATEMENT PLANS	BUILDING 28 SOUTHWEST STAIR TOWER ADDITION	FILED BY: AS SHOWN	
APPROVED SERVICE LINE DIRECTOR	DATE:	APPROVED PATIENT SAFETY	DATE:			PROJECT NO: 263-13-7-0029	
APPROVED PROJECTS SECTION MANAGER	DATE:	APPROVED CHIEF OF POLICE	DATE:	APPROVED CHIEF OF STAFF	DATE:	CAD FILE ASBESTOS ABATEMENT.DWG	
APPROVED DIRECTOR PHS	DATE:	APPROVED SAFETY MANAGER	DATE:			DRAWING NO: AB1_06-10-13	
					LOCATION: VVA MEDICAL CENTER ST. CLOUD, MN 56301		
					DATE: 28	CHECKED BY: RM	MD

