



- GENERAL NOTES:
1. ALL LEVELS (FLOORS) ARE IDENTIFIED FROM THE EXTERIOR GROUND UNLESS NOTED OTHERWISE.
 2. THE LEVELS REFERENCED MAY INCLUDE UPTO AN ADDITIONAL 6 FT TO THE ROOF.
 3. MORTAR AND BRICK SHOULD MATCH THE EXISTING.
 4. BORAL BRICK MOD 32 RED RANGE WIRECUT SHOULD BE USED TO MATCH THE EXISTING FACE BRICK.
 5. DAMAGED BRICK AND MORTAR SHALL BE REMOVED AND REPLACED.
 6. BRICK TO BE CLEANED AND EXISTING AREAS TO BE CLEAN AROUND WINDOWS
 7. APPROXIMATELY 1,783 LINEAR FEET OF TUCKING + OR - 10% CONTRACTOR TO VERIFY ON SITE
 8. CONTRACTOR TO REPLACE BRICK AS REQUIRED, IF BRICK IS RE-USE IT WILL REQUIRED COR APPROVAL.

REVISION: DEFINED SCOPE	
	24 APR 2013
Revision	Date

RECOMMEND APPROVAL			
REQUESTER	Date		
CHIEF OF SERVICE	Date	CHIEF OF STAFF	Date
ASSOC. DIR. PATIENT CARE SVC.	Date	ASSOC. DIR. for OPERATIONS	Date
APPROVAL BY:			Date
MEDICAL CENTER DIRECTOR			

Drawing Title
TUCK POINTING PLAN FOR BUILDING 2
Approved: Safety Manager/M&O Supervisor
Approved:Chief of Facilities Management Svr.

Project Title
EXTERIOR MASONRY TUCK POINTING
Building Number
Location
W.G.(Bill) Hefner Medical Center 1601 Brenner Ave. Salisbury NC 28144

Date
4/23/2013
Project No.
659-13-211
DRAWING NO.
GS-102
DWG. 3 OF 9

