



CONTRACTOR TO CLEAN EXISTING BRICK TYP.
ON EDGES OF WINDOW SILLS _____

CONTRACTOR TO VERIFY TUCKING UNDER
WINDOW SILLS _____

CONTRACTOR TO VERIFY TUCKING ABOVE LINTEL -

CONTRACTOR TO CLEAN EXISTING BRICK TYP.
ON EDGES OF WINDOW SILLS _____

CONTRACTOR TO VERIFY TUCKING UNDER
WINDOW SILLS _____

Department of
Veterans Affairs

1. ALL LEVELS (FLOORS) ARE IDENTIFIED FROM THE EXTERIOR GROUND UNLESS NOTED OTHERWISE.
2. THE LEVELS REFERENCED MAY INCLUDE UPTO AN ADDITIONAL 6 FT TO THE ROOF.
3. MORTAR AND BRICK SHOULD MATCH THE EXISTING.
4. BORAL BRICK MOD 32 RED RANGE WIRECUT SHOULD BE USED TO MATCH THE EXISTING FACE BRICK.
5. DAMAGED BRICK AND MORTAR SHALL BE REMOVED AND REPLACED.
6. BRICK TO BE CLEANED AND EXISTING AREAS TO BE CLEAN AROUND WINDOWS
7. APPROXIMATELY 1,033 LINEAR FEET OF TUCKING + OR - 10%. CONTRACTOR TO VERIFY ON SITE
8. CONTRACTOR TO REPLACE BRICK AS REQUIRED, IF BRICK IS RE-USE IT WILL REQUIRED COR APPROVAL.