Project No.: 656-13-225 SCIP Replace Hot Water Generators

St. Cloud VA Health Care System Main Campus, St. Cloud, Minnesota


CONTRACTOR PARKING & STAGING PROJECT NOTES:

Contractor Parking - allowed in designated project area. Contractor parking area limited to (2) vehicles at a time. No overnight parking.

Contractor Trailer - (1) construction trailer allowed in designated staging area. Trailer to be lockable. VA not responsible for lost or stolen items. Trailer can only be left here for up to 180 days. Must be moved out by the end of September. Relocate to east contractor parking area when it becomes available, coordinate with project CDR.

Demolition Dumpster - allowed near each building during demolition phase of work. Barrier (snow fence) is required to be erected at each location where dumpster is set. Coordinate with project CDR at each building. Contractor responsible for lawn restoration following removal of dumpster at each building. See General Conditions notes on this page.

VA FORM 08-6231



GENERAL CONDITIONS

All dimensions on drawings are approximate; Drawings are not to be scaled. It is the responsibility of the contractor to verify all field conditions and physical dimensions that influence the construction area.

It is recommended that contractors visit the proposed construction site prior to submitting their bids and they are encouraged to do so.

Contractor shall adhere strictly to State and Federal Occupational Safety and Health Administration (DSHA) Standards.

Contractor shall park only in the designated parking areas and are not to park on the lawn areas; the only exception is to load or unload supplies or equipment.

Contractor is responsible for the safeguarding of their tools and equipment. All tools and equipment are not to be left unattended and are to be secured at all times when the contractor is not present, or the construction site is not supervised by the contractor.

All VA property is to be safeguarded from damage. Any damaged VA property is to be restored to original condition prior to damage or replaced completely. This includes installation, labor, and procurement expenses.

All demolished material becomes the property and the responsibility of the contractor with the exception of specified items designated either in the plans or verbally requested by the COR to be retained by the VA. Offsite disposal of the demolished items, per specified guidelines, is the responsibility of the contractor.

Contractor must control demolition and construction dust from facility by erecting

a dust barrier and ventilation with hepa filters. If venting to outside, the contractor will insure negative air pressure is maintained in encapsulated work area. When transporting debris, wet down sufficiently to prevent dust spreading.

If scaffolding is used, it must be used in accordance with (OSHA) regulations and is to be enclosed for the first eight feet above ground at end of each working day, until dismantled. Ladders must be removed and locked up at the end of each working day to prevent unauthorized persons from having access.

Clean all debris from construction site to the satisfaction of the CDR.

Contractor is responsible for erecting a barrier around work site to prevent patients, staff and visitors from entering construction site. This fence may be a plastic snow fence at open trench areas. All other areas require a metal chain-link fence be erected. Fencing to be 8' high, with top and bottom rail. Provide vehicle/equipment and materials swinging gate (lockable). Provide swinging mandoor gate with emergency egress capabilities. Coordinate construction materials and location of fence with CDR.

Contractor is responsible for repairing and replacing any damaged lawn. The restoration will be performed by a landscape contractor that regularly does sodding as part of their business. All damaged lawn will be overcut by 6" or more to accomodate full width rolls of sod. Top soil to be tilled and graded to a smooth matching grade of undamaged lawn. Sod to be thoroughly saturated with water upon placement. The contractor is responsible for watering new sod until project acceptance by the CDR.

Access to all buildings and parking areas must be maintained throughout the project.

Contractors are to coordinate all work with the Contracting Officers Representative.

SHEET INDEX

GENERAL:

GII COVER SHEET

PLUMBING:

PLUMBING ABBREVIATIONS AND SYMBOLS PLUMBING - DEMOLITION PLANS PL101-1 PLUMBING - FLOOR PLAN, ISOMETRIC AND SCHEDULES

PD101-4 PLUMBING - DEMOLITION PLANS

PLUMBING - FLOOR PLAN, ISOMETRIC AND SCHEDULES PL101-4

PD101-8 PLUMBING - DEMOLITION PLANS

PL101-8 PLUMBING - FLOOR PLAN, ISOMETRIC AND SCHEDULES PD101-9 PLUMBING - DEMOLITION PLANS

PL101-9 PLUMBING - FLOOR PLAN, ISOMETRIC AND SCHEDULES

PD101-29 PLUMBING - DEMOLITION PLANS

PL101-29 PLUMBING - FLOOR PLAN, ISOMETRIC AND SCHEDULES

PD101-48 PLUMBING - DEMOLITION PLANS

PLUMBING - FLOOR PLAN, ISOMETRIC AND SCHEDULES PL101-48 PLUMBING - DEMOLITION PLANS PD101-50

PL101-50 PLUMBING - FLOOR PLAN, ISOMETRIC AND SCHEDULES

PD101-51 PLUMBING - DEMOLITION PLANS

PL101-51 PLUMBING - FLOOR PLAN, ISOMETRIC AND SCHEDULES

PLUMBING - HYDRONICS PLAN PL102-51

PD101-59 PLUMBING - DEMOLITION PLANS PLUMBING - FLOOR PLAN, ISOMETRIC AND SCHEDULES

PL101-59

PL501 PLUMBING - DETAILS PL801 PLUMBING - CONTROL SEQUENCES

100% CONSTRUCTION DOCUMENTS - FOR CONSTRUCTION





et 08 30	STAMP/SEAL: I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA.
162	
102	MN 43619
om	DANIEL J. MILLER, AIA REG. NO.
1 2	DATE: 01-15-2013

	APPROVED: SERVICE LINE DIRECTOR	DATE:	APPROVED: INFECTION CONTROL NURSE
IFY THAT THIS PLAN, OR REPORT WAS PREPARED	<u> </u>		<u> </u>
ER MY DIRECT SUPERVISION, A DULY LICENSED ARCHITECT NS OF THE STATE OF	APPROVED: GEMS COORDINATOR	DATE:	APPROVED: PATIENT SAFETY
wil	APPROVED: PROJECTS SECTION MANAGER	DATE:	APPROVED: CHIEF OF POLICE
MN 43619 LLER, AIA REG. NO.	<u> </u>		<u> </u>
5-2013	APPROVED: DIRECTOR FMS	DATE:	APPROVED: SAFETY MANAGER
	L		

DATE:	DRAWING TITLE	PROJECT TITLE	DATE 01,15,2013
DATE:	PROJECT COVER SHEET	HOT WATER GENERATORS	PLOT SCALE AS NOTED
DATE:			PROJECT NO. 656-13-225 SCIP
DATE:	APPROVED: CHIEF OF STAFF DATE:	BUILDING No CHECKED BY RWM NJE	CAD FILE
DATE:	APPROVED: MEDICAL CENTER DIRECTOR DATE:	LOCATION VA MEDICAL CENTER ST.CLOUD, MN 56303	DRAWING NO. Gl1 DWG. 1 OF 23



HVAC SYMBOLS

GAS PRESSURE REGULATOR

RELIEF/EXHAUST AIR (UP)

RELIEF/EXHAUST AIR (DOWN)

[POSITIVE PRESSURE]

[POSITIVE PRESSURE]

ROUND DUCT WITH SIZE INDICATED

→ RL | REFRIGERANT LIQUID LINE

| → RS → REFRIGERANT SUCTION LINE

RETURN DUCT (UP)

DESCRIPTION

GRAVITY BACKDRAFT DAMPER IN DUCT

MOTORIZED OPERATED DAMPER IN DUCT

DUCT WIDTH OR DIAMETER)

RECTANGULAR DUCT W/SIZE INDICATED

RADIUS ROUND ELBOW (RADIUS OF

CENTERLINE OF DUCT EQUAL TO 1.5 X

T FREEZE STAT

G → GAS METER

BF	BUTTERFLY VALVE	GV	GATE VALVE	RWL	RAIN WATER LEADER
CV	CHECK VALVE	GLV	GLOBE VALVE	RPZ	REDUCED PRESSURE BACKFLOW PREVENTOR
CWS	CHILLED WATER SUPPLY	HPC	HIGH PRESSURE CONDENSATE	R	GAS PRESSURE REGULATOR
CWR	CHILLED WATER RETURN	HPS	HIGH PRESSURE STEAM SUPPLY	RD	ROOF DRAIN
СО	CLEAN OUT	Н	WALL HYDRANT	SAN	SANITARY SEWER
CA	COMPRESSED AIR	НВ	HOSE BIBB	SMS	SNOW MELTING SYSTEM SUPPLY
CD	CONDENSATE DRAIN	HWFU	HOT WATER FIXTURE UNITS	SMR	SNOW MELTING SYSTEM RETURN
CS	CONDENSER WATER SUPPLY	HW	HOT WATER	SF	SQUARE FEET
CR	CONDENSER WATER RETURN	HW-H	HOT WATER — HARD	SFU	SUPPLY FIXTURE UNITS
CV	CONTROL VALVE	HWRC	HOT WATER RECIRCULATION	ST	STORM SEWER
CW	COLD WATER	HWS	HOT WATER SUPPLY	TW	TEMPERED WATER
CW-H	COLD WATER — HARD	HWR	HOT WATER RETURN	TYP.	TYPICAL
CWFU	COLD WATER FIXTURE UNITS	HWV	HOT WATER VALVE	DN	DOWN
DFU	DRAINAGE FIXTURE UNITS	IE	INVERT ELEVATION	V	VENT
E	EXISTING (SAN, HW, CW, ETC.)	LPC	LOW PRESSURE CONDENSATE	VA	VACUUM LINE
FFE	FINISH FLOOR ELEVATION	LPS	LOW PRESSURE STEAM SUPPLY	VTR	VENT THRU ROOF
FL	FIRE LINE	LPG	LIQUID PROPANE GAS	wco	WALL CLEAN OUT
FC0	FLOOR CLEAN OUT	MPC	MEDIUM PRESSURE CONDENSATE	WM	WATER METER
FD	FLOOR DRAIN	MPS	MEDIUM PRESSURE STEAM SUPPLY	YCO	YARD CLEAN OUT
					I
	HVAC ABBREVIA	TIO	NS NOTE: NOT	ALL ABI	BREVIATIONS MAY BE USED ON THIS PROJECT
ABBR.	DESCRIPTION	ABBR.	DESCRIPTION	ABBR.	DESCRIPTION
AFF	ABOVE FINISHED FLOOR	FFE	FINISHED FLOOR ELEVATION	OA	OUTSIDE AIR
AFG	ABOVE FINISHED GRADE	G	GAS PIPING	OFCI	OWNER FURNISHED, CONTRACTOR INSTALLED
AD	ACCESS DOORS, VERTICAL/HORIZONTAL	IG	INTERRUPTIBLE GAS PIPING	PD	PRESSURE DROP

FOS | FUEL OIL SUPPLY

FOR | FUEL OIL RETURN

GM GAS METER

FTR | FINNED TUBE RADIATION

GAS PIPING

PLUMBING ABBREVIATIONS

ABOVE FINISHED FLOOR

ABOVE FINISHED GRADE

BASEBOARD RADIATION

BACK WATER VALVE

BALL VALVE

NOTE: NOT ALL ABBREVIATIONS MAY BE USED ON THIS PROJECT

ORWL | OVERFLOW RAIN WATER LEADER

OVERFLOW ROOF DRAIN

REFRIGERANT LIQUID LINE

REFRIGERANT SUCTION LINE

RETURN AIR

SUPPLY AIR

OXYGEN PIPING

OWNER FURNISHED, CONTRACTOR INSTALLED

NATURAL GAS

CONSTRUCTION SCHEDULE

CONSTRUCTION IN EACH BUILDING SHALL BE COMPLETED WITHIN 2-3 WEEKS. IF ADDITIONAL TIME IS REQUIRED, PLUMBING CONTRACTOR

SHALL COORDINATE WITH VA-COR. SYSTEM SHUT DOWN SHALL BE PERFORMED AFTER 8PM. EXACT TIME AND LOCATION OF SHUT DOWN SHALL BE ARRANGED WITH COR PER SPECIFICATIONS. ALL WORK THAT DOES NOT AFFECT SYSTEM SHUT DOWN SHALL BE

PERFORMED DURING NORMAL WORKING HOURS.

SEQUENCE OF CONSTRUCTION

INSTALL TEMPORARY HEAT EXCHANGER (THX-1) AS SHOWN ON PLANS. . TIE TEMPORARY HEAT EXCHANGER (THX-1) STEAM, CONDENSATE,

RECIRC INTO EXISTING SYSTEMS. SHUT DOWN OPERATION OF EXISTING HEAT EXCHANGER AND ENERGIZE

DOMESTIC COLD, DOMESTIC HOT WATER, AND DOMESTIC HOT WATER

TEMPORARY HEAT EXCHANGER (THX-1),

4. DEMO EXISTING HEAT EXCHANGER AS SHOWN ON PLANS.

5. INSTALL NEW HEAT EXCHANGER AS SHOWN ON PLANS.

TO ORIGINAL CONDITION WHEN COMPLETED.

6. SHUT DOWN TEMPORARY HEAT EXCHANGER (THX-1) AND ENERGIZE NEW HEAT EXCHANGERS.

. REMOVE TEMPORARY HEAT EXCHANGER (THX-1) AND ASSOCIATED

PIPING. CAP PIPING AT SYSTEM MAINS. 8. TEMPORARY HEAT EXCHANGER (THX-1) LOCATION SHALL BE RETURNED

NOTE: THE SAME TEMPORARY HEAT EXCHANGER (THX-1) SHALL BE USED FOR EACH BUILDING. WHEN ENTIRE PROJECT IS COMPLETE, OWNER SHALL RETAIN POSSESSION OF TEMPORARY HEAT EXCHANGER

	TEMPORARY HEAT EXCHANGER SCHEDULE											
UNIT TAG	MFGR.	MODEL	HEAT EXCHANGED (MBH)	FLUID TYPE	FLOW RATE (GPM)	FLUID PD (FT H20)	EWT (°F)	LWT (°F) (BEFORE DRV)	LWT (°F) (AFTER DRV)	FLUID TYPE	PRESSURE (PSI)	FLUID PD (PSI)
THX-1	ARMSTRONG	665-DWP-PTW-DMC1-150	3,300	DOMESTIC WATER	50	10	50	140-160	120	STEAM	7	CONSTANT
NOTES: 1. SE	EE DETAIL 2/PL	_501										

			HVAC ABBREVIA		NOTE: NOT	ALL A
DL	DESCRIPTION	ABBR.	DESCRIPTION	ABBR.	DESCRIPTION	ABBR
	SHOE TAKE-OFF (45° ANGLE INLET)	AFF	ABOVE FINISHED FLOOR	FFE	FINISHED FLOOR ELEVATION	OA
 	SPIN-IN TAKE-OFF	AFG	ABOVE FINISHED GRADE	G	GAS PIPING	OFCI
}	SQUARE (MITERED) ELBOW	AD	ACCESS DOORS, VERTICAL/HORIZONTAL	IG	INTERRUPTIBLE GAS PIPING	PD
	SQUARE (MITERED) ELBOW W/TURNING VANES	CFH	CUBIC FEET PER HOUR	ΙE	INVERT ELEVATION	RL
18"9	SQUARE TO ROUND TRANSITION, 15' MAXIMUM ANGLE	CFM	CUBIC FEET PER MINUTE	LWT	LEAVING WATER TEMPERATURE	RS
2	STRAIGHT LATERAL TAKEOFF (ROUND DUCT)	DB/WB	DRY BULB/WET BULB	SF	SQUARE FEET	RA
	STRAIGHT TAP TAKE-OFF	EWT	ENTERING WATER TEMPERATURE	TYP.	TYPICAL	SA
14X12 }	SYMMETRICAL DOVE TAIL WYE	EAT	ENTERING AIR TEMPERATURE	LAT	LEAVING AIR TEMPERATURE	
24X12	STMMETRICAL DOVE TAIL WIE	EA	EXHAUST AIR	LPG	LIQUID PROPANE GAS	
X	TEMPERATURE SENSOR TO CONTROL EQUIPMENT X	ESP	EXTERNAL STATIC PRESSURE	MOD	MOTORIZED OPERATED DAMPER IN DUCT	
×	THERMOSTAT TO CONTROL EQUIPMENT X	E	EXISTING (SA, RA, EA, ETC.)	NG	NATURAL GAS	

GENERAL MECHANICAL NOTES:

- PROVIDE ALL LABOR, MATERIALS AND EQUIPMENT NECESSARY FOR COMPLETE AND OPERATIONAL SYSTEMS DESCRIBED IN THIS SPECIFICATION OR SHOWN ON THE PLANS UNLESS INDICATED OR NOTED OTHERWISE. IT IS THE INTENT OF THE DRAWINGS AND SPECIFICATIONS THAT ALL SYSTEMS BE COMPLETE AND READY FOR OPERATION.
- CONTRACTOR SHALL BE RESPONSIBLE TO REMOVE ALL DEMO'D PIPING BACK TO SOURCE. ABANDONED PIPING SHALL NOT BE ALLOWED.
- EXAMINE PREMISES AND UNDERSTAND THE CONDITIONS WHICH MAY AFFECT THIS DIVISION'S WORK BEFORE SUBMITTING BIDS. NO SUBSEQUENT ALLOWANCE FOR TIME OR MONEY WILL BE CONSIDERED FOR ANY CONSEQUENCE RELATED TO FAILURE TO EXAMINE SITE CONDITIONS.

DESCRIPTION

ACCESS DOORS, VERTICAL/HORIZONTAL

BULLHEAD TEE WITH TURNING VANES

CONNECT TO EXISTING

(UP) [NEGATIVE PRESSURE]

FD FIRE DAMPER IN DUCT

FSD FIRE/SMOKE DAMPER IN DUCT

FLEXIBLE DUCT

1.3 LICENSE, FEES AND PERMITS:

(DOWN) [NEGATIVE PRESSURE]

FLEXIBLE CONNECTION IN DUCT

EXHAUST AIR OR OUTSIDE AIR INTAKE

EXHAUST AIR OR OUTSIDE AIR INTAKE

- CONTRACTOR MUST RETAIN AND PAY FOR ALL LICENSES REQUIRED BY THE CITY AND STATE. THE PLUMBING CONTRACTOR AND ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR ARRANGEMENT OF REQUIRED INSPECTIONS AND PAY ALL PERMIT AND INSPECTION FEES.
- 1.4 CODE OF COMPLIANCE: ALL PLUMBING AND ELECTRICAL WORK SHALL COMPLY WITH APPLICABLE NATIONAL, STATE OR LOCAL CODES, LAWS, ORDINANCES AND/OR REGULATIONS. IF CONTRACTORS ARE AWARE OF CONFLICTS BETWEEN PLANS OR SPECIFICATIONS AND SUCH CODES OR REGULATIONS, THEY SHALL BE BROUGHT TO THE ENGINEER'S ATTENTION PRIOR TO COMMENCING APPLICABLE WORK. IF CONTRACTORS KNOWINGLY PERFORMS WORK IN VIOLATION OF SUCH CODES OR REGULATION, WHETHER SUCH VIOLATION IS SHOWN OR SPECIFIED OR NOT, THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR THE CORRECTION OF THE VIOLATION AT NO ADDITIONAL CHARGE.
- CODE COMPLIANCE IS MANDATORY. NOTHING IN THESE DRAWINGS AND SPECIFICATIONS PERMITS WORK NOT CONFORMING TO THESE CODES. WHERE WORK IS SHOWN TO EXCEED MINIMUM CODE REQUIREMENTS, COMPLY WITH DRAWING AND SPECIFICATIONS.

2 5

STRAIGHT TAP TAKE-OFF

24X12 18" | 15" MAXIMUM ANGLE

(ROUND DUCT)

RECTANGULAR DUCT W/ACCOUSTICAL LINING | SHOE TAKE-OFF (45' ANGLE INLET)

- FIELD VERIFY EXACT SCOPE OF WORK PRIOR TO BID. 1.5 DRAWINGS AND SPECIFICATIONS:
 - PLUMBING PLANS SHOW GENERAL ARRANGEMENT OF PIPING, DUCTWORK, EQUIPMENT, ETC. FOLLOW AS CLOSELY AS ACTUAL BUILDING CONSTRUCTION AND WORK OF OTHER TRADES WILL PERMIT. BECAUSE OF THE SMALL SCALE OF PLANS, IT IS NOT POSSIBLE TO INDICATE ALL OFFSETS, FITTINGS, AND ACCESSORIES WHICH MAY BE REQUIRED. INVESTIGATE STRUCTURAL AND FINISH CONDITIONS AFFECTING THIS WORK AND ARRANGE WORK ACCORDINGLY, PROVIDING SUCH FITTINGS, VALVES AND ACCESSORIES REQUIRED TO MEET THE CONDITIONS.
- 1.6 RECORD DRAWINGS:
 - MAINTAIN ONE SET OF CLEAN WORKING DRAWINGS AT THE JOB SITE AND RECORD "AS-BUILT" INFORMATION FOR ANY CHANGE OR MODIFICATIONS TO THE CONSTRUCTION DOCUMENTS.
- 1.7 GUARANTEE: GUARANTEE THE INSTALLATION FREE FROM DEFECTS OF WORKMANSHIP AND MATERIALS OF A PERIOD OF ONE (1) YEAR AFTER DATE OF CERTIFICATE OF FINAL PAYMENT, AND PROMPTLY REMEDY ANY DEFECTS DEVELOPING DURING THE PERIOD WITHOUT CHARGE.
- A. COORDINATE WORK WITH OTHER TRADES TO AVOID CONFLICT AND TO PROVIDE CORRECT ROUGH-IN AND CONNECTION FOR EQUIPMENT FURNISHED UNDER OTHER TRADES THAT REQUIRE HVAC AND PLUMBING CONNECTIONS. INFORM CONTRACTORS OF OTHER TRADES OF THE REQUIRED CLEARANCES AROUND HVAC AND PLUMBING EQUIPMENT TO MAINTAIN SERVICEABILITY AND CODE


- VERIFY EQUIPMENT DIMENSIONS AND REQUIREMENTS WITH PROVISIONS SPECIFIED UNDER THIS SECTION. CHECK ACTUAL JOB CONDITIONS BEFORE FABRICATING WORK. REPORT NECESSARY CHANGES IN TIME TO PREVENT NEEDLESS WORK. CHANGES OR ADDITIONS SUBJECT TO ADDITIONAL COMPENSATION WHICH ARE MADE WITHOUT WRITTEN AUTHORIZATION AND AN AGREED PRICE, SHALL BE AT CONTRACTOR'S RISK AND EXPENSE.
- 1.9 BASIC MATERIALS AND METHODS: PLUMBING CONTRACTOR AND ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR REQUIRED DIGGING, CUTTING AND PATCHING INCIDENT TO WORK OF THIS DIVISION AND MAKE REQUIRED REPAIRS AFTERWARDS TO SATISFACTION OF ENGINEER. CUT CAREFULLY TO MINIMIZE REPAIRS TO EXISTING WORK. DO NOT CUT BEAMS, COLUMNS, TRUSSES OR ANY
 - STRUCTURAL MEMBER. PATCH AND REPAIR WALLS, FLOORS, CEILINGS AND ROOFS WITH MATERIALS OF SAME QUALITY AND APPEARANCE AS ADJACENT SURFACES UNLESS OTHERWISE SHOWN. SURFACE FINISHES SHALL EXACTLY MATCH EXISTING

FINISHES OF SAME MATERIALS.

- ADJUST LOCATIONS OF PIPES, EQUIPMENT, FIXTURES, ETC. TO ACCOMMODATE WORK FROM INTERFERENCE ANTICIPATED AND ENCOUNTERED. DETERMINE EXACT ROUTE AND LOCATION OF EACH PIPE PRIOR TO FABRICATION. IN THE EVENT THAT OTHER THAN SPECIFIED EQUIPMENT IS USED AND WILL NOT FIT JOB SITE CONDITIONS, THE HVAC CONTRACTOR AND/OR PLUMBING
- PLUMBING AND ELECTRICAL CONTRACTOR SHALL REMOVE ALL DEMO'D PIPE

AND WIRE BACK TO MAIN; NO ABANDON MATERIAL IS ALLOWED.

CONTRACTOR ASSUMES RESPONSIBILITY FOR REPLACEMENT WITH ITEMS NAMED



100% Construction Documents - For Construction



Alexandria Office St. Cloud Office 120 17th Avenue W. 3339 West St. Germain, Suite 250 Alexandria, MN 56308 St. Cloud, MN 56301





6 7


JLG 11050M


I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA. DATE: 01-15-2013


HOT WATER GENERATORS PLUMBING ABBREVIATIONS, SYMBOLS AS NOTED & DRAWING INDEX 656-13-225 PPROVED: PROJECT DIRECTOR AS NOTED | STJ | GAP | XXX LOCATION
ST. CLOUD VA MEDICAL CENTER
PL001
DWG.2 OF

















GENERAL NOTES


- 1. PLUMBING CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS.
- 2. ALL FLOOR AND WALL PENETRATIONS SHALL BE SEALED TO MEET FIRE RATINGS.
- 3. ALL HATCHED ITEMS DENOTES DEMOLITION.

PLAN NOTES

1) PLUMBING CONTRACTOR SHALL REMOVE EXISTING ELECTRIC WATER HEATER.



DEMOLITION ISOMETRIC



100% Construction Documents - For Construction



2 3 5

Alexandria Office St. Cloud Office
120 17th Avenue W. 3339 West St. Germain, Suite 250 Alexandria, MN 56308 St. Cloud, MN 56301



DATE: 01-15-2013

HOT WATER GENERATORS PLUMBING -DEMOLITION PLANS PLOT SCALE
AS NOTED

PROJECT NO.
656-13-225
SCIP


BUILDING No
AS NOTED


CHECKED BY
AS NOTED

CAD FILE
XXX ST. CLOUD, MN 56303


DRAWING NO. PD101-8
ST. CLOUD, MN 56303

DRAWING NO. PD101-8
DWG.7 OF 23












- 1. PLUMBING CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS.
- 2. ALL FLOOR AND WALL PENETRATIONS SHALL BE SEALED TO MEET FIRE RATINGS.
- 3. TEMPORARY WATER HEATER SHALL NOT BE REQUIRED FOR THIS BUILDING. PLUMBING CONTRACTOR SHALL COORDINATE WITH VA STAFF PRIOR TO REPLACEMENT OF WATER HEATER.
- 4. PLUMBING CONTRACTOR SHALL HIRE LICENSED ELECTRICAL CONTRACTOR TO WIRE WATER HEATER (WH-1-8).

	ELECTRIC WATER HEATER SCHEDULE									
UNIT TAG	MFGR.	MODEL	STORAGE CAPACITY (GAL.)	HEATING CAPACITY (WATTS)	GPH RECOVERY AT 90°F RISE	VOLTS	PHASE	LOCATION	NOTES	
WH-1-8	VH-1-8 A.O. SMITH DRE-80-13.5 80 4500 62 240 1 ROOM 13 1									
	NOTES: 1. PROVIDE TEMPERATURE AND PRESSURE RELIEF VALVE.									



100% Construction Documents - For Construction



2 5

Alexandria Office St. Cloud Office
120 17th Avenue W. 3339 West St. Germain, Suite 250
Alexandria, MN 56308 St. Cloud, MN 56301
(320) 762-1290 (320) 217-5557



STAMP/SEAL:

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

MN 44935

SHANE T. JOHNSTON, PE REG. NO.

DATE: 01-15-2013

PROJECT TITLE

PLUMBING - FLOOR PLAN,
ISOMETRIC & SCHEDULES

APPROVED: PROJECT DIRECTOR

DATE

HOT WATER GENERATORS

PLOT SCALE
AS NOTED

PROJECT NO.
656-13-225
SCIP

BUILDING NO
AS NOTED

CHECKED BY
AS NOTED

CAD FILE
XXX

LOCATION
ST. CLOUD VA MEDICAL CENTER
ST. CLOUD, MN 56303

DATE


O1.15.2013


PLOT SCALE
AS NOTED

PROJECT NO.
656-13-225
SCIP

CAD FILE
XXX

DRAWING NO.
PL101-8
DWG.8 OF 23





100% Construction Documents - For Construction



2 3 5

Alexandria Office St. Cloud Office 120 17th Avenue W. 3339 West St. Germain, Suite 250 Alexandria, MN 56308 St. Cloud, MN 56301



JLG 11050M

DATE: 01-15-2013

HOT WATER GENERATORS PLUMBING -DEMOLITION PLANS AS NOTED 656-13-225 BUILDING NO

AS NOTED

CHECKED BY DRAWN

AJF

CAD FILE


XXX LOCATION
ST. CLOUD VA MEDICAL CENTER
DRAWING NO.
PD101-9
ST. CLOUD, MN 56303
DWG.9 OF 23


BUILDING KEY PLAN

PROJECT LOCATION

BUILDING 9

PLAN NOTES





GENERAL NOTES

- 1. PLUMBING CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS.
- 2. ALL FLOOR AND WALL PENETRATIONS SHALL BE SEALED TO MEET FIRE RATINGS.
- 3. SEE SHEET PL-001 FOR SEQUENCE OF CONSTRUCTION.

PLAN NOTES


(1) CAP MEDIUM PRESSURE STEAM PIPE.

- PLUMBING CONTRACTOR SHALL PROVIDE AND INSTALL PRE-MANUFACTURED HEAT EXCHANGER SKID. SKID SHALL BE PRE-PIPE INCLUDING VALVES, GAUGES AND FITTINGS AS SHOWN ON 1/PL501. CONTROLS CONTRACTOR SHALL PROVIDE HEAT EXCHANGER MANUFACTURER REQUIRED FLOW SWITCHES AND TEMPERATURE GAUGES. HEAT EXCHANGER MANUFACTURER SHALL INSTALL FLOW SWITCHES AND TEMPERATURE GAUGES PRIOR TO SHIPMENT. PLUMBING CONTRACTOR, CONTROLS CONTRACTOR AND MANUFACTURER SHALL COORDINATE.
- (3) EXISTING HOT WATER RECIRC. PUMP RELOCATED.
- PLUMBING CONTRACTOR SHALL HIRE A LICENSED ELECTRICAL CONTRACTOR TO WIRE CONDENSATE PUMP. ELECTRICAL CONTRACTOR SHALL WIRE PUMP BACK TO NEAREST EXISTING ELECTRICAL PANEL WITH SPARE CAPACITY AND PROVIDE A 20 AMP BREAKER. NO SPLICING ALLOWED. PROVIDE A NEW TYPED PANEL DIRECTORY IN EXISTING PANEL AFTER WORK IS COMPLETE.
- 5 PLUMBING CONTRACTOR SHALL HIRE A LICENSED ELECTRICAL CONTRACTOR TO PROVIDE 120V POWER TO THE DIGITAL MIXING VALVE, TYPICAL TWO PER SKID. SEE 1/PL501 FOR LOCATION OF MIXING VALVES ON SKID. MIXING VALVES SHALL BE WIRED BACK TO A SPARE 20 AMP BREAKER ON A EXISTING EMERGENCY ELECTRICAL PANEL. PANEL LOCATED IN ENGINEERING STORAGE ROOM 15, EXACT PANEL LOCATION SHALL BE VERIFIED DURING PRE-BID WALK-THRU. PROVIDE NEW TYPED PANEL DIRECTORY IN EXISTING PANEL AFTER WORK IS COMPLETE. NO SPLICING ALLOWED.

	HEAT EXCHANGER SCHEDULE											
UNIT TAG	MFGR.	MODEL	HEAT ENHANCED (MBH)	FLUID TYPE	FLOW RATE (GPM)	FLUID PD (FT H20)	EWT (°F)	LWT (°F) (BEFORE DRV)	LWT (°F) (AFTER DRV)	FLUID TYPE	PRESSURE (PSI)	FLUID PD (PSI)
HX-1-9	ARMSTRONG	535-DWP-PTW-DMC1	1,800	DOMESTIC WATER	23	10	50	140	120	STEAM	7	CONSTANT
HX-2-9	ARMSTRONG	535-DWP-PTW-DMC1	1,800	DOMESTIC WATER	23	10	50	140	120	STEAM	7	CONSTANT
NOTES:	E DETAIL 1/PL	_501										

	RECEIVER CONDENSATE UNIT SCHEDULE								
UNIT TAG	MFGR.	MODEL	NUMBER OF PUMPS	DISCHARGE PRESSURE PSIG	PUMP CAPACITY GPM	RECEIVER CAPACITY GALLONS	MOTOR HP	VOLTS	PHASE
RCU-1-9	HOFFMAN PUMP	WCD12-20B-MA	DUPLEX	20	18	14	1/3	120	1

1. PROVIDE CAST IRON RECEIVER, TWO PUMP AND MOTOR ASSEMBLIES, DOUBLE POLE MECHANICAL ALTERNATOR.



100% Construction Documents - For Construction





Alexandria Office
120 17th Avenue W.
Alexandria, MN 56308
(320) 762-1290

St. Cloud Office
3339 West St. Germain, Suite 250
St. Cloud, MN 56301
(320) 217-5557



_							
	STAMP/SEAL: I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.	PLUMBING - FLOOR PLA ISOMETRIC & SCHEDULE	,	PROJECT TITLE HOT WATER	R GENERA	TORS	PLOT SCA AS NO PROJECT 656-1 SCIP
	SHANE T. JOHNSTON, PE REG. NO.	APPROVED: PROJECT DIRECTOR DAT	:	BUILDING No AS NOTED	CHECKED BY	DRAWN AJF	CAD FILE
	DATE: 01-15-2013			ST. CLOUD V		CENTER	DRAWING PL10 DWG.1





Alexandria, MN 56308 St. Cloud, MN 56301


(320) 217-5557

DATE: 01-15-2013

JLG 11050M

LOCATION
ST. CLOUD VA MEDICAL CENTER
PD101-29
ST. CLOUD, MN 56303

DRAWING NO.
PD101-29
DWG.110F 23



GENERAL NOTES

- 1. PLUMBING CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS.
- 2. ALL FLOOR AND WALL PENETRATIONS SHALL BE SEALED TO MEET FIRE RATINGS.
- 3. SEE SHEET PL-001 FOR SEQUENCE OF CONSTRUCTION.

PLAN NOTES

(1) TEMPOARARY HEAT EXCHANGER (THX-1) LOCATION.


<2>PLUMBING CONTRACTOR SHALL PROVIDE AND INSTALL Y PRE-MANUFACTURED HEAT EXCHANGER SKID. SKID SHALL BE PRE-PIPED INCLUDING VALVES, GAUGES AND FITTINGS AS SHOWN ON DETAIL 1/PL501. CONTROLS CONTRACTOR SHALL PROVIDE HÉAT EXCHANGER MANUFACTURER REQUIRED FLOW SWITCHES AND TEMPERATURE GAUGES. HEAT EXCHANGER MANUFACTURER SHALL INSTALL FLOW SWITCHES AND TEMPERATURE GAUGES PRIOR TO SHIPMENT. PLUMBING CONTRACTOR, CONTROLS CONTRACTOR AND MANUFACTURER SHALL COORDINATE.

(3) CAP EXISTING MEDIUM PRESSURE STEAM.

(4) PLUMBING CONTRACTOR SHALL HIRE A LICENSED ELECTRICAL CONTRACTOR TO PROVIDE 120V POWER TO THE DIGITAL MIXING VALVE, TYPICAL TWO PER SKID. SE# 1/PL501 FOR LOCATION OF MIXING VALVES ON SKID. MIXING VALVES SHALL BE WIRED BACK TO A SPARE 20 AMP BREAKER ON A EXISTING EMERGENCY ELECTRICAL PANEL. PANEL LOCATED IN ELECTRICAL ROOM 12, EXACT PANEL LOCATION SHALL BE VERIFIED DURING PRE-BID WALK-THRU. PROVIDE NEW TYPED PANEL DIRECTORY IN EXISTING PANEL AFTER WORK IS COMPLETE. NO SPLICING ALLOWED.

	HEAT EXCHANGER SCHEDULE											
UNIT TAG	MFGR.	MODEL	HEAT EXCHANGED (MBH)	FLUID TYPE	FLOW RATE (GPM)	FLUID PD (FT H20)	EWT (°F)	LWT (°F) (BEFORE DRV)		FLUID TYPE	PRESSURE (PSI)	FLUID PD (PSI)
HX-1-29	ARMSTRONG	665-DWP-PTW-DMC1-150	3,300	DOMESTIC WATER	50	10	50	140	120	STEAM	7	CONSTANT
HX-2-29	ARMSTRONG	665-DWP-PTW-DMC1-150	3,300	DOMESTIC WATER	50	10	50	140	120	STEAM	7	CONSTANT

NOTES: 1. SEE DETAIL 1/PL501



100% Construction Documents - For Construction



2 3 5


Alexandria Office St. Cloud Office 120 17th Avenue W. 3339 West St. Germain, Suite 250 Alexandria, MN 56308 St. Cloud, MN 56301



	DRAWING TITLE
STAMP/SEAL:	
I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.	PLUMBING - FLO ISOMETRIC & SO
Lane Tollan MN 44935	APPROVED: PROJECT DIRECTOR
SHANE T. JOHNSTON, PE REG. NO.	
DATE: 01-15-2013	
1	-

PLUMBING - FLOOR PLAN, ISOMETRIC & SCHEDULES	PROJECT TITLE HOT WATER	R GENERA	TORS	DATE 01.15.2013 PLOT SCALE AS NOTED
				PROJECT NO. 656-13-225 SCIP
APPROVED: PROJECT DIRECTOR DATE:	BUILDING No AS NOTED	CHECKED BY	DRAWN AJF	CAD FILE
	ST. CLOUD VA	_	CENTER	DRAWING NO. PL101-29 DWG.120F 23

















GENERAL NOTES

- PLUMBING CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS.
- 2. ALL FLOOR AND WALL PENETRATIONS SHALL BE SEALED TO MEET FIRE RATINGS.
- 3. ALL HATCHED ITEMS DENOTES DEMOLITION.
- 4. SEE SHEET PL-001 FOR SEQUENCE OF CONSTRUCTION.

PLAN NOTES

- 1) PLUMBING CONTRACTOR SHALL REMOVE EXISTING DOMESTIC HOT WATER TANK, INSULATION, GAUGES, AND ASSOCIATED MATERIALS.
- 2 PLUMBING CONTRACTOR SHALL REMOVE EXISTING CONDENSATE PIPE, VALVES, CONDENSATE TRAP, AND ASSOCIATED INSULATION AND HANGERS.
- 3 PLUMBING CONTRACTOR SHALL REMOVE EXISTING STEAM PIPE, CONTROL VALVE, AND ASSOCIATED INSULATION AND HANGERS.
- 4 PLUMBING CONTRACTOR SHALL REMOVE EXISTING DOMESTIC HOT WATER PIPE AND ASSOCIATED INSULATION AND HANGERS.
- 5 PLUMBING CONTRACTOR SHALL REMOVE EXISTING DOMESTIC HOT WATER RECIRC. PIPE, VALVES, AND ASSOCIATED INSULATION AND HANGERS.
- 6 PLUMBING CONTRACTOR SHALL REMOVE EXISTING DOMESTIC COLD WATER PIPE, VALVES, AND INSULATION AND HANGERS.
- 7 TIE-IN POINT FOR DOMESTIC HOT WATER TO TEMPORARY HEAT EXCHANGE (THX-1). PLUMBING CONTRACTOR SHALL PIPE DOMESTIC HOT WATER TO TEMPORARY HEAT EXCHANGER (THX-1). SEE SHEET PL101-48 FOR TEMPORARY HEAT EXCHANGER (THX-1) LOCATION.
- 8 TIE-IN POINT FOR DOMESTIC COLD WATER TO TEMPORARY HEAT EXCHANGER (THX-1). PLUMBING CONTRACTOR SHALL PIPE DOMESTIC COLD WATER TO TEMPORARY HEAT EXCHANGER (THX-1) AS REQUIRED. SEE SHEET PL101-48 FOR TEMPORARY HEAT EXCHANGER (THX-1) LOCATION.
- 9 TIE-IN POINT FOR LOW PRESSURE STEAM TO TEMPORARY HEAT EXCHANGER (THX-1). PLUMBING CONTRACTOR SHALL PIPE LOW PRESSURE STEAM TO TEMPORARY HEAT EXCHANGER (THX-1) AS REQUIRED. SEE SHEET PL101-48 FOR TEMPORARY HEAT EXCHANGER (THX-1) LOCATION.
- TIE-IN POINT FOR CONDENSATE TO TEMPORARY HEAT EXCHANGER (THX-1). PLUMBING CONTRACTOR SHALL PIPE CONDENSATE TO TEMPORARY HEAT EXCHANGER (THX-1) AS REQUIRED. SEE SHEET PL101-48 FOR TEMPORARY HEAT EXCHANGER (THX-1) LOCATION.
- TIE-IN POINT FOR HOT WATER RECIRC. TO
 TEMPORARY HEAT EXCHANGER (THX-1). PLUMBING
 CONTRACTOR SHALL PIPE HOT WATER RECIRC. TO
 TEMPORARY HEAT EXCHANGER (THX-1) AS REQUIRED.
 SEE SHEET PL101-48 FOR TEMPORARY HEAT
 EXCHANGER (THX-1) LOCATION.
- 12 PLUMBING CONTRACTOR SHALL REMOVE EXISTING CONCRETE STANDS. PATCH FLOOR TO MATCH EXISTING FLOOR CONDITIONS.



100% Construction Documents - For Construction



Alexandria Office St. Cloud Office 3339 West St. Germain, Suite 250 Alexandria, MN 56308 St. Cloud, MN 56301 (320) 762-1290 (320) 217-5557



SHAMP/SEAL:

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENSINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

APPROVE(

SHANE T. JOHNSTON, PE REG. NO. DATE: 01-15-2013

PROJECT TITLE

PLUMBING DEMOLITON PLANS

PROJECT TITLE
HOT WATER GENERATORS

PLOT SCALE
AS NOTED

PROJECT NO.
656-13-225
SCIP

BUILDING NO
AS NOTED

STJ

DRAWN
AJF

CAD FILE
XXXX

LOCATION
ST. CLOUD VA MEDICAL CENTER
ST. CLOUD, MN 56303


DATE
O1.15.2013


PLOT SCALE
AS NOTED

PROJECT NO.
656-13-225
SCIP


DRAWN
AJF

DRAWING NO.
PD 101-48
DWG.130F 23





PLUMBING FLOOR PLAN SCALE = 1/4"=1'-0" BUILT



2 3 5

GENERAL NOTES

- 1. PLUMBING CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS.
- 2. ALL FLOOR AND WALL PENETRATIONS SHALL BE SEALED TO MEET FIRE RATINGS.
- 3. SEE SHEET PL-001 FOR SEQUENCE OF CONSTRUCTION.

PLAN NOTES

- TEMPOARARY HEAT EXCHANGER (THX-1) LOCATION.
- 2 PLUMBING CONTRACTOR SHALL PROVIDE AND INSTALL PRE-MANUFACTURED HEAT EXCHANGER SKID. SKID SHALL BE PRE-PIPE INCLUDING VALVES, GAUGES AND FITTINGS AS SHOWN ON 1/PL501. CONTROLS CONTRACTOR SHALL PROVIDE HEAT EXCHANGER MANUFACTURER REQUIRED FLOW SWITCHES AND TEMPERATURE GAUGES. HEAT EXCHANGER MANUFACTURER SHALL INSTALL FLOW SWITCHES AND TEMPERATURE GAUGES PRIOR TO SHIPMENT. PLUMBING CONTRACTOR, CONTROLS CONTRACTOR AND MANUFACTURER SHALL COORDINATE.
- (3) PLUMBING CONTRACTOR SHALL HIRE A LICENSED ELECTRICAL CONTRACTOR TO PROVIDE 120V POWER TO THE DIGITAL MIXING VALVE, TYPICAL TWO PER SKID. SEE 1/PL501 FOR LOCATION OF MIXING VALVES ON SKID. MIXING VALVES SHALL BE WIRED BACK TO A SPARE 20 AMP BREAKER ON A EXISTING EMERGENCY ELECTRICAL PANEL. PANEL LOCATED IN SERVICE ROOM 3C, EXACT PANEL LOCATION SHALL BE VERIFIED DURING PRE-BID WALK-THRU. PROVIDE NEW TYPED PANEL DIRECTORY IN EXISTING PANEL AFTER WORK IS COMPLETE. NO SPLICING ALLOWED.

	HEAT EXCHANGER SCHEDULE											
UNIT TAG	MFGR.	MODEL	HEAT EXCHANGED (MBH)	FLUID TYPE	FLOW RATE (GPM)	FLUID PD (FT H20)	EWT (°F)	LWT (°F) (BEFORE DRV)	LWT (°F) (AFTER DRV)	FLUID TYPE	PRESSURE (PSI)	FLUID PD (PSI)
HX-1-48 AR	RMSTRONG	665-DWP-PTW-DMC1-150	3,300	DOMESTIC WATER	50	10	50	140	120	STEAM	7	CONSTANT
HX-2-48 AR	RMSTRONG	665-DWP-PTW-DMC1-150	3,300	DOMESTIC WATER	50	10	50	140	120	STEAM	7	CONSTANT

1. SEE DETAIL 1/PL501

BUILDING KEY PLAN


100% Construction Documents - For Construction





Alexandria Office St. Cloud Office



STAMP/SEAL: I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE	PLUMBING - FLOOI ISOMETRIC & SCHI	,	PROJECT TITLE HOT WATER	R GENERA	TORS	DATE 01.15.2013 PLOT SCALE AS NOTED
LAWS OF THE STATE OF MINNESOTA.						PROJECT NO. 656-13-225 SCIP
SHANE T. JOHNSTON, PE REG. NO.	APPROVED: PROJECT DIRECTOR	DATE:	BUILDING No AS NOTED	CHECKED BY	DRAWN AJF	CAD FILE
DATE: 01-15-2013			ST. CLOUD, N	_	CENTER	DRAWING NO. PL101-48 DWG.140F 23







GENERAL NOTES

- 1. PLUMBING CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS.
- 2. ALL FLOOR AND WALL PENETRATIONS SHALL BE SEALED TO MEET FIRE RATINGS.
- 3. SEE SHEET PL-001 FOR SEQUENCE OF CONSTRUCTION.

PLAN NOTES

TEMPOARARY HEAT EXCHANGER (THX-1) LOCATION.

(2) PLUMBING CONTRACTOR SHALL PROVIDE AND INSTALL

- PRE-MANUFACTURED HEAT EXCHANGER SKID. SKID SHALL BE PRE-PIPE INCLUDING VALVES, GAUGES AND FITTINGS AS SHOWN ON 1/PL501. CONTROLS CONTRACTOR SHALL PROVIDE HEAT EXCHANGER MANUFACTURER REQUIRED FLOW SWITCHES AND TEMPERATURE GAUGES. HEAT EXCHANGER MANUFACTURER SHALL INSTALL FLOW SWITCHES AND TEMPERATURE GAUGES PRIOR TO SHIPMENT. PLUMBING CONTRACTOR, CONTROLS CONTRACTOR AND MANUFACTURER SHALL COORDINATE.
- 3 CAP EXISTING STEAM PIPE.
- 4 PLUMBING CONTRACTOR SHALL HIRE A LICENSED ELECTRICAL CONTRACTOR TO WIRE CONDENSATE PUMP. ELECTRICAL CONTRACTOR SHALL WIRE PUMP BACK TO NEAREST EXISTING ELECTRICAL PANEL WITH SPARE CAPACITY AND PROVIDE A 20 AMP BREAKER. NO SPLICING ALLOWED. PROVIDE A NEW TYPED PANEL DIRECTORY IN EXISTING PANEL AFTER WORK IS COMPLETE.
- PLUMBING CONTRACTOR SHALL HIRE A LICENSED ELECTRICAL CONTRACTOR TO PROVIDE 120V POWER TO THE DIGITAL MIXING VALVE, TYPICAL TWO PER SKID. SEE 1/PL501 FOR LOCATION OF MIXING VALVES ON SKID. MIXING VALVES SHALL BE WIRED BACK TO A SPARE 20 AMP BREAKER ON A EXISTING EMERGENCY ELECTRICAL PANEL. PANEL LOCATED IN MECHANICAL ROOM 21, EXACT PANEL LOCATION SHALL BE VERIFIED DURING PRE—BID WALK—THRU. PROVIDE NEW TYPED PANEL DIRECTORY IN EXISTING PANEL AFTER WORK IS COMPLETE. NO SPLICING ALLOWED.

	HEAT EXCHANGER SCHEDULE											
UNIT TAG	MFGR.	MODEL	HEAT EXCHANGED (MBH)	FLUID TYPE	FLOW RATE (GPM)	FLUID PD (FT H20)	EWT (°F)	LWT (°F) (BEFORE DRV)	` ,	FLUID TYPE	PRESSURE (PSI)	FLUID PD (PSI)
HX-1-50	ARMSTRONG	665-DWP-PTW-DMC1-150	3,300	DOMESTIC WATER	50	10	50	140	120	STEAM	7	CONSTANT
HX-2-50	ARMSTRONG	665-DWP-PTW-DMC1-150	3,300	DOMESTIC WATER	50	10	50	140	120	STEAM	7	CONSTANT


NOTES:
1. SEE DETAIL 1/PL501

RECEIVER CONDENSATE UNIT SCHEDULE

UNIT TAG MFGR. MODEL NUMBER OF PUMPS PRESSURE PSIG PUMP CAPACITY GAPACITY GA

NOTES:

PROVIDE CAST IRON RECEIVER, TWO PUMP AND MOTOR ASSEMBLIES, DOUBLE POLE MECHANICAL ALTERNATOR.



100% Construction Documents - For Construction



Alexandria Office
120 17th Avenue W.
Alexandria, MN 56308
(320) 762-1290

St. Cloud Office
3339 West St. Germain, Suite 250
St. Cloud, MN 56301
(320) 217-5557



DRAWING TITLE

PLUMBING - FLOOR PLAN,
OR REPORT WAS PREPARED BY ME OR UNDER MY
DIRECT SUPERVISION, AND THAT THIS PLAN, SPECIFICATION,
OR REPORT WAS PREPARED BY ME OR UNDER MY
DIRECT SUPERVISION, AND THAT THIS PLAN, SPECIFICATION,
OR REPORT WAS PREPARED BY ME OR UNDER MY
DIRECT SUPERVISION, AND THAT THAT AND ADULY
LICENSED PROFESSIONAL ENGINEER UNDER THE
LAWS OF THE STATE OF MINNESOTA.

APPROVED: PROJECT DIRECTOR

DATE:

STAMP/SEAL:
HOT WATER GENERATORS

PLOT SCALE
AS NOTED

PROJECT NO.
656-13-2225
SCIP

APPROVED: PROJECT DIRECTOR


DATE:


APPROVED: PROJECT DIRECTOR

DATE:

LOCATION
ST. CLOUD VA MEDICAL CENTER
ST. CLOUD, MN 56303

DRAWING NO.
PL101-50
DWG.160F 23







⁴ PICTURE #1

BUILDING 51-ROOM 10



5 PICTURE #2




6 PICTURE #3

PLAN NOTES

- 1>PLUMBING CONTRACTOR SHALL REMOVE EXISTING DOMESTIC HOT WATER TANK, INSULATION, GAUGES, AND ASSOCIATED MATERIALS.
- 2>PLUMBING CONTRACTOR SHALL REMOVE EXISTING CONDENSATE PIPE, VALVES, CONDENSATE TRAP, AND ASSOCIATED INSULATING AND HANGERS.
- 3>PLUMBING CONTRACTOR SHALL REMOVE EXISTING STEAM PIPE, CONTROL VALVE, AND ASSOCIATED INSULATION AND HANGERS.
- (4) PLUMBING CONTRACTOR SHALL REMOVE EXISTING DOMESTIC HOT WATER PIPE AND ASSOCIATED INSULATION AND HANGERS.
- (5>PLUMBING CONTRACTOR SHALL REMOVE EXISTING DOMESTIC HOT WATER RECIRC. PIPE, VALVES, AND ASSOCIATED INSULATION AND HANGERS.
- 6>PLUMBING CONTRACTOR SHALL REMOVE EXISTING DOMESTIC COLD WATER PIPE, VALVES, AND ASSOCIATED INSULATION AND HANGERS.
- (7>TIE-IN POINT FOR DOMESTIC HOT WATER TO TEMPORARY HEAT EXCHANGER (THX-1). PLUMBING CONTRACTOR SHALL PIPE DOMESTIC HOT WATER TO TEMPORARY HEAT EXCHANGER (THX-1). SEE SHEET PL101-51 FOR TEMPORARY HEAT EXCHANGER (THX-1) LOCATION.
- 8 TIE-IN POINT FOR DOMESTIC COLD WATER TO TEMPORARY HEAT EXCHANGER (THX-1). PLUMBING CONTRACTOR SHALL PIPE DOMESTIC COLD WATER TO TEMPORARY HEAT EXCHANGER (THX-1) AS REQUIRED. SEE SHEET PL101-51 FOR TEMPORARY HEAT EXCHANGER (THX-1) LOCATION.
- 9 TIE-IN POINT FOR LOW PRESSURE STEAM TO TEMPORARY HEAT EXCHANGER (THX-1). PLUMBING CONTRACTOR SHALL PIPE LOW PRESSURE STEAM TO TEMPORARY HEAT EXCHANGER (THX-1) AS REQUIRED. SEE SHEET PL101-51 FOR TEMPORARY HEAT EXCHANGER (THX-1) LOCATION.
- (10) TIE-IN POINT FOR CONDENSATE TO TEMPORARY HEAT EXCHANGER (THX-1). PLUMBING CONTRACTOR SHALL PIPE CONDENSATE TO TEMPORARY HEAT EXCHANGER (THX-1) AS REQUIRED. SEE SHEET PL101-51 FOR TEMPORARY HEAT EXCHANGER (THX-1) LOCATION.
- TIE-IN POINT FOR HOT WATER RECIRC. TO 11 TEMPORARY HEAT EXCHANGER (THX-1). PLUMBING CONTRACTOR SHALL PIPE HOT WATER RECIRC. TO TEMPORARY HEAT EXCHANGER (THX-1) AS REQUIRED. SEE SHEET PL-101-51 FOR TEMPORARY HEAT EXCHANGER (THX-1) LOCATION.
- PLUMBING CONTRACTOR SHALL REMOVE EXISTING 12 CONCRETE STAND. PATCH FLOOR TO MATCH EXISTING FLOOR CONDITIONS.
- PLUMBING CONTRACTOR SHALL INSTALL PRESSURE 13> REDUCING STATION (30PSI-7PSI) WHEN INSTALLING STEAM TIE-IN FOR TEMPORARY HEAT EXCHANGER. SEE PL-101-51 FOR LOCATION AND PRESSURE.

- GENERAL NOTES
- PLUMBING CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS.
- 2. ALL FLOOR AND WALL PENETRATIONS SHALL BE SEALED TO MEET FIRE RATINGS.
- 3. ALL HATCHED ITEMS DENOTES RELOCATION OR DEMOLITION.
- 4. SEE SHEET PL-001 FOR SEQUENCE OF CONSTRUCTION.
- 5. PLUMBING CONTRACTOR SHALL COORDINATE INSTALLATION OF TEMPORARY HEAT EXCHANGER (THX-1), RELOCATION OF HYDRONIC PUMPS AS SHOWN ON PL102, DEMOLITION OF EXISTING HEAT EXCHANGER AND INSTALLATION OF NEW HEAT EXCHANGERS HX-1-51 AND HX-2-51.



100% Construction Documents - For Construction



2 3 5

Alexandria Office St. Cloud Office

120 17th Avenue W. 3339 West St. Germain, Suite 250 Alexandria, MN 56308 St. Cloud, MN 56301 (320) 217-5557

Alexandria 525 Broadway Street Alexandria, MN 56308 phone 3 2 0.7 5 9.9 0 3 0 facsimile 3 2 0.7 5 9.9 0 6 2 www.jlgarchitects.com

JLG 11050M

DATE: 01-15-2013

PLUMBING -DEMOLITION PLANS

HOT WATER GENERATORS AS NOTED 656-13-225 BUILDING NO

AS NOTED


CHECKED BY DRAWN


AJF

CAD FILE

XXX LOCATION
ST. CLOUD VA MEDICAL CENTER
PD101-51
ST. CLOUD, MN 56303

DRAWING NO.
PD101-51
DWG.170F 23





GENERAL NOTES

- 1. PLUMBING CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS.
- 2. ALL FLOOR AND WALL PENETRATIONS SHALL BE SEALED TO MEET FIRE RATINGS.
- 3. SEE SHEET PL-001 FOR SEQUENCE OF CONSTRUCTION.
- 4. PLUMBING CONTRACTOR SHALL COORDINATE INSTALLATION OF TEMPORARY HEAT EXCHANGER (THX-1), RELOCATION OF HYDRONIC PUMPS AS SHOWN ON PL102, DEMOLITION OF EXISTING HEAT EXCHANGER AND INSTALLATION OF NEW HEAT EXCHANGERS HX-1-51 AND HX-2-51.

PLAN NOTES

 $\langle 1 \rangle$ TEMPOARARY HEAT EXCHANGER (THX-1) LOCATION.

MANUFACTURER SHALL COORDINATE.

<2>PLUMBING CONTRACTOR SHALL PROVIDE AND INSTALL PRE-MANUFACTURED HEAT EXCHANGER SKID. SKID SHALL BE PRE-PIPE INCLUDING VALVES, GAUGES AND FITTINGS AS SHOWN ON 1/PL501. CONTROLS CONTRACTOR SHALL PROVIDE HEAT EXCHANGER MANUFACTURER REQUIRED FLOW SWITCHES AND TEMPERATURE GAUGES. HEAT EXCHANGER MANUFACTURER SHALL INSTALL FLOW SWITCHES AND TEMPERATURE GAUGES PRIOR TO SHIPMENT. PLUMBING CONTRACTOR, CONTROLS CONTRACTOR AND

	HEAT EXCHANGER SCHEDULE											
UNIT TAG	MFGR.	MODEL	HEAT EXCHANGED (MBH)	FLUID TYPE	FLOW RATE (GPM)	FLUID PD (FT H20)	EWT (°F)	LWT (°F) (BEFORE DRV)	`	FLUID TYPE	PRESSURE (PSI)	FLUID PD (PSI)
HX-1-51	ARMSTRONG	665-DWP-PTW-DMC1-150	3,300	DOMESTIC WATER	50	10	50	140	120	STEAM	7	CONSTANT
HX-2-51	ARMSTRONG	665-DWP-PTW-DMC1-150	3,300	DOMESTIC WATER	50	10	50	140	120	STEAM	7	CONSTANT
NOTES:												

100% Construction Documents - For Construction










STAMP/SEAL: I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.	PLUMBING - FLOOR PLAN, ISOMETRICS & SCHEDULES
SHANE T. JOHNSTON, PE REG. NO. DATE: 01-15-2013	APPROVED: PROJECT DIRECTOR DATE:

HOT WATER GENERATORS PLOT SCALE
AS NOTED
PROJECT NO.
656-13-225 BUILDING NO CHECKED BY DRAWN CAD FILE XXXX ST. CLOUD VA MEDICAL CENTER DRAWING NO. PL 101-51 ST. CLOUD, MN 56303

BUILDING KEY PLAN







GENERAL NOTES


- PLUMBING CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS.
- ALL FLOOR AND WALL PENETRATIONS SHALL BE SEALED TO MEET FIRE RATINGS.
- 3. ALL HATCHED ITEMS DENOTES DEMOLITION.
- SEE SHEET PL-001 FOR SEQUENCE OF CONSTRUCTION.

PLAN NOTES

- PLUMBING CONTRACTOR SHALL REMOVE EXISTING
 ELECTRIC WATER HEATER. PLUMBING CONTRACTOR
 SHALL HIRE A LICENSED ELECTRICAL CONTRACTOR TO
 DISCONNECT AND REMOVE ALL ASSOCIATED ELECTRICAL
 (CONDUIT, CONDUCTORS, DISCONNECTS, ETC.) WITH
 EXISTING WATER HEATER. PROVIDE NEW TYPED PANEL
 DIRECTORY IN EXISTING PANEL AFTER WORK IS
 COMPLETE.
- PLUMBING CONTRACTOR SHALL REMOVE EXISTING DOMESTIC HOT AND COLD WATER PIPE, VALVES, GAUGES AND ASSOCIATED INSULATION AND HANGARS. PLUMBING CONTRACTOR SHALL TIE HOT WATER PIPE INTO NEW HEAT EXCHANGER (HX-1-59 & HX-2-59), SEE PL-101-59. PLUMBING CONTRACTOR SHALL CAP EXISTING COLD WATER PIPE GOING TO EXISTING ELECTRIC WATER HEATER.
- PLUMBING CONTRACTOR SHALL VERIFY EXACT LOCATION OF EXISTING LOW PRESSURE STEAM.
- PLUMBING CONTRACTOR SHALL RELOCATE EXISTING RECIRCULATION PUMP. SEE 2/PL101-59 FOR NEW PUMP LOCATION. PLUMBING CONTRACTOR SHALL HIRE A LICENSED ELECTRICAL CONTRACTOR TO RELOCATE ALL ASSOCIATED ELECTRICAL (CONDUIT, CONDUCTORS, DISCONNECTS, ETC) WITH EXISTING PUMP. EXTEND ALL EXISTING ELECTRICAL CONDUIT, ETC. AS REQUIRED FROM THIS LOCATION TO NEW LOCATION SHOWN ON 2/PL101-59. PROVIDE NEW CONDUCTORS, NO SPLICING IS ALLOWED.
- PLUMBING CONTRACTOR SHALL REMOVE EXISTING PUMP. PLUMBING CONTRACTOR SHALL HIRE A LICENSED ELECTRICAL CONTRACTOR TO REMOVE ALL ASSOCIATED ELECTRICAL (CONDUIT, CONDUCTORS, DISCONNECTS, ETC) WITH EXISTING PUMP. PROVIDE NEW TYPED PANEL DIRECTORY IN EXISTING PANEL AFTER WORK IS COMPLETE. VA HAS FIRST RIGHT OF REFUSAL.

PLAN NOTES

- 1 PLUMBING CONTRACTOR SHALL REMOVE EXISTING DOMESTIC HOT WATER TANK, INSULATION, GAUGES, AND ASSOCIATED MATERIALS.
- 2 PLUMBING CONTRACTOR SHALL REMOVE EXISTING CONDENSATE PIPE, VALVES, CONDENSATE TRAP, AND ASSOCIATED INSULATION AND HANGERS.
- 3 PLUMBING CONTRACTOR SHALL REMOVE EXISTING STEAM PIPE, CONTROL VALVE, AND ASSOCIATED INSULATION AND HANGERS.
- PLUMBING CONTRACTOR SHALL REMOVE EXISTING DOMESTIC HOT WATER PIPE VALVES AND ASSOCIATED INSULATION AND HANGERS.
- 5 PLUMBING CONTRACTOR SHALL REMOVE EXISTING DOMESTIC HOT WATER RECIRC. PIPE, VALVES, AND ASSOCIATED INSULATION AND HANGERS.
- 6 PLUMBING CONTRACTOR SHALL REMOVE EXISTING DOMESTIC COLD WATER PIPE, VALVES, AND ASSOCIATED INSULATION AND HANGERS.
- TIE-IN POINT FOR DOMESTIC HOT WATER TO TEMPORARY HEAT EXCHANGER (THX-1). PLUMBING CONTRACTOR SHALL PIPE DOMESTIC HOT WATER TO TEMPORARY HEAT EXCHANGER (THX-1). SEE SHEET PL101-59 FOR TEMPORARY HEAT EXCHANGER (THX-1) LOCATION.
- 8 TIE-IN POINT FOR DOMESTIC COLD WATER TO TEMPORARY HEAT EXCHANGER (THX-1). PLUMBING CONTRACTOR SHALL PIPE DOMESTIC COLD WATER TO TEMPORARY HEAT EXCHANGER (THX-1) AS REQUIRED. SEE SHEET PL101-59 FOR TEMPORARY HEAT EXCHANGER (THX-1) LOCATION.
- 9 TIE-IN POINT FOR LOW PRESSURE STEAM TO TEMPORARY HEAT EXCHANGER (THX-1). PLUMBING CONTRACTOR SHALL PIPE LOW PRESSURE STEAM TO TEMPORARY HEAT EXCHANGER (THX-1) AS REQUIRED. SEE SHEET PL101-59 FOR TEMPORARY HEAT EXCHANGER (THX-1) LOCATION.
- TIE-IN POINT FOR CONDENSATE TO TEMPORARY HEAT EXCHANGER (THX-1). PLUMBING CONTRACTOR SHALL PIPE CONDENSATE TO TEMPORARY HEAT EXCHANGER (THX-1) AS REQUIRED. SEE SHEET PL101-59 FOR TEMPORARY HEAT EXCHANGER (THX-1) LOCATION.
- PLUMBING CONTRACTOR SHALL UTILIZE EXISTING RECIRC. PUMP DURING TEMPORARY INSTALLATION OF THX-1. SEE SHEET PL101-59 FOR TEMPORARY HEAT EXCHANGER (THX-1) LOCATION. PLUMBING CONTRACTOR SHALL HIRE A LICENSED ELECTRICAL CONTRACTOR TO RELOCATE ASSOCIATED WIRING. AFTER TEMPORARY USAGE OF THX-1 IS COMPLETE REFER TO NOTE #18 ON THIS PLAN FOR FINAL DEMOLITION OF PUMP.
- 12) PLUMBING CONTRACTOR SHALL REMOVE EXISTING HEAT EXCHANGER STAND. PATCH FLOOR TO MATCH FLOOR CONDITIONS.
- 13 PLUMBING CONTRACTOR SHALL REMOVE EXISTING COMPRESSED AIR PIPING, VALVES AND ASSOCIATED CONTROLS. COMPRESSED AIR PIPE SHALL BE DEMO'D BACK TO MAIN AND CAPPED.



100% Construction Documents - For Construction



Alexandria Office St. Cloud Office 3339 West St. Germain, Suite 250 St. Cloud, MN 56301 (320) 762-1290 (320) 217-5557



JLG 11050M

DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

MN 4SHANE T. JOHNSTON, PE REG
DATE: 01-15-2013

PROJECT TITLE
HOT WATER GENERATORS

PLUMBING DEMOLITION PLANS

PROJECT TITLE
HOT WATER GENERATORS

PLOT SCALE
AS NOTED
PROJECT NO.
656-13-225
SCIP

APPROVED: PROJECT DIRECTOR


DATE:
AS NOTED


PROJECT TITLE
HOT WATER GENERATORS

PLOT SCALE
AS NOTED
PROJECT NO.
656-13-225
SCIP

AS NOTED
STJ DRAWN
AJF
XXX

DRAWING NO.
PD101-59
DWG. 20 OF 23





GENERAL NOTES

- 1. PLUMBING CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS.
- 2. ALL FLOOR AND WALL PENETRATIONS SHALL BE SEALED TO MEET FIRE RATINGS.
- 3. SEE SHEET PL-001 FOR SEQUENCE OF CONSTRUCTION.

PLAN NOTES

 $\langle 1 \rangle$ TEMPOARARY HEAT EXCHANGER (THX-1) LOCATION.

(2) PLUMBING CONTRACTOR SHALL PROVIDE AND INSTALL PRE-MANUFACTURED HEAT EXCHANGER SKID. SKID SHALL BE PRE-PIPE INCLUDING VALVES, GAUGES AND FITTINGS AS SHOWN ON 1/PL501 AND 2/PL501. CONTROLS CONTRACTOR SHALL PROVIDE HEAT EXCHANGER MANUFACTURER REQUIRED FLOW SWITCHES AND TEMPERATURE GAUGES PRIOR TO SHIPMENT. PLUMBING CONTRACTOR, CONTROLS CONTRACTOR AND MANUFACTURER SHALL COORDINATE.

(3) CAP EXISTING MEDIUM PRESSURE STEAM.

(4) CAP EXISTING COMPRESSED AIR PIPE AT MAIN.


5 CAP EXISTING DOMESTIC HOT WATER.

6 CAP EXISTING DOMESTIC COLD WATER.

7) RELOCATED EXISTING RECIRC. PUMP.

	HEAT EXCHANGER SCHEDULE											
UNIT TAG	MFGR.	MODEL	HEAT EXCHANGED (MBH)	FLUID TYPE	FLOW RATE (GPM)	FLUID PD (FT H20)	EWT (°F)	LWT (°F) (BEFORE DRV)	`	FLUID TYPE	PRESSURE (PSI)	FLUID PD (PSI)
HX-1-59	ARMSTRONG	665-DWP-PTW-DMC1-150	3,300	DOMESTIC WATER	160	10	50	160	120	STEAM	7	CONSTANT
HX-2-59	ARMSTRONG	665-DWP-PTW-DMC1-150	3,300	DOMESTIC WATER	160	10	50	160	120	STEAM	7	CONSTANT


NOTES:
1. SEE DETAIL 1/PL501.




100% Construction Documents - For Construction



2 3 5




Alexandria, MN 56308 St. Cloud, MN 56301



MP/SEAL:	DRAWING TITLE	PROJECT TITLE HOT WATER GENERATORS	DATE 01.15.2013
REBY CERTIFY THAT THIS PLAN, SPECIFICATION, REPORT WAS PREPARED BY ME OR UNDER MY ECT SUPERVISION, AND THAT I AM A DULY ENSED PROFESSIONAL ENGINEER UNDER THE	PLUMBING - FLOOR PLAN, ISOMETRIC & SCHEDULES		PLOT SCALE AS NOTED
/S OF THE STATE OF MINNESOTA.			PROJECT NO. 656-13-225 SCIP
Lane T. Johan MN 44935	APPROVED: PROJECT DIRECTOR DATE:	BUILDING No CHECKED BY DRAWN AS NOTED STJ AJF	CAD FILE
ANE T. JOHNSTON, PE REG. NO.		7.01	
TE: 01-15-2013		ST. CLOUD VA MEDICAL CENTER ST. CLOUD, MN 56303	DRAWING NO. PL101-59 DWG. 21 OF 23





ADJUSTABLE ROLLER HANGER

ABOVE 2" DIA. PIPE

2" DIA. & SMALLER

VERTICAL

INSTALLATION OF THERMOMETER WELLS

5 RECEIVER CONDENSATE UNIT DETAIL

100% Construction Documents - For Construction



TYPICAL PIPE HANGER DETAIL






	DRAWING TITLE
STAMP/SEAL:	
I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.	PLUMBING DETAILS
Fare T. Johlan MN 44935	APPROVED: PROJECT DIRECTOR
SHANE T. JOHNSTON, PE REG. NO.	
DATE: 01-15-2013	


	PLUMBING DETAILS	HOT WATER GENERATORS	01.15.2013 PLOT SCALE AS NOTED
			PROJECT NO. 656-13-225 SCIP
-	APPROVED: PROJECT DIRECTOR DATE:	AS NOTED CHECKED BY AJF	CAD FILE XXX
		ST. CLOUD VA MEDICAL CENTER ST. CLOUD, MN 56303	DRAWING NO. PL501 DWG.220F 23


GENERAL NOTES

PLAN NOTES



STEAM TO HOT WATER HEAT EXCHANGER FOR DOMESTIC HOT WATER (TYPICAL FOR EACH BUILDING)





- 1. CONTROLS CONTRACTOR SHALL FURNISH FLOW SWITCHES AND TEMPERATURE SENSOR WELLS TO HEAT EXCHANGER SKID MANUFACTURER FOR INSTALLATION AT THE FACTORY.
- 2. HEAT EXCHANGER SKID MANUFACTURER SHALL FURNISH AND INSTALL HEAT EXCHANGER MOTORIZED ISOLATION VALVES. VALVES SHALL BE WIRED TO THE BAS CONTROL PANEL IN THE FIELD BY THE CONTROLS CONTRACTOR.
- 3. CONTROLS CONTRACTOR SHALL FURNISH HEAT EXCHANGER STEAM CONTROL VALVES TO THE MECHANICAL CONTRACTOR FOR FIELD INSTALLATION. VALVES SHALL BE WIRED TO THE BAS CONTROL PANEL IN THE FIELD BY THE CONTROLS CONTRACTOR.

VAMC St Cloud - DHW HX Upgrades Project - POINTS LIST

TAG	DESCRIPTION	TYPE	ALARM	GRAPHIC	TREND	NOTES
HX1V1-O	Heat Exchanger 1 - Steam Valve Output	AO		X		Fail Closed
HX1LW-T	Heat Exchanger 1 - Leaving Water Temp	AI	Х	X	Х	HIGH LIMIT ALARMS
DHWF1-S	Domestic Hot Water HX-1 Flow Status	BI	Х	X	Х	
HX1ISO-C	Heat Exchanger 1 - Iso Valve Command	ВО		X	Х	2-way Isolation Valve - Fail Clo
HX2V1-O	Heat Exchanger 2 - Steam Valve Output	AO		X		Fail Closed
HX2LW-T	Heat Exchanger 2 - Leaving Water Temp	AI	Х	X	Х	HIGH LIMIT ALARMS
DHWF2-S	Domestic Hot Water HX-2 Flow Status	BI	Х	X	X	
HX2ISO-C	Heat Exchanger 2 - Iso Valve Command	ВО		X	Х	2-way Isolation Valve - Fail Clo
FUTURE	RESERVED	ВО				Future Lead Pump Command
FUTURE	RESERVED	BI				Future Lead Pump Status
FUTURE	RESERVED	ВО				Future Standby Pump Comma
FUTURE	RESERVED	BI				Future Standby Pump Statu
DHWST-SP	DHW Supply Temp Setpoint	AD		X	Х	
DHWSYS-EN	Domestic Hot Water System Enable	BD		X	Х	
DHWST-HL	DHW Supply Temp Hi Limit	AD		X		
DWR-T	Domestic Water Return Temp	AI		Х	Х	
DHWS-T	Domestic Hot Water Supply Temp	AI	Х	X	Х	HIGH & LOW LIMIT ALARMS

SECTION 23 09 23

DIRECT-DIGITAL CONTROL SYSTEM FOR HVAC.

PART 1- SEQUENCES OF OPERATION

- 1.1 STEAM TO HOT WATER HEAT EXCHANGER FOR DOMESTIC HOT WATER
- A. SYSTEM ENABLE: THE DOMESTIC HOT WATER HEATING SYSTEM WILL AUTOMATICALLY START WHEN THE SYSTEM ENABLE IS "ON". WHEN THE SYSTEM ENABLE IS "OFF" THE DOMESTIC HOT WATER HEATING SYSTEM WILL BE DISABLED.
- B. <u>HEAT EXCHANGER CONTROL:</u> THIS SYSTEM CONSISTS OF TWO (2) STEAM HEAT EXCHANGERS (HX). BOTH HEAT EXCHANGERS WILL OPERATE SIMULTANEOUSLY. EACH HX WILL HAVE AN ISOLATION VALVE ON THE WATER SIDE THAT WILL BE CLOSED WHEN THE HX IS INACTIVE AND OPEN WHEN IT IS ACTIVE. EACH UNIT WILL HAVE A LOW PRESSURE STEAM INLET VALVE(OPEN/CLOSE) THAT WILL BE CLOSED WHEN THE HX IS INACTIVE AND OPEN 100% WHEN IT IS ACTIVE (CONTROL VALVE SHALL BE IN SEQUENCE WITH WATER SIDE ISOLATION VALVE). THE VALVES WILL NOT BE ALLOWED TO OPERATE UNLESS THE HX IS ACTIVE AND FLOW THROUGH THE HX IS PROVEN (VIA THE FLOW SWITCH). IF THE DOMESTIC HOT WATER SUPPLY TEMPERATURE IS MORE THAN 5 DEG F (ADJ) BELOW SETPOINT FOR MORE THAN 10 MINUTES (ADJ) A CRITICAL "PRIMARY DOMESTIC HOT WATER HEAT EXCHANGER FAILURE" ALARM WILL BE GENERATED.
- C. HIGH TEMPERATURE SAFETY: WHEN THE WATER TEMPERATURE, AS MEASURED BY THE LEAVING WATER SENSOR AT EACH HX OR THE SENSOR LOCATED ON THE COMMON SUPPLY PIPING, EXCEEDS THE HOT WATER SUPPLY TEMPERATURE HIGH LIMIT (160 DEGF — FULLY ADJUSTABLE) A CRITICAL "HIGH DOMESTIC WATER TEMPERATURE" ALARM WILL BE GENERATED AND THE STEAM VALVES WILL BE SHUT DOWN — A MANUAL RESET WILL BE REQUIRED TO RESTART THE SYSTEM.

END OF SECTION

100% Construction Documents - For Construction



 2
 5



HOT WATER GENERATORS PLUMBING -CONTROLS SEQUENCE I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA. PLOT SCALE

AS NOTED AS NOTED STJ AJF XXX DATE: 01-15-2013 ST. CLOUD VA MEDICAL CENTER PL801
ST. CLOUD, MN 56303



Alexandria Office St. Cloud Office

Alexandria, MN 56308 St. Cloud, MN 56301

120 17th Avenue W. 3339 West St. Germain, Suite 250

(320) 217-5557