



Plate (Ivory) part number is dependent on need: (Leviton Part numbers below)

- 1 Port = 41080-1TP
- 2 Port = 41080-2TP
- 3 Port = 41080-3TP
- 4 Port = 41080-4TP
- 5 Port = N/A
- 6 Port = 41080-6TP

Cable will be Category 5e Plenum or better color coded commensurate with wall plate port (e.g. white wall plate port = white cable run, yellow wall plate port = yellow cable run, etc.)

**Data line installation Wire pair pinout** configuration will be completed using **T568A** standard. Installations will be appropriately labeled, using existing numbering scheme, at both the wall plate and data closet patch panel ends to ensure individual identification of lines (Questions regarding labeling scheme can be referred to the Facility Chief Information Officer, Telecommunications Specialist or Contract Telecommunications Technician as appropriate).

**Cable certification will be performed and results provided to contracting officer for reference by Office of Information and Technology, Service Delivery and Engineering Field Office Staff.**