



C



E

GENERAL NOTES

- A. GUARDRAILS AT MODULAR RETAINING WALLS ARE NOT SHOWN IN ELEVATION FOR CLARITY.
- B. PROVIDE ARCHITECTURAL PRECAST ENCLOSURE AT MAIN BUILDING CORE.
- C. WHERE GFRG TURNS A CORNER PROVIDE CORNER UNIT. (IE DO NOT HAVE MITERED JOINTS AT CORNER)
- D. PROVIDE RETURN CORNERS ON ARCHITECTURAL PRECAST PANELS AT CORE. DO NOT MITER CORNERS
- E. CURTAIN WALL SHALL BE VERTICALLY CAPTURED WITH STRUCTURAL SILICONE HORIZONTALS
- F. PROVIDE EXTERIOR DUROPLEX ON ALL CMU WALLS

KEYED NOTES

- 1 WHITE MEMBRANE ROOF SYSTEM ADHERED DIRECTLY TO CONCRETE ROOF PANELS
- 2 GFRG FASCIA
- 3 GFRG SOFIT/FASCIA UNIT. PROVIDE SEAMLESS CORNER UNITS TYPICAL ALL 4 SIDES
- 4 PROVIDE MEMBRANE ROOF SYSTEM OVER COLD FORMED METAL FRAMING SEALED WEATHER TIGHT TO GFRG PERIMETER SLOPED TO CONCEALED GUTTER.
- 5 CONCEALED GUTTER SLOPE TO ALUMINUM DOWNSPOUTS ON EAST SIDE OF CORE.
- 6 12" X 24" PRECAST CONCRETE COLUMN T MATCH PRECAST FINIS
- 7 PRECAST FIN AND GFRG BRIS SOLEIL REFER TO ALTERNATES 2
- 8 PRECAST FIN AND BEYOND ON SOUTH ELEVATION
- 9 MODULAR BLOCK RETAINING WALL BASIS OF DESIGN VERSA LOCK MOSAIC SANDSTONE
- 10 METAL LOUVER
- 11 ALUMINUM DOWNSPOUT
- 12 MODULAR BLOCK RETAINING WALL
- 13 CONCEALED MEMBRANE GUTTER SHED TO CONCEALED GUTTER IN LOW COLD FORM SUPPORTED MEMBRANE ROOF.
- 14 THERE ARE TWO LIGHT WALL. ONE ON EACH SIDE OF THE CENTRAL DRIVE RAMP. IT IS NECESSARY TO PROVIDE A GUARD RAIL AT OPENINGS IN LIGHT WALL. PROVIDE CONTINUOUS CABLE GUARD RAILS AT BOTH LIGHT WALLS. CONTRACTORS OPTION TO PROVIDE INDIVIDUAL PAINTED GALVANIZED STEEL GUARDS AT EACH OPENING.
- 15 SLOPE TO DRAIN MAINTAINING 7"-9" CLEARANCE
- 16 HEIGHT OF LIGHT WALLS TO ALIGN WITH TOP OF BARRIER BEAM THIS LOCATION
- 17 CURTAIN WALL

2 LONGITUDINAL BUILDING SECTION
3/32" = 1'-0"

1 WEST ELEVATION
3/32" = 1'-0"

9		
8		
7		
6		
5		
4		
3		
2		
1		
Revisions		Date

CONSULTANTS:

ERIKSON ENGINEERING
CIVIL ENGINEERING
145 COMMERCE DRIVE
GRAY SLAKE, ILLINOIS 60030

ARCHITECT/ENGINEERS:

CANNON
DESIGN

1100 Clark Avenue
St. Louis, Missouri 63102
T: 314.241.6250
F: 314.241.2570

Baltimore ■ Boston ■ Buffalo ■ Calgary ■ Chicago
Houston ■ Los Angeles ■ Mumbai ■ New York ■ Phoenix
St. Louis ■ San Francisco ■ Shanghai ■ Toronto
Vancouver ■ Victoria ■ Washington DC

Drawing Title

WEST ELEVATIONS AND
LONGITUDINAL BUILDING SECTION

Approved: Project Director

Project Title

VA MEDICAL CENTER
FAYETTEVILLE ARKANSAS
PARKING GARAGE

Location 1100 NORTH COLLEGE AVENUE
FAYETTEVILLE, AR 72703

Date
APRIL 19, 2013

Checked

Drawn
MJZ

Project No. 003640.05

Building No.

Drawing No.

A0304

OFFICE OF
CONSTRUCTION AND
FACILITIES
MANAGEMENT

Department of
Veterans Affairs