

1 1-A2 1st Floor Plan

SCALE: 1/8" = 1'-0"

PROJECT NORTH



4 1-A2 Enlarged Plan

SCALE: 1/4" = 1'-0"



5 1-A2 Counter Elevation

SCALE: 1/4" = 1'-0"



6 1-A2 Enlarged Plan

SCALE: 1/4" = 1'-0"



Type A

Partition Types

SCALE 1 1/2"=1'-0"

Concrete Stain Application:

CONCRETE TO BE STAINED ONLY AFTER INFILL/PATCH OF EXIST'G CONCRETE FLR.

1. Concrete stain should be applied on to a dry surface where moisture content should not exceed 3lbs/1000 sq ft of surface (ASTM F710).
2. Air, surface and material temperature must be between 50 degrees and 90 degrees F and at least 5 degrees F above the dew point during and for 24 hours after application.
3. Do not apply if rain is expected in 12 hours following the application.
4. Stir stain thoroughly before and during application.
5. A minimum two coats is required. Apply with brush, roller or spray.
6. When using more than one container, intermix all containers together to ensure color uniformity.
7. Prior to applying the first coat, dry-sweep the concrete with a stiff broom or shop vacuum to remove all surface latent.
8. First coat: apply first coat evenly, working in one direction. Allow to dry at least 2 hours before applying second coat.
9. Second coat: apply second coat crosswise to the first coat. Two coats of Concrete stain water based are usually sufficient. However, extremely porous surfaces may require a third coat for a uniform appearance. If more than two coats are applied a Slip-Resistive Additive is to be used.
10. Allow 2 hours between coats. Allow 72 to 96 hours drying conditions before using the surface for traffic.



2 1-A2 2nd Floor Plan

SCALE: 1/8" = 1'-0"

PROJECT NORTH



KEY PLAN

PROJECT NORTH

100% SUBMISSION
FOR CONSTRUCTION
MARCH 27th, 2013

Revisions	Date

Project Lead

Northeast Infrastructure LLC
100 4th Street, Suite 24
Honesdale, PA 18431
570.253.2245 570.251.9551 fax
www.neinfra.com
Service Disabled
Veteran Owned
Small Business

Professional Seal

REGISTERED ARCHITECT COMMONWEALTH OF PENNSYLVANIA ROBERT J. HILLER

Architect

HILLER ARCHITECTURAL DESIGN
Architecture
Space Planning
Interior Design
45 North Front Street Milton, PA 17847
Tel 570.742.9352 Fax 570.742.9379
www.hillerdesart.com

Electrical

ENGINEERING GROUP LTD.
ARRIS
67 PUBLIC SQUARE
SUITE 725
WILKES-BARRE, PA 18701
PHONE: 570/825-7760
FAX: 570/825-9001
WEB SITE: WWW.ARRISENG.COM

Drawing Title
1ST & 2ND FLOOR NEW WORK PLANS, ENLARGED PLANS, PARTITION TYPES & SCHEDULES

Facility Project Name

Project Title
FCA UPGRADE
AUDITORIUM, B92

Building Number 92
Checked D.ECK
Drawn B.ERB
Location BATH, NEW YORK

Date 11/29/2012
Project No. 528A6-12-606

DRAWING NO.
DRAWING
A-2
DWG. 4 OF 11

VA