

**Question for Building 2 Front Side Replacement
VA246-13-B-4155**

1. The Architectural drawings page 5 call out the sizes for 3 window types A1, A2 and A15. This page does not give the size of window types G, E, F and D.
The dimensions for E and F are located in the detail in upper left hand corner of sheet 5.
The dimensional openings of the "G" windows are 4'-0" X 5'-6". It is the responsibility of the contractor to measure the windows for replacement.
The "D" windows are two A2 windows- See Revised drawing Sheet 5 for detail.
2. Page 1 of the architectural general notes call out A2 type window as the "corner windows", but on the floor plan they are window type E, is this correct? In the same paragraph it calls out for room 2106 to have a corner window, I am assuming this is really to be room 2016, please advise?
 - See the detail on sheet 5 for the Windows "E" these consist of A2 window connected with mullions.
 - The room number should be 2016
3. On sheet #2 the second floor plan and the third floor plan in the bottom right hand corner 2 windows from each floor are missing window types, are these windows not to be included in the proposal?
These windows should be A1 on both 2nd and 3rd floor. See revised drawings
4. Same question as above but in reference to the third floor plan top right corner?
These windows should be A1 on both 2nd and 3th floor. See revised drawings
5. Page 3 and page 4 has the 5th floor shown, I am assuming this is not correct?
The page 4 should not have had the 5th floor shown. See revised drawing.
6. Room 5014 is it to be a D type window or an A as shown.
Should be a "D". See revised drawing.
7. On the fifth floor plan the corner windows in rooms 5007 and 5021 are shown to be window type A1, shouldn't they be type?
They should be "E" windows. See Revised Drawing
8. I do not see where it is referenced to which windows are to get detention screens, please advise?
The drawings indicate detention screen. This was a mistake because they were removed during the previous window replacement. There are no detention screens to be installed.
9. Will patients and VA personnel be in the area while the windows are being changed.
No, rooms will be vacated during removal and installation.

**Question for Building 2 Front Side Replacement
VA246-13-B-4155**

10. How many rooms with the VA be providing at one time?

That will be determined after award and start up to see how many the contractor can do in a day, and also what the staff in the areas will allow. This will vary from day to day.