

1. Building 101 hallway going to Emergency Department and Intensive Care Unit

Card Reader by Security Vendor

Each Door to Have:

- 3 Each Fire Rated Hinges (Stamped) 1 and ½ Hr Rating
- 1 Each Fire Rated Panic Hardware (Labeled) 1 and ½ Hr Rating
- 1 Each Top and Bottom Surface Mounted Fire Rated Vertical Rods (Labeled) 1 and ½ Hr Rating
- 1 Each Fire Rated Closer (Labeled) 1 and ½ Hr Rating
- 1 Each Overlapping Astragal

Door Style/ Function: Doors will be steel fire rated and have visible fire rated seal on door. Doors locked and operated from inside. Doors will be bidirectional (LHRB) and operated by employee card reader, or buzzer system that allows visitors access through police/security permission.

2. Building 1 Stairwell Door Ground Floor Across From Elevators

Door to Have:

- 3 Fire Rated Hinges (Stamped) 1 and ½ Hr Rating
- 1 Fire Rated Passage Cylindrical Hardware (Stamped) 1 and ½ Hr Rating
- 1 Fire Rated Closer (Labeled) 1 and ½ Hr Rating

Door Style/ Function: Door will be steel fire rated and have visible fire rated seal on door. Door will be RHRB.

3. Building 1 Addition of New Double Doors Outside of Elevator Lobby

Doors to Have:

- 3 Each Fire Rated Hinges (Stamped) 1 and ½ Hr Rating
- 1 Each Fire Rated Panic Hardware (Labeled) 1 and ½ Hr Rating

- 1 Each Top and Bottom Surface Mounted Fire Rated Vertical Rods (Labeled) 1 and ½ Hr Rating
- 1 Each Fire Rated Closer (Labeled) 1 and ½ Hr Rating
- 1 Each Overlapping Astragal

Door Function: Doors will be steel fire rated and have visible fire rated seal on doors. Doors will be bidirectional (LHRB) and be operated off of magnetic hold opens hard lined into fire alarm system. Doors will remain open until a fire alarm is alerted.

4. Building 1 Fourth Floor B Side Hospice

Doors to Have:

- 3 Each Fire Rated Hinges (Stamped) 1 and ½ Hr Rating
- 1 Each Fire Rated Panic Hardware (Labeled) 1 and ½ Hr Rating With Classroom Key Access
- 1 Each Top and Bottom Surface Mounted Fire Rated Vertical Rods (Labeled) 1 and ½ Hr Rating
- 1 Each Fire Rated Closer (Labeled) 1 and ½ Hr Rating
- 1 Coordinator
- 1 Astragal

Door Style/ Function: Doors will be steel fire rated and have visible fire rated seal on doors. Doors will be unidirectional (LHRB/RHRB) and operate off either magnetic hold opens or hydraulic fire alarm system. Doors will also have half lite windows, and must latch at top and bottom.

5. Building 1 Fourth Floor A Side

Doors to Have:

- 3 Each Fire Rated Hinges (Stamped) 1 and ½ Hr Rating
- 1 Each Fire Rated Panic Hardware (Labeled) 1 and ½ Hr Rating With Classroom Key Access

- 1 Each Top and Bottom Surface Mounted Fire Rated Vertical Rods (Labeled) 1 and ½ Hr Rating
- 1 Each Fire Rated Closer (Labeled) 1 and ½ Hr Rating
- 1 Coordinator
- 1 Astragal

Door Style/Function: Doors will be steel fire rated and have visible fire rated seal on doors. Doors will be unidirectional (LHRB/RHRB) and operate off magnetic hold opens hard lined into fire alarm system. Doors will have half lite windows, and must latch at top and bottom.

6. Building 17 Stair Tower

Door to Have:

- 3 Fire Rated Hinges (Stamped) 1 and ½ Hr Rating
- 1 Fire Rated Panic Hardware (Labeled) 1 and ½ Hr Rating With Storeroom Key Access
- 1 Fire Rated Closer (Labeled) 1 and ½ Hr Rating

Door Style/Function: Door will be metal fire rated and have visible seal on door. Door is an exterior door (RHRB) and will operate off panic device for exiting and key access (storeroom) for entrance.

7. Building 18 Second Floor

Doors to Have:

- 3 Each Fire Rated Hinges (Stamped) 1 and ½ Hr Rating
- 1 Each Fire Rated Panic Hardware (Labeled) 1 and ½ Hr Rating With Classroom Access
- 1 Each Top and Bottom Surface Mounted Fire Rated Vertical Rods (Labeled) 1 and ½ Hr Rating
- 1 Each Fire Rated Closer (Labeled) 1 and ½ Hr Rating
- 1 Coordinator
- 1 Astragal

Door Style/Function: Doors will be steel fire rated and have visible seal on door. Doors will be unidirectional (LHRB/RHRB) and operate off of magnetic hold opens hard lined into fire alarm system. Doors will have half lite windows and must latch at top and bottom.

Manufacturers for Hardware:

Panic Hardware: Stanley Precision, Von Duprin or anything compatible

Closers: LCN or anything compatible

Hinges: Stanley or anything compatible