

SECTION 26 56 00
EXTERIOR LIGHTING**PART 1 - GENERAL****1.1 DESCRIPTION**

This section specifies the furnishing, installation, and connection of exterior luminaries, controls, poles and supports.

1.2 RELATED WORK

- A. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: General electrical requirements and items that are common to more than one section of Division 26.
- B. Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS: Conduits, fittings, and boxes for raceway systems.
- C. Section 26 05 21, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES (600 VOLTS AND BELOW): Low voltage power and lighting wiring.
- D. Section 26 05 41, UNDERGROUND ELECTRICAL CONSTRUCTION: Underground handholes and conduits.
- E. Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS: Requirements for personnel safety and to provide a low impedance path for possible ground fault currents.

1.3 SUBMITTALS

- A. Submit in accordance with Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.
- B. Shop Drawings:
 - 1. Sufficient information, clearly presented, shall be included to determine compliance with drawings and specifications.
 - 2. Include electrical ratings, dimensions, mounting, details, materials, required clearances, terminations, wiring and connection diagrams, photometric data, ballasts, poles, luminaries, lamps and controls.
- C. Manuals: Two weeks prior to final inspection, submit four copies of operating and maintenance manuals to the Resident Engineer. Include technical data sheets, wiring and connection diagrams, and information for ordering replacement parts.
- D. Certifications: Two weeks prior to final inspection, submit four copies of the following to the Resident Engineer:
 - 1. Certification that the materials are in accordance with the drawings and specifications.

2. Certification, by the Contractor, that the complete installation has been properly installed and tested.

1.4 APPLICABLE PUBLICATIONS

Publications listed below (including amendments, addenda, revisions, supplements and errata) form a part of this specification to the extent referenced. Publications are referenced in the text by the basic designation only.

A. Aluminum Association Inc. (AA):

AAH35.1-2006Alloy and Temper Designation Systems for Aluminum

B. American Concrete Institute (ACI):

318-2005Building Code Requirements for Structural Concrete

C. American National Standards Institute (ANSI):

C81.61-2005Electrical Lamp Bases

D. American Society for Testing and Materials (ASTM):

A123/A123M-2002Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products

A153/A153M-2001.....Zinc Coating (Hot-Dip) on Iron and Steel Hardware - AASHTO No.: M232

B108-03a -2003Aluminum-Alloy Permanent Mold Castings

E. Illuminating Engineering Society of North America (IESNA)

HB-9-2000.....Lighting Handbook

RP-8-2000 (R-2005).....Roadway Lighting

F. National Electrical Manufacturers Association (NEMA):

C78.43-2005Electric Lamps - Single-Ended Metal-Halide Lamps

C78.1381-1998.....(R 1997) Electric Lamps - 70-Watt M85 Metal-Halide Lamps

C82.4-2002Ballasts for High-Intensity-Discharge and Low-Pressure Sodium Lamps (Multiple-Supply Type)

C136.17-2005Roadway Lighting Equipment - Enclosed Side-Mounted Luminaries for Horizontal-Burning High-Intensity-Discharge Lamps

G. National Fire Protection Association (NFPA):

70-2005National Electrical Code (NEC)

H. Underwriters Laboratories, Inc. (UL):

496-2004Edison-Base Lamp holders

- 773-1995.....Plug-in, Locking Type Photo controls, for Use
with Area Lighting
- 773A-2006Non-industrial Photoelectric Switches for
Lighting Control
- 1029-1994.....High-Intensity-Discharge Lamp Ballasts
- 1598-2004Luminaries

1.5 DELIVERY, STORAGE, AND HANDLING

Poles: Do not store poles on ground. Store poles so they are at least 305 mm (one foot) above ground level and growing vegetation. Do not remove factory-applied pole wrappings until just before installing pole.

PART 2 - PRODUCTS

2.1 MATERIALS AND EQUIPMENT

Materials and equipment shall be in accordance with NEC, UL, ANSI, and as shown on the drawings and specified.

2.2 POLES

A. General:

1. Poles shall be square aluminum as shown on the drawings, and as specified. Finish shall be as specified on the drawings.
2. The pole and arm assembly shall be designed for wind loading of 161 km/hr (100 miles per hour), with an additional 30 percent gust factor, supporting luminaire(s) having the effective projected areas indicated. The effective projected area of the pole shall be applied at the height of the pole base as shown on the drawings.
3. Poles shall be anchor-bolt type designed for use with underground supply conductors. Poles shall have oval-shaped handhole having a minimum clear opening of 65 by 125 mm (2.5 by 5 inches). Handhole cover shall be secured by stainless steel captive screws.
4. Provide a steel-grounding stud opposite hand hole openings.
5. Provide a base cover matching the pole in material and color to conceal the mounting hardware pole-base welds and anchor bolts.
6. Hardware: All necessary hardware shall be 300 series stainless steel.

B. Types:

1. Aluminum Poles: Manufactured of corrosion resistant AA AAH35.1 aluminum alloys conforming to AASHTO LTS-4 for Alloy 6063-T6 or Alloy 6005-T5 for wrought alloys, and Alloy 356-T4 (3,5) for ASTM B108-03 cast alloys. Poles shall be seamless extruded or spun

seamless type. Provide a pole grounding connection designed to prevent electrolysis when used with copper ground wire. Base covers for aluminum poles shall be cast from 356-T6 aluminum alloy in accordance with ASTM B108-03.

2.3 FOUNDATIONS FOR POLES

- A. Foundations shall be cast-in-place concrete.
- B. Foundations shall support the effective projected area of the specified pole, arm(s), and luminaire(s) under wind conditions previously specified in this section.
- C. Place concrete in spirally wrapped treated paper forms for round foundations, and construct forms for square foundations.
- D. Rub-finish and round all above-grade concrete edges to approximately 6 mm (1/4 inch) radius.
- E. Concrete shall have 3000 psi minimum 28 day compressive strength.
- F. Anchor bolt assemblies and reinforcing of concrete foundations shall be as shown on the drawings and meet ACI 318. Anchor bolts shall be in a welded cage or properly positioned by the tie wire to stirrups.
- G. Prior to concrete pour, install a copperclad steel ground rod, not less than 19 mm (3/4-inch) diameter by 3000 mm (10 feet) long, below each foundation. Drive the rod vertically under the foundation so not less than 1800 mm (6 feet) of rod is in contact with the earth. Remainder of rod may be in the concrete pour. Where rock or layered rock is present, drill a hole not less than 50 mm (2 inches) in diameter and 1800 mm (6 feet) deep, backfill with tamped fine sand and drive the rod into the hole. Bond the rod to the pole with not less than number 6 AWG bare copper wires. The method of bonding shall be approved for the purpose.

2.4 LUMINAIRES

- A. UL 1598 and NEMA C136.17. Luminaries shall be weatherproof, heavy duty, outdoor types designed for efficient light utilization, adequate dissipation of lamp and ballast heat and safe cleaning and relamping.
- B. IESNA HB-9 and RP-8 light distribution pattern types shall be as shown on the drawings.
- C. Incorporate ballasts in the luminaire housing except where otherwise shown on the drawings.
- D. Lenses shall be frame-mounted heat-resistant, borosilicate glass. Attach the frame to the luminaire housing by hinges or chain. Use heat

and aging resistant resilient gaskets to seal and cushion lenses and refractors in luminary doors.

- E. Lamp sockets for high intensity discharge (H.I.D) fixture shall have locking type porcelain enclosures in conformance to the applicable requirements of ANSI C81.61 and UL 496.
- F. Pre-wire internal components to terminal strips at the factory.
- G. Bracket mounted luminaries shall have leveling provisions and clamp type adjustable slip-fitters with locking screws.
- H. Materials shall be rustproof. Latches and fittings shall be non-ferrous metal.
- I. IESNA Cutoff Category: full-cutoff.

2.5 LAMPS

- A. Install the proper lamps in every luminaire installed.
- B. Lamps to be general-service, outdoor lighting types.
- C. Metal-Halide Lamps: NEMA C78.43 or NEMA C78.1381
- D. Compact Fluorescent Lamps: Per Section 26 51 00 INTERIOR LIGHTING.
- E. Mercury vapor lamps shall not be used.

2.6 BALLASTS

- A. High Intensity Discharge Ballasts: High efficiency, high power factor, copper-wound constant wattage type and shall meet the requirements of UL 1029 and NEMA C82.4.
 - 1. Ballasts shall operate the discharge lamp of the type, wattage, and voltage shown on the drawings.
 - 2. Ballasts shall have individual overcurrent protection (inline fuse holder) as recommended by the ballast manufacturer.
 - 3. Ballasts shall be capable of providing reliable starting of the lamps at minus 30 degrees C.
 - 4. Open-circuit operation shall not reduce the average life.
- B. Compact Fluorescent Ballasts: Per Section 26 51 00 INTERIOR LIGHTING.
- C. Locate protective devices for ballasts to be accessible if the devices are not integral with ballasts.
- D. Each ballast shall operate not more than one lamp except where otherwise shown on the drawings.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install lighting in accordance with the NEC, as shown on the drawings, and in accordance with manufacturer's recommendations.
- B. Poles:

1. Provide pole foundations with galvanized steel anchor bolts, threaded at the top end and bent 1.57 rad 90 degrees at the bottom end. Provide galvanized nuts, washers, and ornamental covers for anchor bolts. Thoroughly compact backfill with compacting arranged to prevent pressure between conductor, jacket, or sheath and the end of conduit. Adjust poles as necessary to provide a permanent vertical position with the bracket arm in proper position for luminaire location.
 2. After the poles have been installed, shimmed and plumbed, grout the spaces between the pole bases and the concrete base with non-shrink concrete grout material. Provide a plastic or copper tube, of not less than 9 mm (3/8-inch) inside diameter, through the grout tight to the top of the concrete base for moisture weeping.
- C. Foundation Excavation: Depth shall be as indicated. Dig holes large enough to permit the proper use of tampers to the full depth of the hole. Place backfill in the hole in 150 mm (6 inch) maximum layers and thoroughly tamp. Place surplus earth around the pole in a conical shape and pack tightly to drain water away.

3.2 GROUNDING

Ground noncurrent-carrying parts of equipment including metal poles, luminaries, mounting arms, brackets, and metallic enclosures as specified in Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS. Where copper grounding conductor is connected to a metal other than copper, provide specially treated or lined connectors suitable and listed for this purpose.

- - - E N D - - -