











SITE SURFACE REMOVAL INDEX				
Approximate Quantity	SURFACE Unit	MINIMUM DEPTH OF REMOVAL (INCHES)	Symbol	Description
1750	SF	FULL REMOVAL		CONCRETE SIDEWALK
350	LF	FULL REMOVAL		GRANITE CURB
16,616	SF	6		ASPHALT
250	SF	36		GRASS AND TOPSOIL
650	SF	72		LOOSE SOIL AND DEBRIS
950	LF	FULL REMOVAL		EXISTING FENCE, POSTS AND CONCRETE FOOTERS
106	SF	12		ROUNDED GRAVEL
106	SF	FULL REMOVAL		ALLEN BLOCK WALL

TRENCHING DATA					
TRENCH #	APPROXIMATE MAX. DEPTH BELOW GRADE	APPROXIMATE WIDTH	UTILITY ADDED & DRAWING REFERENCE	APPROXIMATE CUT VOLUME (CY)	NOTES
1	4'-0"	3'-6"	1) 4X4" GRS CONDUIT COMMUNICATION DUCT BANK PER DRAWING ES-100	87	CONTRACTOR SHALL ENSURE THAT SERVICE ROAD REMAINS OPEN DURING ALL WEEKDAYS DURING CONTRACT PERFORMANCE PERIOD. ALL WORK ON TRENCH ONE SHALL BE DURING WEEKEND HOURS. UTILIZE ROAD PLATE TO ENSURE TRENCH IS COVERED DURING WEEKDAYS AND USABLE BY TRAFFIC. INCLUDING TRACTOR TRAILER DELIVERY TRUCKS.
2	6'-0"	6'-0"	1) 4X4" GRS CONDUIT COMMUNICATION DUCT BANK PER DRAWING ES-100. 2) 2X1-1/2" GRS CONDUIT COMMUNICATION DUCT BANK PER DRAWING ES-100. 3) 2X1-1/2" GRS CONDUIT POWER DUCT BANK PER DRAWING ES-100	209	1) EXCAVATE WITH CAUTION NEAR EXISTING BUILDING SERVICE FEEDERS. VERIFY UTILITIES BEFORE STARTING EXCAVATION. 2) AFTER INSTALLATION OF UTILITIES INDICATED, BACKFILL TRENCH PER 9/GS-103.
3	7'-0"	4'-0"	1) 4" SCR30 DRAIN PIPE AND CLEANOUTS PER DRAWING PS-100	70	1) TAKE CARE NOT TO DISTURB EXISTING SEWER AND WATER MAINS WHILE EXCAVATING EXCEPT WHERE CALLED OUT FOR REMOVAL. 2) AFTER INSTALLATION OF UTILITIES INDICATED, BACKFILL TRENCH PER PER 8/GS-103.
4	4'-0"	4'-0"	1) 4X1-1/2" GRS CONDUIT POWER DUCT BANK PER DRAWING ES-100. 2) 2X1-1/2" GRS CONDUIT COMMUNICATION DUCT BANK PER DRAWING ES-100.	40	1) TAKE CARE NOT TO DISTURB EXISTING SEWER AND WATER MAINS WHILE EXCAVATING WHERE CALLED OUT FOR REMOVAL. 2) AFTER INSTALLATION OF UTILITIES INDICATED, BACKFILL TRENCH PER PER 9/GS-103.
5	4'-0"	4'-0"	1) RE ROUTE EXISTING FIRE ALARM SYSTEM FROM BLDG.16 EXTERIOR WALL PER DRAWING ES-100.	27	1) TAKE CARE NOT TO DISTURB EXISTING SEWER AND WATER MAINS WHILE EXCAVATING EXCEPT WHERE CALLED OUT FOR REMOVAL. 2) AFTER INSTALLATION OF UTILITIES INDICATED, BACKFILL TRENCH PER PER 8/GS-103.
6	4'-0"	4'-0"	1) 6X1-1/2" SCHEDULE 80 PVC POWER CONDUITS PER ES-100. 2) 2X1-1/2" SCHEDULE 80 PVC COMMUNICATION CONDUITS PER ES-100.	118	1) TAKE CARE NOT TO DISTURB EXISTING SEWER AND WATER MAINS WHILE EXCAVATING EXCEPT WHERE CALLED OUT FOR REMOVAL. 2) AFTER INSTALLATION OF UTILITIES INDICATED, BACKFILL TRENCH PER PER 9/GS-103.
7	4'-0"	4'-0"	1) ACO GRATE DRAIN SYSTEM AND 4" SCR30 DRAIN PIPE WITH CLEANOUT PER DRAWING PS-100.	62	1) TAKE CARE NOT TO DISTURB EXISTING SEWER AND WATER MAINS WHILE EXCAVATING EXCEPT WHERE CALLED OUT FOR REMOVAL. 2) AFTER INSTALLATION OF UTILITIES INDICATED, BACKFILL TRENCH PER PER 8/GS-103 & 3/PS-100.
8	4'-0"	4'-0"	1) ACO GRATE DRAIN SYSTEM AND 4" SCR30 DRAIN PIPE PER DRAWING PS-100.	11	1) TAKE CARE NOT TO DISTURB EXISTING SEWER AND WATER MAINS WHILE EXCAVATION EXCEPT WHERE CALLED OUT FOR REMOVAL. 2) AFTER INSTALLATION OF UTILITIES INDICATED, BACKFILL TRENCH PER 8/GS-103 & 3/PS-100.

		(Company Logo/Information Block)	Drawing Title SITE REMOVALS, TRENCHING, AND TEMPORARY SITE ACCESS PLAN	Project Title UPGRADE FOR BUILDING 16 SITEMWORK	Date 05/04/2013		R
					Project No. 528A7-13-715		
			Approved: Facility Manager	Building Number 16	Checked CF		Drawn AZH
				Location VAMC SYRACUSE, NY	DRAWING NO. GS-100		
					Dwg. 3 Of 11		
Revisions	Date						