

- CONTRACTOR'S OPTION TO PROVIDE GALV. 16 GA BY THE DEPTH OF THE WALL METAL STUDS AS BLOCKING
- 22. WHERE NEW CONSTRUCTION (I.E. DOORS, FRAMES, CASEWORK, EQUIPMENT, ETC.) IS INDICATED TO BE INSTALLED IN EXISTING CONSTRUCTION, THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS FOR PROPER FIT AND FOR ACCESS INTO THE BUILDING PRIOR TO SHOP DRAWING SUBMITTAL, ORDERING AND DELIVERING TO THE SITE.

## Hampton VA, VAMC 05/03/2013 Renovate / Expand SCI, Phase II, 590-911 590-911 RDC/JPA Project No. 11004.00

**INDEX OF DRAWINGS** 

137-G000 COVER SHEET

137-C401 UTILITY PLAN

137-C503 DETAILS

137-CD101 EXISTING TOPOGRAPHY AND DEMOLITION PLAN

PIPE BASEMENT NOTE PLAN - AREA B

FIRST FLOOR NOTE PLAN - AREA A FIRST FLOOR NOTE PLAN - AREA B PENTHOUSE NOTE AND DIMENSION PLAN

**REFLECTED CEILING PLAN - AREA B** 

DOOR SCHEDULE

PERGOLA DETAILS

FINISH DETAILS

137-S100 GENERAL NOTES

137-S101 TYPICAL DETAILS 137-S102 TYPICAL DETAILS

137-A707

137-A801

137-A901

DOOR & FRAME DETAILS

HEAD WALL AND MISC. DETAILS

CASEWORK SECTIONS & DETAILS

137-S201A EXISTING FIRST FLOOR FRAMING PLAN NORTH 137-S201B EXISTING FIRST FLOOR FRAMING PLAN SOUTH

137-S202A EXISTING ROOF FRAMING PLAN NORTH

137-S202B EXISTING ROOF FRAMING PLAN SOUTH 137-S300 PIPE BASEMENT FOUNDATION PLAN

137-F101 PARTIAL FIRST FLOOR PLAN – AREA A 137-F102 PARTIAL FIRST FLOOR PLAN – AREA B

137-PD101 PARTIAL PIPE BASEMENT PLAN – AREA A - REMOVALS

137-PD102 PARTIAL PIPE BASEMENT PLAN – AREA B - REMOVALS

137-P101 PARTIAL PIPE BASEMENT PLAN – AREA A – NEW WORK

137-P102 PARTIAL PIPE BASEMENT PLAN – AREA B – NEW WORK

137-P103 PARTIAL FIRST FLOOR PLAN – AREA A – NEW WORK

137-P104 PARTIAL FIRST FLOOR PLAN – AREA B – NEW WORK

137-P105 PARTIAL FIRST FLOOR PLAN - AREA A - MEDICAL GAS

137-P106 PARTIAL FIRST FLOOR PLAN - AREA B - MEDICAL GAS

137-M401 ENLARGED EXISTING PENTHOUSE - REMOVALS AND NEW WORK

137-M402 ENLARGED NEW PENTHOUSE PLANS AND SECTIONS - NEW WORK

137-P107 SOIL, WASTE & VENT DIAGRAM - AREA A 137-P108 SOIL, WASTE & VENT DIAGRAM - AREA B

137-M001 INDEX, LEGEND, AND GENERAL NOTES 137-M301 EXISTING PENTHOUSE SECTIONS

137-M603 STEAM AND HOT WATER SYSTEM SCHEMATICS

137-M801 DEDUCT ALTERNATE PLANS - REMOVALS AND NEW WORK

137-MH101 FIRST FLOOR DUCTWORK PLAN AREA A - NEW WORK

137-MH102 FIRST FLOOR DUCTWORK PLAN AREA B - NEW WORK

137-MP100 PIPE BASEMENT PIPING PLAN - NEW WORK

137-E201 NEW SIGNALS CLOSET ELEVATIONS

137-ED101 FIRST FLOOR AREA "A" - REMOVALS

137-EL101 FIRST FLOOR AREA "A" - LIGHTING

137-EL102 FIRST FLOOR AREA "B" - LIGHTING

137-EP101 FIRST FLOOR AREA "A" - POWER

137-EP102 FIRST FLOOR AREA "B" - POWER

137-ET102 FIRST FLOOR AREA "B" - SIGNALS

137-EP105 FIRST FLOOR BUILDING 137A - POWER 137-ET101 FIRST FLOOR AREA "A" - SIGNALS

137-EL103 PENTHOUSE PLANS - LIGHTING, POWER, SIGNALS

137-EP103 ROOF PLAN AREA "A" - POWER AND LIGHTNING PROTECTION 137-EP104 ROOF PLAN AREA "B" - POWER AND LIGHTNING PROTECTION

137-EL100 PIPE BASEMENT - NEW WORK

137-ED102 FIRST FLOOR AREA "B" - REMOVALS

137-MP101 FIRST FLOOR PIPING PLAN AREA A - NEW WORK

137-MP102 FIRST FLOOR PIPING PLAN AREA B - NEW WORK

137-PD103 PARTIAL FIRST FLOOR PLAN – AREA A - REMOVALS 137-PD104 PARTIAL FIRST FLOOR PLAN – AREA B - REMOVALS

137-P001 INDEX, LEGEND & SCHEDULES

137-S301 FIRST FLOOR FRAMING PLAN 137-S301R FIRST FLOOR REINFORCING PLAN

137-S302 ROOF FRAMING PLAN 137-S401 FOUNDATION DETAILS 137-S402 FOUNDATION DETAILS 137-S411 PILE CAP DETAILS

137-S501 FRAMING DETAILS 137-S601 BRACING ELEVATIONS 137-S701 RESTORATION DETAILS

137-P601 PLUMBING DETAILS

137-M501 DETAILS

137-M503 DETAILS

137-M504 DETAILS 137-M601 SCHEDULES 137-M602 SCHEDULES

137-P801 DEDUCT ALTERNATE PLANS

137-M701 CONTROLS AND AUTOMATION 137-M702 CONTROLS AND AUTOMATION

137-MH103 ROOF PLAN - NEW WORK

137-E501 ELECTRICAL DETAILS

137-E502 TECHNOLOGY DETAILS

137-E503 SINGLE LINE DIAGRAM

137-E602 LIGHTING FIXTURES (1) 137-E603 LIGHTING FIXTURES (2)

137-E604 LIGHTING FIXTURES (3

137-ES101 ELECTRICAL SITE PLAN

137-E601 ELECTRICAL SCHEDULES

137-E504 SECURITY DETAILS

137-MD101 FIRST FLOOR AREA A - REMOVALS 137-MD102 FIRST FLOOR AREA B - REMOVALS

FIRST FLOOR FURNITURE PLAN - AREA A

FIRST FLOOR FURNITURE PLAN - AREA B

**EXTERIOR ELEVATIONS - EAST ADDITION** 

ALUMINUM WINDOW AND STORFRONT ELEVATIONS

FIRST FLOOR WALL TYPE AND DIMENSION PLAN - AREA A FIRST FLOOR WALL TYPE AND DIMENSION PLAN - AREA B

137-C301 GRADING AND EROSION CONTROL PLAN 137-C302 EROSION CONTROL DETAILS AND NOTES

137-G000

Hampton, Va 1 of 135

JOHN A. POE

Date

APPROVED: CHIEF OF STAFF

8

APPROVED: DIRECTOR, HAMPTON VA MEDICAL CENTER

STRUCTURAL ENGINEER 100 E. EIGHTH STREET CINCINNATI, OH 45202 513.241.3222 P 513.241.2981 F

CONSULTANTS

THP LIMITED INC. GET SOLUTIONS **GEOTECHNICAL ENGINEER ENVIRONMENTAL ENGINEER** 1592 PENNIMAN RD SUITE E WILLIAMSBURG, VA 23185 757.564.6452 P

WOOLPERT CIVIL ENGINEER 676 INDEPENDENCE PARKWAY SUITE 100 CHESAPEAKE, VA 23320 757.549.3549 P

757.549.6540 F

HEAPY ENGINEERING MECHANICAL ELECTRICAL COMMISSIONING TECHNOLOGY 1400 WEST DOROTHY LANE DAYTON, OH 45409 937.224.0861 P 937.224.5777 F

UNLESS WOOD BLOCKING IS SPECIFICALLY CALLED FOR BY THE MANUFACTURER.

TERRACON INC. 5240 GREEN'S DAIRY ROAD RALEIGH, NC 27616 919.873.2211 P 919.873.9555 F


RDC/JOHN POE ARCHITECTS 524 FERNWOOD DRIVE ALTAMONTE SPRINGS, FLORIDA 937 461 3290 PHONE 937 461 0260 FAX 1-800-362-1523 jpa@johnpoe.com


**COVER SHEET** 


rawing Title

pproved: Project Director

ARCHITECT/ENGINEERS:












Plate 3.01-1



FENCING AND ARMORING

CORRECT METHODS OF TREE FENCING



Apply 10-10-10 fertilizer at a rate of 450 lbs. / acre (or 10 lbs. / 1,000 sq. ft.)
Apply Pulverized Agricultural Limestone at a rate of 2 tons/acre (or 90 lbs. / 1,000 sq. ft.)

1 - A soil test is necessary to determine the actual amount of lime required to adjust the soil pH of site.
2 - Incorporate the lime and fertilizer into the top 4 – 6 inches of the soil by disking or by other means.
3 - When applying Slowly Available Nitrogen, use rates available in <u>Erosion & Sediment Control Technical Bulletin</u>

# 4, 2003 Nutrient Management for Development Sites at http://www.dcr.state.va.us/sw/e&s.htm#pubs

SEED <sup>1</sup>		
LAND USE	SPECIES	APPLICATION RATES
Minimum Care Lawn (Commercial or Residential)	Tall Fescue <sup>1</sup> or	175 - 200 lbs
	Bermudagrass <sup>1</sup>	75 lbs
High-Maintenance Lawn	Tall Fescue <sup>1</sup> or	200-250 lbs
	Bermudagrass <sup>1</sup> (seed) <b>or</b>	40 lbs. (unhulled 30 lbs. (hulled
	Bermudagrass <sup>1</sup> (by other vegetative establishment method, see Std. & Spec. 3.34)	
General Slope (3:1 or less)	Tall Fescue <sup>1</sup>	128 lbs
	Red Top Grass or Creeping Red Fescue	2 lbs
	Seasonal Nurse Crop <sup>2</sup>	<u>20 lbs</u> TOTAL: 150 lbs
Low-Maintenance Slope (Steeper than 3:1)	Tall Fescue <sup>1</sup>	93-108 lbs
	Bermudagrass <sup>1</sup>	0-15 lbs
	Red Top Grass or Creeping Red Fescue	2 lbs
	Seasonal Nurse Crop <sup>2</sup>	20 lbs
	Sericea Lespedeza <sup>3</sup>	20 lbs

Use seasonal nurse crop in accordance with seeding dates as stated below:

 February March - April

3 - May through October, use hulled seed. All other seeding periods, use unhulled seed. If Weeping Lovegrass is used, include in any slope or low maintenance mixture during warmer seeding periods, increase to 30 -40 lbs/acre.

## FERTILIZER & LIME

- Apply 10-20-10 fertilizer at a rate of 500 lbs. / acre (or 12 lbs. / 1,000 sq. ft.)
   Apply Pulverized Agricultural Limestone at a rate of 2 tons/acre (or 90 lbs. / 1,000 sq. ft.)
- A soil test is necessary to determine the actual amount of lime required to adjust the soil pH of site.
   Incorporate the lime and fertilizer into the top 4 6 inches of the soil by disking or by other means.
   When applying Slowly Available Nitrogen, use rates available in <u>Erosion & Sediment Control Technical Bulletin #</u>

1, 2003 Nutrient Management for Development Sites at http://www.dcr.state.va.us/sw/e&s.htm#pubs

## **EROSION CONTROL NOTES:**

FILTERING DEVICE.

ES-1: UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND VIRGINIA REGULATIONS VR 625-02-00 EROSION AND SEDIMENT CONTROL REGULATIONS.

ES-2: THE VA AND VDCR MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.

 $^{
m J}$  ES-3: ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING.

ES-4: A COPY OF THE APPROVED EROSION CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.

ES-5: PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS), THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION CONTROL PLAN


TO THE OWNER FOR REVIEW AND APPROVAL BY THE PLAN APPROVING AUTHORITY.

ES-6: THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TOO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE PLAN APPROVING AUTHORITY.

ES-7: ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED.

ES-8: DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO AN APPROVED

ES-9: THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES PERIODICALLY AND AFTER EACH RUNOFF-PRODUCING RAINFALL EVENT, ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY.



Safety Fence - 7 feet tall

**CONSULTANTS:** 

Source: Virginia Erosion And Sediment Control Handbook

Revisions Date

WOOLPERT
DESIGN | GEOSPATIAL | INFRASTRUCTURE

ARCHITECT/ENGINEERS:

676 Independance Parkway, Suite 100 Chesapeake, VA 23320 757-549-3549 FAX: 757-549-3540 Hampton VA, VAMC Renovate / Expand SCI, Phase II, 590-911 Project Phase

Drawing Title

Approved: Project Director

EROSION CONTROL DETAILS
AND NOTES

Project Phase

Building Number Checked Drawn

Date
04/26/2013

Project No.
590-911
RDC/JPA Project No. 11004.00

Drawing Number
137-C302

Project Phase

ding Number
137

SM

Drawn
DF AND LB

137-C302

Dwg. 05 of 135

