
Project No.: 656-12-182 SCIP Fire Alarm Replacement

St. Cloud VA Health Care System Main Campus, St. Cloud, Minnesota



GENERAL CONDITIONS

All dimensions on drawings are approximate; Drawings are not to be scaled. It is the responsibility of the contractor to verify all field conditions and physical dimensions that influence the construction area.

It is recommended that contractors visit the proposed construction site prior to submitting their bids and they are encouraged to do so.

Contractor shall adhere strictly to State and Federal Occupational Safety and Health Administration (OSHA) Standards.

Contractor shall park only in the designated parking areas and are not to park on the lawn areas; the only exception is to load or unload supplies or equipment.

Contractor is responsible for the safeguarding of their tools and equipment. All tools and equipment are not to be left unattended and are to be secured at all times when the contractor is not present, or the construction site is not supervised by the contractor.

All VA property is to be safeguarded from damage. Any damaged VA property is to be restored to original condition prior to damage or replaced completely. This includes installation, labor, and procurement expenses.

All demolished material becomes the property and the responsibility of the contractor with the exception of specified items designated either in the plans or verbally requested by the COR to be retained by the VA.

Offsite disposal of the demolished items, per specified guidelines, is the responsibility of the contractor.

Contractor must control demolition and construction dust from facility by erecting a dust barrier and ventilation with hepa filters. If venting to outside, the contractor will insure negative air pressure is maintained in encapsulated work area. When transporting debris, wet down sufficiently to prevent dust spreading.

If scaffolding is used, it must be used in accordance with (OSHA) regulations and is to be enclosed for the first eight feet above ground at end of each working day, until dismantled. Ladders must be removed and locked up at the end of each working day to prevent unauthorized persons from having access.

Clean all debris from construction site to the satisfaction of the CDR.

Contractor is responsible for erecting a barrier around work site to prevent patients, staff and visitors from entering construction site. This fence may be a plastic snow fence at open trench areas. All other areas require a metal chain-link fence be erected. Fencing to be 8' high, with top and bottom rail.

Provide vehicle/equipment and materials swinging gate (lockable).

Provide swinging mandoor gate with emergency egress capabilities.

Coordinate construction materials and location of fence with COR.

Contractor is responsible for repairing and replacing any damaged lawn. The restoration will be performed by a landscape contractor that regularly does sodding as part of their business. All damaged lawn will be overcut by 6" or more to accomodate full width rolls of sod. Top soil to be tilled and graded to a smooth matching grade of undamaged lawn. Sod to be thoroughly saturated with water upon placement. The contractor is responsible for watering new sod until project acceptance by the CDR.

Access to all buildings and parking areas must be maintained throughout the project.

Contractors are to coordinate all work with the Contracting Officers Representative.


SHEET INDEX

Drawing No.	Title				
	GENERAL	FA101-8	Building 8 Fire Alarm Plan - First Floor		
G100	Project Cover Sheet	FA100-9	Building 9 Fire Alarm Plan - Basement &		
	ARCHITECTURAL		First Floor		
AS100-2	Building 2 Partial Basement Plan	FA100-10	Building 10 Fire Alarm Plan - Basement		
A5100 Z		FA100-28	Building 28 Fire Alarm Plan - Basement		
	HVAC	FA101-28	Building 28 Fire Alarm Plan - First Floor		
MH001	HVAC Title Sheet	FA100-29	Building 29 Fire Alarm Plan - Basement		
MH100-4	Building 4 HVAC Plan - Basement	FA101-29	Building 29 Fire Alarm Plan - First Floor		
MH100-49	Building 49 HVAC Plan - Basement	FA100-48	Building 48 Fire Alarm Plan - Basement		
MH100-51	Building 51 HVAC Plan - Basement	FA101-48	Building 48 Fire Alarm Plan - First Floor		
		FA100S-49	Building 49 Fire Alarm Plan - Sub		
	FIRE ALARM		Basement		
FA100	Fire Alarm Title Sheet	FA100-49	Building 49 Fire Alarm Plan - Basement		
FS100	Fire Alarm Site Plan	FA101-49	Building 49 Fire Alarm Plan - First Floor		
FA100-1	Building 1 Fire Alarm Plan - Basement	FA100-50	Building 50 Fire Alarm Plan - Basement		
FA101-1	Building 1 Fire Alarm Plan - First Floor	FA101-50	Building 50 Fire Alarm Plan - First Floor		
FA100-2	Building 2 Fire Alarm Plan - Basement	FA100S-51	Building 51 Fire Alarm Plan - Sub		
FA101-2	Building 2 Fire Alarm Plan - First Floor		Basement		
FA100-3	Building 3 Fire Alarm Plan - Basement	FA100-51	Building 51 Fire Alarm Plan - Basement		
FA101-3	Building 3 Fire Alarm Plan - First Floor	FA101-51	Building 51 Fire Alarm Plan - First Floor		
FA102-3	Building 3 Fire Alarm Plan - Second Floor	FA200	Fire Alarm Network Riser Diagram		
FA100-4	Building 4 Fire Alarm Plan - Basement	П			
FA101-4	Building 4 Fire Alarm Plan - First Floor		CONTRACTOR AND SUBS TO REVIEW LISTED FIRE ALARM AND MECHANICAL DRAWING SHEETS FOR ELECTRICAL WORK TO BE PERFORMED. NEW WALL CONSTRUCTION SHOWN ON SHEET AS100-2. CONTRACTOR AND SUBS TO REVIEW ALL DRAWINGS FOR MISCELLANEOUS LOCATIONS REQUIRING		
FA102-4	Building 4 Fire Alarm Plan - Second Floor				
FA100-5	Building 5 Fire Alarm Plan - Basement	11			

100% CONSTRUCTION DOCUMENTS - FOR CONSTRUCTION

Building 7 Fire Alarm Plan - First Floor

Building 8 Fire Alarm Plan - Basement






	STAMP/SEAL:				
et 8	I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA.				
0					
52	MN 43619				
m	DANIEL J. MILLER, AIA REG. NO.				
3	DATE: 03.12.2013				

APPROVED: SERVICE LINE DIRECTOR	DATE:	APPROVED: INFECTION CONTROL NURSE	DATE:	DRAWING TITLE
				PROJECT COVER SHEET
APPROVED: GEMS COORDINATOR	DATE:	APPROVED: PATIENT SAFETY	DATE:	
				APPROVED: ASSOCIATE HEALTH CARE SYSTEM DIRECTOR DATE:
		<u></u>		
APPROVED: PROJECTS SECTION MANAGER	DATE:	APPROVED: CHIEF OF POLICE	DATE:	
				APPROVED: CHIEF OF STAFF DATE:
APPROVED: DIRECTOR FMS	DATE:	APPROVED: SAFETY MANAGER	DATE:	
AFFROYED. DIRECTOR TWO	DAIL.	AFFROVED. SPIETI WINNIGER	DAIL.	APPROVED: HEALTH CARE SYSTEM DIRECTOR DATE:

FA100-8



INFILL OR PATCHING OF WALL AREA FOR (OR FOLLOWING) FIRE ALARM WORK.