KEY NOTES

(01) NEW EXHAUST GRILLE AND DUCTWORK CONNECTED TO EXISTING EXHAUST DUCT. BALANCE TO AIRFLOWS AS INDICATED ON PLANS.

(02) NEW SUPPLY DIFFUSER AND DUCTWORK CONNECTED TO EXISTING SUPPLY DUCT.

(03) RELOCATED THERMOSTAT WITH CONTROL WIRING EXTENDED AS NEEDED TO RECONNECT. CONNECT BOTH TERMINAL UNITS TO SINGLE THERMOSTAT.

(04) RELOCATED THERMOSTAT WITH CONTROL WIRING EXTENDED AS NEEDED TO RECONNECT.

(05) ADJUST TERMINAL BOX CONTROLS TO OPERATE IN CONSTANT VOLUME MODE.

(06) BALANCE SYSTEM TO PROVIDE NEW AIRFLOWS AS INDICATED ON PLANS AND AIRFLOWS PREVIOUSLY RECORDED TO EXISTING AIRFLOW DEVICES.

(07) CAP AND SEAL EXISTING DUCTWORK OPEN TO PLENUM.

(08) RELOCATED TEMP TRAC MONITOR. VERIFY FINAL LOCATION WITH OWNER.

(09) COORDINATE FINAL LOCATION OF CEILING AIR DEVICES WITH SIEMENS CEILING RAIL SYSTEM REQUIREMENTS.

(10) EXISTING TEMPERATURE AND HUMIDITY SENSORS TO REMAIN. CONFIRM DUCT MOUNTED HUMIDIFIER CYCLES ON/OFF WITH ROOM SENSOR TO MAINTAIN SENSOR SETPOINT. REPAIR AS REQUIRED.

(11) REFER TO SPECIFICATION SECTION 233100 FOR DUCTWORK REQUIREMENTS AT LEAD SHIELDED WALLS.

GENERAL NOTES

1. ALL NEW SUPPLY AIR DUCTWORK SHALL BE EXTERNALLY INSULATED.

2. MECHANICAL CONTRACTOR TO VERIFY TERMINAL BOXES IN SCOPE OF WORK ARE FUNCTIONING PROPERLY. TEST ACTUATORS AND REPAIR BOXES AS REQUIRED FOR PROPER OPERATION.

3. MECHANICAL CONTRACTOR TO MEASURE BASELINE TRAVERSE READINGS PRIOR TO DEMOLITION/ CONSTRUCTION AND FORWARD THE MEASURED READINGS TO THE ARCHITECT, ENGINEER, AND GENERAL CONTRACTOR.

RENOVATION LEGEND

SYMBOL	DESCRIPTION
———	NEW CONSTRUCTION
———	EXISTING TO REMAIN
◔	CONNECT TO EXISTING AT THIS POINT



2 ENLARGED PLAN - TREATMENT RM. 5
1/4" = 1'-0"



1 SECOND FLOOR NEW - DUCTWORK
1/8" = 1'-0"



KEYPLAN - BUILDING 111

95% SUBMISSION - NOT FOR CONSTRUCTION

Revisions:	Date

Stamp / Seal

THESE DOCUMENTS ARE FOR INTERIM REVIEW AND NOT INTENDED FOR CONSTRUCTION, BIDDING, OR PERMIT PURPOSES.
2-14-2013
ENGINEER OF RECORD
DARREN LEE HARVEY, PE
STATE: KANSAS
REGISTRATION #: 19666

CONSULTANTS:

IEA
9201 West Broadway
Brooklyn Park, MN 55445
Toll Free: 800.233.9513
Tel: 763.315.7900
Fax: 763.315.7920

SSR Smith Seckman Reid, Inc.
11460 Tomahawk Creek Pkwy, Suite 320
Leawood, KS 66211
(913) 319-3560
FAX: (913) 319-3579
www.ssr-inc.com
Project # 1255071

ARCHITECT/ENGINEERS:

COX DESIGN ASSOCIATES
ARCHITECTURE PLANNING INTERIORS

CHICAGO
345 N. Canal Street Suite 701
Chicago, Illinois 60606
T: 312.454.9434
F: 312.454.9439

AUSTIN
5121 Bee Cave Road #203
Austin, Texas 78746
T: 512.327.4149
F: 512.327.7679

Drawing Title: SECOND FLOOR NEW - DUCTWORK

Project Name: 111 RENOVATE X-RAY 5

Location: CLEMENT J. ZABLOCKI VA MEDICAL CENTER
MILWAUKEE, WI

Project Number: 695-12-195

Date: 02.14.13

Drawing Number: MH-201

Building Number: 111

Checked: DLH

Drawn: EPS

Dwg. of

Office of Construction and Facilities Management

VA FORM 08-6231