

AMENDMENT# A00001

I. GENERAL

The following corrections, changes, additions or deletions shall be made to the solicitation. All other terms, conditions, and instructions shall remain the same.

1. Proposal due date is hereby extended to Friday **May 31**, 2013 no later than **10:00AM**.
2. Correct project cost magnitude is **between \$1,000,000 to \$2,000,000**.
3. Project duration shall not exceed **270** calendar days from issuance of the Notice to Proceed (NTP).
4. Hard copies of proposals are not required or desired. Proposals shall be sent via e-mail only.

II. DRAWINGS AND SPECIFICATIONS

Drawings

1. Clarification #1 Landscape Detail 2 / L2.1 references structural drawings for post embedment footing for guardrail. Structural drawing does not show this information.
 - Detail 7/S1 refers to a grout pocket of 12” deep for post embedment.

Clarification #2 Landscape Detail 2 / L2.2 references structural drawings for post embedment footing for handrail. Structural drawing does not show this information.

- Detail 2/ L2.2 has been revised to show the footing size for handrail.

Clarification #3 S1: Detail 5 – Monument Sign.
Stone veneer should be applied to both front and back of the sign wall.

- Drawing S1/ Detail 5 has been revised to show stone veneer on both sides.

Clarification #4 Detail 3 – Stone Wall. Detail also needs to address the condition of the monument sign wall, e.g. veneer on both front and back, height of wall, etc.

- L2.1 Detail 3 has been revised to clarify the condition at the monument sign wall. Detail 5/S1 and Detail 4/Z1 also show the two sided condition. Detail 3/Z1 and L2.1 Detail 3 shows the height of the monument sign wall to be 4’-0”.

Clarification #5 Details 1 and 3 – Notes should reference Civil Drawings (C3.0) for layout and Landscape Drawings (Sheet L2.1) for details.

- Drawing Z1: Details 1 and 3 – Note referencing Civil Drawings (C3.0) for layout and Landscape Drawings (Sheet L2.1) for details has been added.

Clarification #6 Z1: Detail 4 specifies stainless steel letters painted white. Is this correct – painting on stainless steel? (Is this a durable finish?)

- Drawing Z1: Architect confirms that the design intent is to have painted stainless steel signage letters.

Clarification #7 The cover sheet and scope of work are dated March 13, 2013. The civil and structural sheets are dated March 12, 2013. The landscape and signage sheets are dated February 8, 2013. The electrical sheet is dated December 17, 2012.

- Dates on all sheets have been revised to be May 7, 2013

FOR OFFICIAL USE ONLY
Source Selection Information—See FAR 2.101 & 3.104
VA261-13-R-0957 – Retaining Wall Parking Lot 100W – Palo Alto

Clarification #8 Sheet L1.0 – Paving legend specifies acid washed finish. It should be sand-blasted.

- Sheet L1.0 Paving Legend has been revised to specify sand-blast finish for concrete.

2. A cloud and addendum notation on sheet L2.2 shall require Contractor to ignore. (NO COST OR SCOPE CHANGE)

3. Add "multi-trunk" to the specifications for *Cercis occidentalis* in the Plant Legend on sheet L1.0. (NO COST OR SCOPE CHANGE)

Specifications

1. Section 32 05 20 CEMENT AND CONCRETE FOR LANDSCAPING EXTERIOR IMPROVEMENTS, 1.2 Related Work referenced 32 05 23 for other concrete items. This specification section has been eliminated and the information has been consolidated with 32 05 20 and 03 30 00.

2. Section 32 84 00 PLANTING IRRIGATION, 2.10 Automatic Control Equipment – Independent Electric Controllers.

•2.10. A “Product as manufactured by Hydropoint (Weather Trak ET Pro2S Central) and conforming to this specification is acceptable.” The product is WeatherTRAK ET Pro2 Smart Water Manager -- WTPRO2S-C-XX-SPH, CIM-4YA

“XX” below refers to # of stations.

The “C” means Central Internet Management & Control.

The “SPH” means Stainless steel Pedestal enclosure, Heavy duty.

The VA would like to include five total years of service – “CIM-4YA”

3. Section 10 14 00 SIGNAGE has been revised

4. Spec Section 32 84 00, Page 7. 2.10 WTPRO2S-C-XX-SPH, CIM-4YA” is revised to “WTPRO2S-C-48-SPH, CIM-5YA”

5. L2.01 / Detail 3, Stone Wall, plan view.

The call-out “Extent of Concrete Backing Wall at Partial Retaining Location” is revised to read “Extent of Concrete Backing Wall at Freestanding Location”. The call-out “Extent of Concrete Backing Wall and Footing at Freestanding Location” is revised to read “Extent of Concrete Backing Wall and Footing at Partial Retaining Location”.

III. OFFEROR REQUESTS FOR INFORMATION RFI's & GOVERNMENT RESPONSES

Responses to RFI's submitted by May 17, 2013 deadline are included herein as an attachment.