

# Scope of Work

**Project Number:** 437-13-119

**Project Title:** REPLACE LOADING DOCK LEVELERS AND BUMPERS

**Description of Work:** Work shall include, but shall not be limited to providing all labor, materials, equipment, etc necessary to completely prepare the site for Fargo VA Health Care System project 437-13-119, Replace Loading Dock Levelers and Bumpers in accordance with this Scope of Work, the contract documents, all applicable federal, state and local codes and NFPA. The construction work shall account for phasing of the work as indicated on the plans so that the VA minimally impacted in terms services provided to our customers and parking lost during construction.

Work shall include, but shall not be limited to removing and replacing the existing loading dock levelers at the main Medical Center (quantity = 3) and the warehouse (quantity = 2) in accordance with the contract documents. Work shall be phased so each building has at least one loading dock operational at all times. Work shall involve, but shall not be limited to: removal of loading dock levelers, installation of new loading dock levelers, removal and replacement of concrete, removal and replacement of electrical power and controls associated with the loading dock levelers.

**Durations of Work:** 180 days