



- ## GENERAL NOTES
1. SEE SPECIFIC BUILDING ISOMETRICS FOR PIPE SIZES.
 2. SEE BUILDING FLOOR PLANS AND ISOMETRICS FOR EXISTING PIPE LOCATIONS.

PLAN NOTES

- 1 PLUMBING CONTRACTOR SHALL CONNECT STEAM PIPING TO HEAT EXCHANGER IN THE FIELD.
- 2 PROVIDED BY CONTROLS CONTRACTOR. INSTALL BY MANUFACTURER.
- 3 PLUMBING CONTRACTOR SHALL PIPE HOT WATER PIPE BACK TO TIE-IN POINT.
- 4 PLUMBING CONTRACTOR SHALL PIPE CONDENSATE BACK TO TIE-IN POINT.
- 5 PLUMBING CONTRACTOR SHALL PIPE HOT WATER REIRC. PIPE BACK TO TIE-IN POINT.
- 6 PLUMBING CONTRACTOR SHALL PIPE COLD WATER PIPE BACK TO TIE-IN POINT.
- 7 PLUMBING CONTRACTOR SHALL PIPE STEAM BACK TO TIE-IN POINT. NO CONTROL VALVE REQUIRED.
- 8 PLUMBING CONTRACTOR SHALL PIPE 160° HOT WATER TO KITCHEN AND BOOSTER HEATER IN BUILDING 4.
- 9 DIGITAL MIXING VALVE. PROVIDE RADA DR680 OR APPROVED EQUAL. PLUMBING CONTRACTOR SHALL SHIELD DIGITAL MIXING VALVE ELECTRICAL BACK TO EXISTING EMERGENCY ELECTRICAL PANEL. BOTH MIXING VALVES ON SMD SHALL BE WIRED BACK TO A SPARE 20 AMP BREAKER.
- 10 CONDENSATE TRAP, ARMSTRONG 814 OR APPROVED EQUAL.
- 11 DIGITAL MIXING VALVE. PROVIDE RADA DR680 OR APPROVED EQUAL. PLUMBING CONTRACTOR SHALL HIRE A LICENSED ELECTRICAL CONTRACTOR TO PROVIDE 120V POWER TO DIGITAL MIXING VALVE.

△	ADDENDUM #2	05-23-13
160	REVISION	DATE

Alexandria
525 Broadway Street
Alexandria, MN 56308
phone 3 207 5 99 0 30
facsimile 3 207 5 99 0 62
www.jlgarchitects.com
copyright © 2012

STAMPED:
I HEREBY CERTIFY THAT THIS PLAIN SPECIFICATION
ON REPORT WAS PREPARED BY ME OR UNDER MY
SUPERVISION, AND THAT I AM A LEO
EMPLOYED BY THE POLICE DEPARTMENT OF THE
CITY OF MINNEAPOLIS, MINNESOTA, UNDER THE
LAWS OF THE STATE OF MINNESOTA.

Shane T. Johnston
SHANE T. JOHNSTON, PII
DATE: 01-15-2013

MIN 44005
REC. NO.

FORMING TITLE	PLUMBING DETAILS
APPROVED PROJECT DIRECTOR	DATE:

PRODUCT TITLE	HOT WATER GENERATORS	DATE	01.15.2013
BUILDING NO.		FLOOR SCALE	
AS NOTED		AS NOTED	
(LOCATION)		NO.	
ST. CLOUD VA MEDICAL CENTER		656-4-3-225	
ST. CLOUD MN 56303		SCIP	
DRAWING NO.		XXX FILE	
Pt. 50			
Rev. 220			
23			

