

CLEMENT J. ZABLOCKI MEDICAL CENTER
MILWAUKEE, WI
PROJECT NAME: Building 41 Re-roofing Project
VA PROJECT NO: 695-12-109SCP
Construction PO No: _____

DEPARTMENT OF VETERANS AFFAIRS

AMENDMENT 001

ISSUE DATE: May 23, 2013

The following instructions herein and the listed documents below are hereby modified to be incorporated as part of the contract documents.

This Addendum consists of the following:

- (1) Narrative page to clarify contractor questions; responses are shown in *italic red*
 - Copy of revised Painting Specification 099000
 - Copy of Detail 1/A500
 - Copy of Detail 28/A500
1. The specifications posted for this project say they're for a different project and in some areas don't make sense. Will there be new specifications provided specific to this project? We are holding back questions pertaining to those spec.'s anticipating new spec.'s will be posted, please advise – *Refer to reposted specifications*
 2. If new specifications are provided, will there be an extension to the time period for additional questions since we still do not have the correct spec's? This is typically the area of the bid documents that generates the most questions. – *Refer to attached write-up from GLAC / VA*
 3. The current painting spec section will not open. Will there be a new spec. for painting provided? – *Refer to attached painting specification*
 4. Detail 24 A500, what is the 1" slate overhang refer too? – *Please disregard all references to slate; roof material shall be asphalt shingles as per specifications*
 5. No Detail #1 for lower roof on A500, will one be issued? – *Please refer to attached detail*
 6. No detail #28 for upper roof on A500, will one be issued? - *Please refer to attached detail*
 7. No details shown for Roof "D" EPDM alternate, will one be issued? – *Please refer to Details 2A and 2B / A500 in the Bid Set for the base bid and alternate details respectively*
 8. Will the metal element on top of chimney of Roof "C" be repaired or replaced? – *Repaired if possible; replaced only if necessary; provide pricing for both*
 9. A500 notes existing Eave Cornice coping to remain, but spec section calls for its removal, which one is correct? – *Coping shall be removed only as necessary to install new roofing system; then it is to be reinstalled; all fasteners shall be sealed to assure water-tight condition; damaged or dented coping pieces shall be reshaped prior to reinstallation; refer to attached Detail 28/A500*

END OF AMENDMENT 001