

FINISH SCHEDULE

FINISH CONTRACTOR MUST REVIEW ALL SPECIFICATIONS AND DRAWINGS PRIOR TO ORDERING MATERIALS AND COMMENCING FABRICATION AND INSTALLATION. MANY ITEMS ARE LONG-LEAD AND SHOULD BE ORDERED PROMPTLY. LOCATION DESCRIPTIONS ARE FOR REFERENCE ONLY AND ARE NOT INDICATIVE OF EVERY OCCURRENCE OF A PARTICULAR FINISH. REFER TO FINISH PLAN FOR EXACT LOCATIONS.

CEILING
 AS MANUFACTURED BY ARMSTRONG WORLD INDUSTRIES, INC. SALES REPRESENTATIVE: NANCY MEDL. PHONE: 215-491-2179

WHEREVER POSSIBLE, GRIDS TO BE CENTERED IN THE ROOM ON THE CENTER LINE OF THE CEILING TILE. INSTALL NO TILE SMALLER THAN 6" WIDE. ALL CEILING GRIDS TO BE ARMSTRONG WORLD INDUSTRIES. COLOR: WHITE, U.N.O.

C-1
 STYLE: HEALTH ZONE ULTIMA #1501 OR APPROVED EQUAL. EDGE PROFILE: BEVELED REGULAR. DIMENSIONS: 2' x 2' x 3/4". GRID: PRELUDE. COLOR: WHITE. FOR USE AS THE GENERAL CEILING, U.N.O.

C-2
 STYLE: OPTIMA OPEN PLAN #3534 OR APPROVED EQUAL. EDGE PROFILE: BEVELED REGULAR. DIMENSIONS: 2' x 2' x 1". GRID: 1518 SQUARE REGULAR. COLOR: WHITE.

C-3
 GYPSUM WALLBOARD SOFFIT. COLOR: T80

NOTE: WHERE THE FASCIA OF SOFFITS ALIGNS WITH THE ADJACENT PARTITION, PROVIDE 1/4" FRY REVEAL TO TERMINATE A MATERIAL OR COLOR. ALL SOFFIT FASCIA ARE TO RECEIVE PAINT, NOT VINYL WALLCOVERING. PLEASE REFER TO THE REFLECTED CEILING PLAN FOR LOCATIONS OF CEILING TILES.

C-4
 STYLE: OPTIMA OPEN PLAN #1981 OR APPROVED EQUAL. EDGE PROFILE: BEVELED REGULAR. DIMENSIONS: 2' x 2' x 3/4". GRID: 1518 PRELUDE WITH 52 LONG-BEVELED REGULAR SHORT. COLOR: WHITE.

C-5
 STYLE: METALWORKS EFFECTS WOOD LOOKS #464FX_ OR APPROVED EQUAL. EDGE PROFILE: SQUARE REGULAR. FABRICATION: M2. DIMENSIONS: 2' x 2' x 5/8". GRID: 1518 PRELUDE XL. COLOR: EFFECTS WALNUT FXWN ACCESSORIES:

- FIBERGLASS W/ILLUMINATED 100
- SPRUE PLATE WITH SET SCREWS
- EFFECTS HOLD DOWN CLIP FOR CUT PANEL INSTALLATIONS
- 1518 EDGE CAP FOR CUT REGULAR PANELS

AXIOM KNIFE EDGE TRIM AND ALL ACCESSORIES FINISH: WHITE.

C-6
 STYLE: METALWORKS LINEAR - INTERIOR #462YXWN OR APPROVED EQUAL. COLOR: EFFECTS WALNUT FXWN. PERFORMANCE OPTION: MICROPERFORATED. PANEL WIDTH: 4". EDGE DETAIL: SQUARE WITH EXTENDED FLANGE. DIMENSIONS: 16" x 4" x 3/8". SUSPENSION SYSTEM: #5467 STANDARD CARRIER ACCESSORIES: ASSUME ALL ACCESSORIES - PANEL SPLICES, PANEL END CAPS, TRIM MOLDSINGS & PRESSURE SPRINGS.

C-7
 STYLE: METALWORKS LINEAR - EXTERIOR #460YXWN OR APPROVED EQUAL. COLOR: EFFECTS WALNUT FXWN. PERFORMANCE OPTION: UNPERFORATED. PANEL WIDTH: 4". EDGE DETAIL: SQUARE WITH EXTENDED FLANGE. DIMENSIONS: 16" x 4" x 3/8". SUSPENSION SYSTEM: #5467 STANDARD CARRIER ACCESSORIES: ASSUME ALL ACCESSORIES - PANEL SPLICES, PANEL END CAPS, TRIM MOLDSINGS & PRESSURE SPRINGS.

PANT
 ALL PAINT AS MANUFACTURED BY: SHERWIN WILLIAMS

NOTE: ALL WALLS TO BE EGGSHELL FINISH U.N.O. TOILET ROOMS ARE TO BE SEMI-GLOSS WATER BASE EPOXY. ALL TRIM AND FRAMES TO BE SEMI-GLOSS FINISH. METAL PANELS TO BE PAINTED TO MATCH ADJACENT WALL. ALL GWR CEILING AND SOFFITS TO BE FLAT FINISH U.N.O. SOFFITS ARE NEVER TO RECEIVE VINYL WALLCOVERING AND FACE AND UNDERSIDE ARE TO BE PAINTED TO MATCH. EXPOSED CEILING TO RECEIVE TWO-PART EPOXY COATING.

PT-1
 COLOR: DOWNY SW7002 FOR USE AS GENERAL PAINT, U.N.O.

PT-2
 COLOR: CORN WEDGE SW7539 FOR USE AS DOOR FRAME AND TRIM PAINT, U.N.O.

PT-3
 COLOR: SMOKEY TOPAZ SW6117 FOR USE AS ACCENT PAINT

PT-4
 COLOR: STUNNING SHADE SW7082 FOR USE AS ACCENT PAINT

PT-5
 COLOR: MESSENGER BAG SW 7740 FOR USE AS ACCENT PAINT

PT-6
 COLOR: MANNERED GOLD SW6130 FOR USE AS ACCENT PAINT

PT-7
 COLOR: WAFFES SW8104 FOR USE AS ACCENT PAINT

PT-8
 COLOR: RESTRAINED GOLD SW6129 FOR USE AS ACCENT PAINT

PT-9
 COLOR: TIGERREY SW6242 FOR USE AS ACCENT PAINT

PT-10
 COLOR: EDGY GOLD SW6409 FOR USE AS ACCENT PAINT

PT-11
 COLOR: BRACING BLUE SW6242 FOR USE AS ACCENT PAINT

PT-12
 COLOR: EXCLUSIVE PLUM SW6263 FOR USE AS ACCENT PAINT

PT-13
 COLOR: DISTANCE SW6243 FOR USE AS ACCENT PAINT

PT-14
 COLOR: GREY CLOUDS SW6768 FOR USE IN TOILET ROOMS

SPECIALTY PAINT COATING
 AS MANUFACTURED BY HOPPER SALES REPRESENTATIVE: JENIFER HOPPER. PHONE: 480-609-7555

SPC-1
 STYLE: WS-456 - CUSTOM VENETIAN FINISH OR APPROVED EQUAL. BASE COAT: FINISH COLOR AND CUSTOM WHITE CEMENT BY HOPPER FOR USE ON EXPOSED COLUMNS.

CERAMIC WALL TILE
 AS MANUFACTURED BY DALTILE SALES REPRESENTATIVE: SUSAN METKA. PHONE: 484-576-9387

CWT-1
 STYLE: SPARK COLORBODY PORCELAIN OR APPROVED EQUAL. COLOR: TOASTED LUSTER SK52. DIMENSIONS: 12" x 24" x 1/8". GROUT COLOR: T80. GROUT WIDTH: 1/8".

CWT-2
 STYLE: COVE BASE S-30C3TB OR APPROVED EQUAL. DIMENSIONS: 8" x 12". GROUT COLOR: TO MATCH CWT-1. GROUT WIDTH: TO MATCH CWT-1.

CWT-3
 STYLE: SPARK COLORBODY PORCELAIN OR APPROVED EQUAL. COLOR: WARM FIELD BLEND S30C3 SK55. DIMENSIONS: 17" x 2" (SHEET 11-5/8" X 11-5/8"). GROUT COLOR: T80. GROUT WIDTH: 1/8".

RUBBER BASE
 AS MANUFACTURED BY MANNINGTON SALES REPRESENTATIVE: JESSICA D'ANGELO. PHONE: 610-675-6599

RB-1
 STYLE: PREMIUM EDGE RUBBER WALL BASE (TYPE TP) OR APPROVED EQUAL. COLOR: TOASTED SESAME 924. DIMENSIONS: 4" x 12" x 3/32". 6" IN SOLED UTILITY ROOMS AND JANITORS CLOSETS. FINISH: SMOOTH MATTE FINISH. ACCESSORIES: PREMIUM EDGE FACTORY PRE-FORMED MOLDED CORNERS SEAL JOINTS BETWEEN TOP OF WALL BASE AND IRREGULAR WALL SURFACES.

WALL PROTECTION
 AS MANUFACTURED BY C/S ACRYO-VN SALES REPRESENTATIVE: BRAD GILDIN. PHONE: 610-625-0220

PWP-1
 PLASTIC WALL PROTECTION OR APPROVED EQUAL. STYLE: 4000 300X RIGID SHEET. DIMENSIONS: 4' x 10' SHEET. SURFACE: SHADOWGRAN. COLOR: BEIGE #103. JOINTS/TRANSITIONS: COLOR MATCHING CAULK (NO PLASTIC TRIM PICES).

CG-1
 STYLE: C03-CORNER GUARD OR APPROVED EQUAL. COLOR: 03-8M FOR ODD ANGLES. ANGLE: 90 DEGREES. DIMENSIONS: 3/16" X 1/2" X FULL HEIGHT. 304 STAINLESS ALLOY WITH #4 SATIN FINISH. MOUNTED WITH CONSTRUCTION ADHESIVE AND STAINLESS STEEL SCREWS.

CG-2
 NOT USED

CG-3
 STYLE: CUSTOM FABRICATED STAINLESS STEEL CORNER GUARD. DIMENSIONS: 4' x 4' x 88" L. FIBERGLASS. 1/8" GAUGE. SATIN FINISH. TO BE FASTENED MECHANICALLY WITH ADHESIVE.

BG-1
 STYLE: FR-225N BUMPER GUARD OR APPROVED EQUAL. PATTERN: MORGCCO CLOVE 1P727. DIMENSIONS: 2" x 14" x 1/2". ACRYO-VN 4000 COVER. TEXTURE: SHADOWGRAN. COLOR: BEIGE #103. RETAINER: ALUMINUM. COLOR MATCHING END CAPS.

HR-1
 STYLE: P-RHS PLATFORM HANDRAIL OR APPROVED EQUAL. DIMENSIONS: 6-3/8" x 3"D. TOP RAIL WOOD SPECIES: MAPLE. TOP RAIL WOOD FINISH: 448 WALNUT. BOTTOM RAIL COLOR: #4 POLISH (3 SIDES). BRACKET COLOR: T80. MATCHING END CAPS RETURNING TO THE WALL.

HR-2
 STYLE: HRS-8C RENAISSANCE HANDRAIL OR APPROVED EQUAL. DIMENSIONS: 5-1/4" x 3"D. FINISH: #4 SATIN FINISH. MATCHING END CAPS RETURNING TO THE WALL.

HR-3
 STYLE: HRB9-20 W/PSYCH COVER OR APPROVED EQUAL. DIMENSIONS: 6-1/4" x 3"D. WOOD SPECIES: MAPLE. WOOD COLOR: 448 WALNUT. CONTINUOUS BRACKET ENCLOSURE. MATCHING END CAPS RETURNING TO THE WALL.

PLASTIC LAMINATE
 AS MANUFACTURED BY WILSONART SALES REPRESENTATIVE: ROSE LEISTER. PHONE: 609-685-1683

PL-1
 STYLE: COLUMBIAN WALNUT T943-07 OR APPROVED EQUAL. FOR USE AS VERTICAL LAMINATE, U.N.O.

ARCHITECTURAL WALL PANELS
 AS MANUFACTURED BY TRESPA DISTRIBUTOR: SS RESOURCE CONNECTION. SALES REPRESENTATIVE: MICHAEL SOPRANI. PHONE: 610-291-7800

AWP-1
 STYLE: TRESPA MIEZEON OR APPROVED EQUAL. COLOR: WYVIST COUNTRY WOOD. TEXTURE: SATIN. THICKNESS: 1/4" (6mm). PANEL TYPE: DOUBLE SIDED DECORATIVE.

SOLID SURFACE POLYMER
 AS MANUFACTURED BY CORIAN DISTRIBUTOR: OR BRIGGS. SALES REPRESENTATIVE: ROBIN BUSBY. PHONE: 484-289-2561

SSP-1
 COLOR: COTTAGE LANE OR APPROVED EQUAL. FOR USE AS GENERAL COUNTERTOP, U.N.O.

AS MANUFACTURED BY MEGANITE DISTRIBUTOR: FESSERHALL INC. SALES REPRESENTATIVE: ROSE LEISTER. PHONE: 609-685-1683

SSP-2
 COLOR: ROCKY ROAD GRANITE OR APPROVED EQUAL. FOR USE IN TOILET ROOMS AND LABORATORY.

SSP-3
 SOLID SURFACE POLYMER SINK. CORIAN 180 SIDE OVERFLOW. COLOR: BISCUE. FOR USE AS TYPICAL TOILET ROOM SINK, U.N.O.

CARPET
 AS MANUFACTURED BY SHAW CONTRACT SALES REPRESENTATIVE: VICKY MCCONAGHY. PHONE: 810-299-0852

CPT-1
 STYLE: FEELING FLUSH / RADIANCE TILE 50261 OR APPROVED EQUAL. COLOR: NATURAL TONG 20755. TYPE: TILE. DIMENSIONS: 24" x 24". INSTALLATION: QUARTER TURN FOR USE IN LOBBY AND WAITING AREAS.

CPT-2
 STYLE: FEELING FLUSH / GLITZ TILE 50360 OR APPROVED EQUAL. COLOR: NATURAL TONG 20755. TYPE: TILE. DIMENSIONS: 24" x 24". INSTALLATION: QUARTER TURN FOR USE IN OFFICES AND SUPPORT AREAS.

VINYL COMPOSITION TILE
 AS MANUFACTURED BY MANNINGTON SALES REPRESENTATIVE: JESSICA D'ANGELO. PHONE: 610-675-6599

VCT-1
 STYLE: PROGRESSIONS OR APPROVED EQUAL. COLOR: WALNUT 55123. DIMENSIONS: 12" x 12" x 1/32".

VCT-2
 STYLE: PROGRESSIONS OR APPROVED EQUAL. COLOR: WHEAT 55123. DIMENSIONS: 12" x 12" x 1/32".

VCT-3
 STYLE: PROGRESSIONS OR APPROVED EQUAL. COLOR: SPROUT 55535. DIMENSIONS: 12" x 12" x 1/32".

VCT-4
 STYLE: PROGRESSIONS OR APPROVED EQUAL. COLOR: PRAIRIE SAND 55183. DIMENSIONS: 12" x 12" x 1/32".

VCT-5
 STYLE: PROGRESSIONS OR APPROVED EQUAL. COLOR: AUTUMN LEAF 55559. DIMENSIONS: 12" x 12" x 1/32".

VCT-6
 STYLE: PROGRESSIONS OR APPROVED EQUAL. COLOR: EGGSHELL 55244. DIMENSIONS: 12" x 12" x 1/32".

VCT-7
 STYLE: PROGRESSIONS OR APPROVED EQUAL. COLOR: GINGERBREAD 55529. DIMENSIONS: 12" x 12" x 1/32".

LUXURY VINYL TILE

NOT USED

LVT-1
 STYLE: NATURAL CREATIONS ARBORART OR APPROVED EQUAL. PATTERN: DRIFTWOOD BRONZE TP63. FORM: FLANK. DIMENSIONS: 48" x 9" x 0.125".

LVT-2
 STYLE: NATURAL CREATIONS MYSTIX OR APPROVED EQUAL. PATTERN: MORGCCO CLOVE 1P727. FORM: TILE. DIMENSIONS: 18" x 18" x 0.125".

LVT-3
 STYLE: NATURAL CREATIONS MYSTIX OR APPROVED EQUAL. PATTERN: ARIA CHARCOAL TP796. COLOR: COLOR MATCHING END CAPS.

SOLID RUBBER TILE
 AS MANUFACTURED BY MANNINGTON SALES REPRESENTATIVE: JESSICA D'ANGELO. PHONE: 610-675-6599

NOTE: TO BE INSTALLED WITH MANUFACTURER'S TWO PART EPOXY ADHESIVE

SRT-1
 STYLE: COLORSPEC OR APPROVED EQUAL. COLOR: FOG 874. DIMENSIONS: 18-1/8" x 18-1/8" x 1/8".

SRT-2
 STYLE: COLORSPEC OR APPROVED EQUAL. COLOR: FLINT 875. DIMENSIONS: 18-1/8" x 18-1/8" x 1/8".

SRT-3
 STYLE: COLORSPEC OR APPROVED EQUAL. COLOR: ALPINE GLOW 879. DIMENSIONS: 18-1/8" x 18-1/8" x 1/8".

SRT-4
 STYLE: COLORSPEC OR APPROVED EQUAL. COLOR: SEDUM 880. DIMENSIONS: 18-1/8" x 18-1/8" x 1/8".

SHEET VINYL
 AS MANUFACTURED BY MANNINGTON SALES REPRESENTATIVE: JESSICA D'ANGELO. PHONE: 610-675-6599

SV-1
 STYLE: BIOSPEC MD OR APPROVED EQUAL. COLOR: SANDSPRIT 1030. DIMENSIONS: 6" ROLL GOODS x 0.080" THICKNESS. HEAT WELD: COLOR MATCHING.

SVB-1
 FLASH COVE WALL BASE OR APPROVED EQUAL. STYLE: TO MATCH SV-1. COLOR: TO MATCH SV-1. DIMENSIONS: 6" H. ACCESSORIES: #040 ROUND CAP - 1/8" AND 1-1/8" RADIUS PLASTIC COVE FILLET STRIP.

SV-2
 STYLE: BIOSPEC MD OR APPROVED EQUAL. COLOR: TOASTED SESAME 10333. DIMENSIONS: 6" ROLL GOODS x 0.080" THICKNESS. HEAT WELD: COLOR MATCHING.

SVB-2
 FLASH COVE WALL BASE OR APPROVED EQUAL. STYLE: TO MATCH SV-2. COLOR: TO MATCH SV-2. DIMENSIONS: 6" H. ACCESSORIES: #040 ROUND CAP - 1/8" AND 1-1/8" RADIUS PLASTIC COVE FILLET STRIP.

SV-3
 STYLE: BIOSPEC MD OR APPROVED EQUAL. COLOR: BROWNSTONE 15385. DIMENSIONS: 6" ROLL GOODS x 0.080" THICKNESS. HEAT WELD: COLOR MATCHING.

SVB-3
 FLASH COVE WALL BASE OR APPROVED EQUAL. STYLE: TO MATCH SV-3. COLOR: TO MATCH SV-3. DIMENSIONS: 6" H. ACCESSORIES: #040 ROUND CAP - 1/8" AND 1-1/8" RADIUS PLASTIC COVE FILLET STRIP.

SV-4
 STYLE: BIOSPEC MD OR APPROVED EQUAL. COLOR: LAVENDER GREY 19414. DIMENSIONS: 6" ROLL GOODS x 0.080" THICKNESS. HEAT WELD: COLOR MATCHING.

SVB-4
 FLASH COVE WALL BASE OR APPROVED EQUAL. STYLE: TO MATCH SV-4. DIMENSIONS: 24" x 24". INSTALLATION: QUARTER TURN FOR USE IN LOBBY AND WAITING AREAS.

SV-5
 STYLE: BIOSPEC MD OR APPROVED EQUAL. COLOR: TARRAGON 15388. DIMENSIONS: 6" ROLL GOODS x 0.080" THICKNESS. HEAT WELD: COLOR MATCHING.

SVB-5
 FLASH COVE WALL BASE OR APPROVED EQUAL. STYLE: TO MATCH SV-5. COLOR: TO MATCH SV-5. DIMENSIONS: 6" H. ACCESSORIES: #040 ROUND CAP - 1/8" AND 1-1/8" RADIUS PLASTIC COVE FILLET STRIP.

SV-6
 STYLE: BIOSPEC MD OR APPROVED EQUAL. COLOR: DARK CHOCOLATE 15398. DIMENSIONS: 6" ROLL GOODS x 0.080" THICKNESS. HEAT WELD: COLOR MATCHING.

CERAMIC TILE
 AS MANUFACTURED BY MEGHOSHADES SYSTEMS SALES REPRESENTATIVE: JAMIE BLOK. PHONE: 215-516-1731

CT-1
 STYLE: ERG - STONE PROJECT. COLOR: GREY. CUT: GROSS CUT. FINISH: NATURAL. DIMENSIONS: 12" x 24" x 3/8". GROUT JOINT: 1/8". GROUT COLOR: T80.

CTB-1
 SERIES: TO MATCH CT-1. STYLE: TO MATCH CT-1. COLOR: AUTUMN LEAF 55559. DIMENSIONS: 12" x 12" x 1/32".

CT-2
 STYLE: ERG - STONE PROJECT. COLOR: GREY. CUT: VENICUT. DIMENSIONS: 12" x 24" x 3/8". GROUT JOINT: 1/8". GROUT COLOR: T80.

CT-3
 STYLE: SPARK COLORBODY PORCELAIN OR APPROVED EQUAL. COLOR: TOASTED LUSTER SK52. DIMENSIONS: 12" x 24" x 1/8". GROUT COLOR: T80.

SEAMLESS EPOXY FLOOR
 AS MANUFACTURED BY STONHARD, INC. SALES REPRESENTATIVE: BOB STEIN. PHONE: 610-416-0171

EP-1
 STYLE: STONGLAD LITF OR APPROVED EQUAL. COLOR: PEWTER. GAUGE: 1/4" (6mm). TEXTURE: MEDIUM WITH URETHANE BASED SEALER FOR USE WITH THE MORGUE.

EPB-1
 STYLE: TO MATCH EP-1. COLOR: TO MATCH EP-1. DIMENSIONS: 6" H INTEGRAL BASE.

EP-2
 STYLE: STONGLAD GS EPOXY MORTAR WITH STONKOTE GSA EPOXY PIGMENTED TOPCOAT OR APPROVED EQUAL. COLOR: PEWTER. GAUGE: 1/4" (6mm). TEXTURE: MEDIUM WITH URETHANE BASED SEALER FOR USE AS TYPICAL SUPPORT SPACE FLOOR (I.E. TRASH ROOM, PUMP ROOM, ETC.)

EPB-2
 STYLE: TO MATCH EP-2. COLOR: TO MATCH EP-2. DIMENSIONS: 6" H INTEGRAL BASE.

EP-3
 STYLE: STONRES RTX. COLOR: TARDIA PEARL. GAUGE: 1/4" (6mm). TEXTURE: MEDIUM WITH URETHANE BASED SEALER FOR USE WITHIN THE EMPLOYEE BREAK ROOM ON THE 1ST FLOOR.

EPB-3
 STYLE: TO MATCH EP-3. COLOR: TO MATCH EP-3. DIMENSIONS: 6" H INTEGRAL BASE.

ENTRANCE MAT
 AS MANUFACTURED BY THE MOHAWK GROUP - LEES SALES REPRESENTATIVE: MICHELLE RUBANDO. PHONE: 215-630-6993

EM-1
 COLLECTION: TUFF STUFF OR APPROVED EQUAL. STYLE: STEP IN STYLE MODULAR GT06. COLOR: BLANET STONE 00518. DIMENSIONS: 24" x 24". INSTALLATION: BRICK.

FLOORING ACCESSORIES
 ACCESSORY PICES: SCHLUTER TRANSITION STRIPS. CARPET TO RESILIENT OR SHEET VINYL: SCHLUTER SCHEINE-AE100. CARPET TO LVT: SCHLUTER SCHEINE-AE100. CARPET TO CERAMIC TILE: SCHLUTER SCHEINE-AE100. CARPET TO EXISTING: SCHLUTER-RENO-RAMP-AERP 1005. CERAMIC TILE TO EPOXY: SCHLUTER SCHEINE-AE100. CERAMIC TILE TO SHEET VINYL: SCHLUTER SCHEINE-AE100.

DECORATIVE GLAZING
 AS MANUFACTURED BY SKYLINE DESIGN SALES REPRESENTATIVE: CINDY BENTZ. PHONE: 215-348-8786

DG-1
 MATERIAL: BOTANICA LAVENDER - OPTION 2B. SIDE ONE: ECO ETCH PATTERN ON CLEAR FIELD. SIDE TWO: CLEAR PATTERN ON ECO ETCH FIELD.

DG-2
 MATERIAL: BOTANICA WILD PERSIMMON - GLASS CONCEPT 4A. SIDE ONE: ECO ETCH PATTERN ON CLEAR FIELD. SIDE TWO: CLEAR PATTERN ON ECO ETCH FIELD.

DG-3
 MATERIAL: ORGANICS FERN. SIDE ONE: ECO ETCH PATTERN ON CLEAR FIELD. SIDE TWO: ECO ETCH PATTERN ON CLEAR FIELD.

FABRIC WRAPPED PANELS
 AS MANUFACTURED BY CARNegie FABRICS SALES REPRESENTATIVE: TERRI MARTELL. PHONE: 305-952-6411

FWP-1
 STYLE: XOREL - FLUX 6557. COLOR: F79. CONTENTS: 100% XOREL. WIDTH: 58". REPEAT: 3/4" LENGTH. BACKING: ACRYLIC BACKING.

CUBICLE CURTAIN
 AS MANUFACTURED BY ARCHITEX SALES REPRESENTATIVE: SHAWN WENTRAUB. PHONE: 610-322-8993

TO BE INSTALLED 15" A.F.F. TO BOTTOM OF HEM WITH CODE COMPLIANT MESH AT TOP WHERE REQUIRED.

CC-1
 STYLE: RA600. COLOR: LEAF. WIDTH: 72". PATTERN REPEAT: 12" V. NONE H. RAILROCKS: REVERSE REPEAT. CONTENTS: 100% TREVIRA CS.

WT-1
 MANUAL SHADE: MEGHOSH SLIMLINE WITH FASCIA OR APPROVED EQUAL. MOUNT: WALL OR CEILING. SHADE/LOTH: ECOVEL 1350 SERIES (5% OPEN). COLOR: WHITE 1551. CONTENT: 100% THERMOPLASTIC OLEFIN. WIDTH: 100". NFPA 701-2004: PASS. FOR USE ON ALL EXTERIOR WINDOWS EXCEPT FOR 1ST FLOOR ENTRANCE AND 2ND FLR WAITING, U.N.O.

WT-2
 MANUAL SHADE: MEGHOSH WIDE DOUBLESHADE #16 WITH FASCIA OR APPROVED EQUAL. MOUNT: WALL OR CEILING. DIMENSIONS: 5-6/8" D X 7-11/16" H. SHADE/LOTH #1: ECOVEL 1350 SERIES (5% OPEN). COLOR: WHITE 1551. CONTENT: 100% THERMOPLASTIC OLEFIN. WIDTH: 100". NFPA 701-2004: PASS. FOR USE IN THE FIRST FLOOR WAITING AREA, U.N.O.

WT-3
 MOTORIZED SHADE: ELECTRO1 EXTENDED DRIVE END BRACKET CONTROLLER: SUNDLIER WINDOWMANAGEMENT SYSTEM. MOUNT: CEILING POCKET #5113. SHADE/LOTH: ECOVEL 1350 SERIES (5% OPEN). COLOR: WHITE 1551. CONTENT: 100% THERMOPLASTIC OLEFIN. WIDTH: UP TO 180" W. LENGTH: 150". NFPA 701-2004: PASS. FOR USE IN THE FIRST FLOOR WAITING AREA, U.N.O.

EP-1
 STYLE: STONGLAD LITF OR APPROVED EQUAL. COLOR: PEWTER. GAUGE: 1/4" (6mm). TEXTURE: MEDIUM WITH URETHANE BASED SEALER FOR USE WITH THE MORGUE.

EPB-1
 STYLE: TO MATCH EP-1. COLOR: TO MATCH EP-1. DIMENSIONS: 6" H INTEGRAL BASE.

EP-2
 STYLE: STONGLAD GS EPOXY MORTAR WITH STONKOTE GSA EPOXY PIGMENTED TOPCOAT OR APPROVED EQUAL. COLOR: PEWTER. GAUGE: 1/4" (6mm). TEXTURE: MEDIUM WITH URETHANE BASED SEALER FOR USE AS TYPICAL SUPPORT SPACE FLOOR (I.E. TRASH ROOM, PUMP ROOM, ETC.)

EPB-2
 STYLE: TO MATCH EP-2. COLOR: TO MATCH EP-2. DIMENSIONS: 6" H INTEGRAL BASE.

EP-3
 STYLE: STONRES RTX. COLOR: TARDIA PEARL. GAUGE: 1/4" (6mm). TEXTURE: MEDIUM WITH URETHANE BASED SEALER FOR USE WITHIN THE EMPLOYEE BREAK ROOM ON THE 1ST FLOOR.

EPB-3
 STYLE: TO MATCH EP-3. COLOR: TO MATCH EP-3. DIMENSIONS: 6" H INTEGRAL BASE.

ENTRANCE MAT
 AS MANUFACTURED BY THE MOHAWK GROUP - LEES SALES REPRESENTATIVE: MICHELLE RUBANDO. PHONE: 215-630-6993

EM-1
 COLLECTION: TUFF STUFF OR APPROVED EQUAL. STYLE: STEP IN STYLE MODULAR GT06. COLOR: BLANET STONE 00518. DIMENSIONS: 24" x 24". INSTALLATION: BRICK.

FLOORING ACCESSORIES
 ACCESSORY PICES: SCHLUTER TRANSITION STRIPS. CARPET TO RESILIENT OR SHEET VINYL: SCHLUTER SCHEINE-AE100. CARPET TO LVT: SCHLUTER SCHEINE-AE100. CARPET TO CERAMIC TILE: SCHLUTER SCHEINE-AE100. CARPET TO EXISTING: SCHLUTER-RENO-RAMP-AERP 1005. CERAMIC TILE TO EPOXY: SCHLUTER SCHEINE-AE100. CERAMIC TILE TO SHEET VINYL: SCHLUTER SCHEINE-AE100.

DECORATIVE GLAZING
 AS MANUFACTURED BY SKYLINE DESIGN SALES REPRESENTATIVE: CINDY BENTZ. PHONE: 215-348-8786

DG-1
 MATERIAL: BOTANICA LAVENDER - OPTION 2B. SIDE ONE: ECO ETCH PATTERN ON CLEAR FIELD. SIDE TWO: CLEAR PATTERN ON ECO ETCH FIELD.

DG-2
 MATERIAL: BOTANICA WILD PERSIMMON - GLASS CONCEPT 4A. SIDE ONE: ECO ETCH PATTERN ON CLEAR FIELD. SIDE TWO: CLEAR PATTERN ON ECO ETCH FIELD.

DG-3
 MATERIAL: ORGANICS FERN. SIDE ONE: ECO ETCH PATTERN ON CLEAR FIELD. SIDE TWO: ECO ETCH PATTERN ON CLEAR FIELD.

EQUIPMENT SCHEDULE - 3545						
EQUIP #	DESCRIPTION	RELOCATED BY	PURCHASED BY	PLACED BY	INSTALLED BY	COMMENTS
002	AV Cart	OWNER	OWNER	OWNER	OWNER	54"H x 30"W x 22"D
005	Workstation Mounting Bracket W/Adjustable Arm and Computer	OWNER	OWNER	OWNER	OWNER	
006	Wheel Chair	OWNER	OWNER	OWNER	OWNER	
007	Wheelchair, Bariatric	OWNER	OWNER	OWNER	OWNER	
008	Microscope	OWNER	OWNER	OWNER	OWNER	
010	Crash Cart	OWNER	OWNER	OWNER	OWNER	Omnicell G4 w/ 20 LL Defibrillator Monitor Pacemaker
011b	Triple Box Glove Dispenser	OWNER	OWNER	OWNER	CONTRACTOR	
014	Hamper, Soiled Linen	OWNER	OWNER	OWNER	OWNER	
20a	Locker, 12"x12"x72" Flat Top	-	CONTRACTOR	CONTRACTOR	CONTRACTOR	
020a	Locker Full Height, 12"x15"x72" Flat Top	-	CONTRACTOR	CONTRACTOR	CONTRACTOR	
020b	Locker, Full Height - Purse	-	CONTRACTOR	CONTRACTOR	CONTRACTOR	
026	Printer/Fax/Copier, Floor Standing	OWNER	OWNER	OWNER	OWNER	
027	Printer, Countertop	OWNER	OWNER	OWNER	OWNER	Lexmark
031	Refrigerator with Freezer	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	
032	Refrigerator, Undercounter, Medical Grade	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	
034a	Disposal, Sharps, Floor	OWNER	OWNER	OWNER	OWNER	
039	Stool, Exam, Cushion-Seat	-	OWNER	OWNER	OWNER	
041	Table, Exam	-	OWNER	CONTRACTOR	CONTRACTOR	
046	Track, Cubicle Curtain, Ceiling Mounted	-	CONTRACTOR	CONTRACTOR	CONTRACTOR	
053a	Label Machine	OWNER	OWNER	OWNER	OWNER	Zebra Z Series Metal
053b	Label Machine	OWNER	OWNER	OWNER	OWNER	
053c	Label Machine	OWNER	OWNER	OWNER	OWNER	24 M Plus
065	Kiosk, Check-In, Registration	-	OWNER	CONTRACTOR	CONTRACTOR	
066	Ophthalmic Stand	-	OWNER	CONTRACTOR	CONTRACTOR	
068	Cart Medication	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	
069	Specimen Lock Box	-	OWNER	CONTRACTOR	CONTRACTOR	
101	Cabinet, Flammable Storage	CONTRACTOR	-	CONTRACTOR	CONTRACTOR	
117	Monitor, LCD, 24"	-	OWNER	CONTRACTOR	CONTRACTOR	
123	Lift, Portable, Patient	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	Genie Model SLA-
125	Urine Analysis System	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	Arkray AX-4280
126	Immunoassay System, Access 2	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	Beckman Coulter
128	Refrigerator, Blood Bank, Double Door	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	Helmer Series Horizon
129	Refrigerator, Blood Bank, Single Door	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	
130	DxC 600, with Workstation	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	UniCel DxC 600 Synchron Clinical System (BBR11-1B) Thermo Fisher Jewett
131	Refrigerator, Blood Bank, Single Door, TFJ	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	Boekel Incubator
132	Incubator, Digital	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	Tosoh : G8 HPLC Analyzer
134	Analyzer	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	
135	Hemostasis Analyzer	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	
137	Hematology Analyzer	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	Coulter LH 500 - Water connection
138	Water Purification System	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	Coulter LH 500 - Water connection
139	Slide Strainer	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	Midas II Slide Strainer
140	Monitor, Computer, LCD, 24"	OWNER	OWNER	OWNER	OWNER	
141	Powerwar UPS	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	Powerwar
144	Chair, Clinical, Blood Draw	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	
145	Biofreeze, Ultra Low Freezer	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	(Reyco Freezers) Thermo Scientific: B.C. Allegra X-22 Series
146	Centrifuge	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	
147	Centrifuge - Beckman Spinchron	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	Bechman Spinchron
148	Bio Hood	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	
149	Printer, Countertop	OWNER	OWNER	OWNER	OWNER	Brother HL-5340D
150	Refrigerator with Freezer, -20 degrees	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	
151	Printer, Countertop	OWNER	OWNER	OWNER	OWNER	
152	Shredder	OWNER	OWNER	OWNER	OWNER	Nexcut : E-Series Shred Cart
153	Data Innovations	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	
154	Data Link	CONTRACTOR	OWNER	CONTRACTOR	CONTRACTOR	
157	Patient Lift	-	CONTRACTOR	CONTRACTOR	CONTRACTOR	REFER TO DETAIL F9/AE603
200	Portable MRI Unit, 14' X 60'	-	OWNER	CONTRACTOR	CONTRACTOR	Unit with AC Units and Chiller