

TABLE 1
SUMMARY OF BUILDING MATERIALS
Sorted by Building and Material Code

VA Medical Center Building 41
5000 W National Ave, West Milwaukee, WI
Project Reference #: 13490

Building: 1

Material Code	Material Description	ACM	Estimated Qty
MB8M-1	8" BRICK & MORTAR - CREAM	NEG	
MCT-1	CEILING TILE & MASTIC - 12 INCH: WHITE W/HOLES (TILE - NEG; MASTIC - POS)	POS	1070 sf
MF12-1	12" FLOOR TILE & MASTIC - CREAM WITH BLACK STREAKS	POS	1615 sf
MF9-1	9" FLOOR TILE & MASTIC - GRAY WITH BLACK STREAKS	POS	100 sf
MFL-1	LINOLEUM & MASTIC - BROWN, CREAM	NEG	
MFSP	BLACK FLOOR SQUEAK PAPER	NEG	
MPG-1	WINDOW PANE GLAZING - CREAM (<1% ASBESTOS BY PLM)	POS	4000 lf
MRS-1	ROOF SHINGLE - BLACK	ATC	
MRS-2	ROOF SHINGLE - GREEN	ATC	
MRS-3	ROOF SHINGLE - GRAY	ATC	
MSBM	STONE BLOCK MORTAR	NEG	
MSTD-1	STAIR TREAD - BROWN	NEG	
MV4-1	4" VINYL BASEBOARD & MASTIC - BLACK	NEG	
SPI-C	PLASTER - CEILING	NEG	
SPI-W	PLASTER - WALL	NEG	
TF10F	6-10" FITTING ON FIBERGLASS PIPE INSULATION	ATC	15 E
TF5F	0-5" FITTING ON FIBERGLASS	ATC	10 E
TM10	6-10" MAGNESIA PIPE INSULATION	ATC	150 lf
TM5	0-5" MAGNESIA PIPE INSULATION	ATC	100 lf

Notes:
sf = Square Feet
lf = Linear Feet
E = Each

ATC = Assumed to contain asbestos
NEG = Asbestos content less than or equal to one percent
POS = Asbestos content greater than one percent