

SCOPE OF WORK

INSTALL NEW ROOF STRUCTURE ON EXISTING MATERIAL STORAGE BINS FORT MCPHERSON NATIONAL CEMETERY, MAXWELL, NE 69151

- A. The Contractor: Shall furnish all labor, material, equipment, and supervision to construct a new wood-frame construction, standing seam metal roof and metal siding clad walls on top of two existing material storage bins, as described herein.
- B. The Work: The Work shall include, but shall not be limited to the following (not necessarily in the order indicated):
1. Contractor shall construct a 16' x 49' rectangular frame structure per the manufacturers' requirements with two interior compartment walls, back wall, and 3/12 slope mono-pitch roof with eaves meeting the following criteria:
 - a. Standing seam metal roof system on 5/8" CDX treated roof sheathing and pressure treated wood purlins
 - b. Prefinished vertical rib metal siding on 1/2" CDX treated sheathing and wood studs.
 - c. 22-gauge steel roof panels and 24-gauge steel sidewall panels.
 - d. Factory applied finish on all steel and aluminum components.
 - e. Colors shall be as follows: Side panels: "Yellow Sand" exterior (to match surrounding maintenance buildings), "White" interior. Roof panels: "Special Brown" (to match PIC standing seam metal roof).
 2. Haul away & dump debris and waste to an approved disposal site.
 3. Thoroughly clean up the work area at the end of each day's work, and at completion of the project. Leave premises clean and free of waste, scrap, used equipment, or other material intentionally or incidentally delivered to the site by Contractor or Contractor's personnel.
 4. Upon completion of work, structure manufacturer's representative shall inspect the completed work and issue warranty.
- C. Time of Completion: The project shall be completed within 120 calendar days after contract award.
- D. Code Compliance: All work shall be performed in accordance with the International Building Code (IBC).
- E. Contractor Quality Control: The Job Site Superintendent will: a) review and approve submittals, b) inspect the quality of work performed, and c) certify the completed work for payment and other purposes.
- F. Availability/Constraints of Site: See attachments "*Section 01 00 00, General Requirements*"; "*Section 01 33 23, Shop Drawings and Product Data*"; "*Section 01 42 19, Reference Standards*"; "*Section 01 74 19, Construction Waste Management*"; "*Section 06 10 00, Rough Carpentry*"; "*Section 07 40 00, Roof and Siding Panels*"; "*Section 07 41 13, Standing Seam Metal Roofing*"; "*Section 07 60 00, Flashing and Sheet Metal*"; "*Section 07 92 00, Joint Sealants*"; and "*Fort McPherson National Cemetery - Additional Information and Requirements*."
- G. Submittals After Award: Submit the following documentation:
1. Specifications and test reports for products to be used including manufacturer's recommended procedures for installation.
 2. Samples per specifications.
 2. Material Safety Data Sheets for all products.
 3. Roof warranty information and Roof Information Card.
- H. Drawings: Sheet X-1, "*Title Sheet*"; Sheet L-1, "*Site Plan*"; Sheet A-1, "*Roof Plan and Elevations*"; and Sheet A-2, "*Sections and Details*."
- I. POC: The Contracting Officer's Representative (COR) for this project is: Ted Feeney.
- J. Project completion: The project site shall be protected and/or restored to a condition equal to that existing prior to the commencement of work.

END OF SCOPE OF WORK