

**SECTION 01 00 00
GENERAL REQUIREMENTS**

TABLE OF CONTENTS

1.1	GENERAL INTENTION	2
1.2	STATEMENT OF BID ITEM(S).....	2
1.3	SPECIFICATIONS AND DRAWINGS FOR CONTRACTOR	2
1.4	FIRE SAFETY.....	2
1.5	OPERATIONS AND STORAGE AREAS.....	3
1.6	ALTERATIONS.....	3
1.7	DISPOSAL AND RETENTION	4
1.8	PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS	4
1.9	RESTORATION	5
1.10	USE OF ROADWAYS.....	5
1.11	TEMPORARY TOILETS	5
1.12	AVAILABILITY AND USE OF UTILITY SERVICES	5
1.13	HISTORIC PRESERVATION	6

SECTION 01 00 00
GENERAL REQUIREMENTS

1.1 GENERAL INTENTION

- A. Contractor shall completely furnish labor, tools, equipment, materials, etc to perform work as required by drawings and specifications.
- B. Visits to the site by Bidders may be made only by appointment with Cemetery Director.

1.2 STATEMENT OF BID ITEM(S)

- A. **ITEM I, GENERAL CONSTRUCTION:** Work includes general construction to accomplish installation of a new standing seam metal roof and metal siding over wood frame for the existing concrete material storage bins at Fort McPherson National Cemetery.

1.3 SPECIFICATIONS AND DRAWINGS FOR CONTRACTOR

- A. **AFTER AWARD OF CONTRACT,** 2 sets of specifications and drawings will be furnished.

1.4 FIRE SAFETY

- A. Applicable Publications: Publications listed below form part of this Article to extent referenced. Publications are referenced in text by basic designations only.
 - 1. American Society for Testing and Materials (ASTM)
 - E84-1998 Surface Burning Characteristics of Building Materials
 - 2. National Fire Protection Association (NFPA):
 - 10-1998 Standard for Portable Fire Extinguishers
 - FCLCH-30-1996 Flammable and Combustible Liquids Code
 - 51B-1999 Standard for Fire Prevention During Welding, Cutting and Other Hot Work
 - 70-1999 National Electrical Code
 - 241-1996 Standard for Safeguarding Construction, Alteration, and Demolition Operations
 - 3. Occupational Safety and Health Administration (OSHA)
 - 29 CFR 1926 Safety and Health Regulations for Construction
- B. Fire Safety Plan: Establish and maintain a fire protection program in accordance with 29 CFR 1926. Prior to start of work, prepare a plan detailing project-specific fire safety measures, including periodic status reports, and submit to COR.
- C. Site and Building Access: Maintain free and unobstructed access to facility emergency services and for fire, police and other emergency response forces in accordance with NFPA 241.
- D. Separate temporary facilities, such as trailers, storage sheds, and dumpsters, from existing buildings and new construction by distances in accordance with NFPA 241. For small facilities with less than 6 m (20 feet) exposing overall length, separate by 3m (10 feet).
- E. Fire Extinguishers: Provide and maintain extinguishers in construction areas and temporary storage areas in accordance with 29 CFR 1926, NFPA 241 and NFPA 10.
- F. Flammable and Combustible Liquids: Store, dispense and use liquids in accordance with 29 CFR 1926, NFPA 241 and NFPA 30.
- G. Smoking: Smoking is prohibited in and adjacent to construction areas inside existing buildings and additions under construction. In separate and detached buildings under construction, smoking is prohibited except in designated smoking rest areas.
- H. Dispose of waste and debris in accordance with NFPA 241. Remove from site daily.

- I. Perform other construction, alteration and demolition operations in accordance with 29 CFR 1926.

1.5 OPERATIONS AND STORAGE AREAS

- A. The Contractor shall confine all operations (including storage of materials) on Government premises to areas authorized or approved by the Contracting Officer. The Contractor shall hold and save the Government, its officers and agents, free and harmless from liability of any nature occasioned by the Contractor's performance.
- B. Temporary buildings (e.g., storage sheds, shops, offices) and utilities may be erected by the Contractor only with the approval of the Contracting Officer and shall be built with labor and materials furnished by the Contractor without expense to the Government. The temporary buildings and utilities shall remain the property of the Contractor and shall be removed by the Contractor at its expense upon completion of the work. With the written consent of the Contracting Officer, the buildings and utilities may be abandoned and need not be removed.
- C. The Contractor shall, under regulations prescribed by the Contracting Officer, use only established roadways, or use temporary roadways constructed by the Contractor when and as authorized by the Contracting Officer. When materials are transported in prosecuting the work, vehicles shall not be loaded beyond the loading capacity recommended by the manufacturer of the vehicle or prescribed by any Federal, State, or local law or regulation. When it is necessary to cross curbs or sidewalks, the Contractor shall protect them from damage. The Contractor shall repair or pay for the repair of any damaged curbs, sidewalks, or roads.
- D. Working space and space available for storing materials shall be as determined by the COR.
- E. Workmen are subject to rules of Cemetery applicable to their conduct.
- F. Execute work in such a manner as to interfere as little as possible with work being done by others. Keep roads clear of construction materials, debris, standing construction equipment and vehicles at all times.
- G. Contractor shall notify the COR two weeks in advance of the proposed date of starting work. Arrange such dates to ensure accomplishment of this work in successive phases mutually agreeable to Cemetery Director and COR.
- H. Construction Fence: Before work begins, Contractor shall provide a 4' high orange plastic snow fence around the work area. Maintain fence to protect employees and public from construction area hazards.
- I. To minimize interference of construction activities with flow of Cemetery traffic, comply with the following:
 1. Keep roads, walks and entrances to grounds, to parking and to occupied areas of buildings clear of construction materials, debris and standing construction equipment and vehicles. At least one lane must be open to traffic at all times.
 2. Method and scheduling of required cutting, altering and removal of existing roads, walks and entrances must be approved by the COR.
- J. Coordination of Construction with Cemetery Director: The burial activities at a National Cemetery shall take precedence over construction activities. The Contractor must cooperate and coordinate with the Cemetery Director, through the COR, in arranging construction schedule to cause the least possible interference with cemetery activities. Construction noise during the interment services shall not disturb the service. Trucks and workmen shall not pass through the service area during this period.
- K. The Contractor is required to discontinue his work sufficiently in advance of Federal holidays.

1.6 ALTERATIONS

- A. Survey: Before any work is started, the Contractor shall photo-document a thorough survey with the COR of areas in which work is to occur, and areas which are anticipated routes of access, and furnish a copy to the Contracting Officer. The Contractor is responsible for verifying all dimensions in the drawings. The documentation shall note any discrepancies between drawings and existing conditions at site. Documentation shall designate areas for working space, materials storage and routes of access to areas within buildings where alterations occur and which have been agreed upon by Contractor and COR.
- B. Re Survey: One week before expected partial or final inspection date, the Contractor and COR together shall make a thorough re survey of the work areas. They shall report on conditions as compared with conditions of same as noted in preconstruction survey.
 - 1. Re survey report shall also list any damage caused by and, will form basis for determining extent of repair work required of Contractor to restore damage caused by Contractor's workmen in executing work of this contract.
- C. Protection: Provide the following protective measures:
 - 1. Temporary protection against damage for portions of existing structures and grounds where work is to be done, materials handled and equipment moved and/or relocated.
 - 2. Dampen debris to keep down dust during construction. Broom clean at the end of each workday. Remove debris as it is created.

1.7 DISPOSAL AND RETENTION

- A. Materials and equipment accruing from work removed and from demolition of buildings or structures, or parts thereof, shall be disposed of in accordance with contract specification Section 01 74 19 CONSTRUCTION WASTE MANAGEMENT, and as follows:
 - 1. Reserved items which are to remain property of the Government are identified by the COR or noted on drawings or in specifications as items to be stored. Items that remain property of the Government shall be removed or dislodged from present locations in such a manner as to prevent damage which would be detrimental to re-installation and reuse. Store such items where directed by COR.
 - 2. Items not reserved shall become property of the Contractor and be removed by Contractor from the Cemetery.
 - 3. Items of portable equipment and furnishings located in rooms and spaces in which work is to be done under this contract shall remain the property of the Government. Such items which are NOT required by drawings and specifications to be either relocated or reused will be removed by the Government in advance of work to avoid interfering with Contractor's operation.

1.8 PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS

- A. The Contractor shall preserve and protect all structures, equipment, and vegetation (such as trees, shrubs, and grass) on or adjacent to the work site, that are not to be removed and which do not unreasonably interfere with the work required under this contract. The Contractor shall only remove trees when specifically authorized to do so, and shall avoid damaging vegetation that will remain in place. If any limbs or branches of trees are broken during contract performance, or by the careless operation of equipment, or by workmen, the Contractor shall trim those limbs or branches with a clean cut and paint the cut with a tree pruning compound as directed by the Contracting Officer.
- B. The Contractor shall protect from damage all existing improvements and utilities at or near the work site and on adjacent property of a third party, the locations of which are made known to or should be known by the Contractor. The Contractor shall repair any damage to those facilities, including those that are the property of a third party, resulting from failure to

comply with the requirements of this contract or failure to exercise reasonable care in performing the work. If the Contractor fails or refuses to repair the damage promptly, the Contracting Officer may have the necessary work performed and charge the cost to the Contractor.

1.9 RESTORATION

- A. Remove, cut, alter, replace, patch and repair existing work as necessary to install new work. Existing work to be altered or extended and that is found to be defective in any way, shall be reported to the COR before it is disturbed. Materials and workmanship used in restoring work, shall conform in type and quality to that of original existing construction, except as otherwise shown or specified.
- B. Upon completion of contract, deliver work complete and undamaged. Existing work (walls, ceilings, partitions, floors, mechanical and electrical work, lawns, paving, roads, walks, etc.) disturbed or removed as a result of performing required new work, shall be patched, repaired, reinstalled, or replaced with new work, and refinished and left in as good condition as existed before commencing work.
- C. At Contractor's own expense, Contractor shall immediately restore to service and repair any damage caused by Contractor's workmen to existing piping and conduits, wires, cables, etc., of utility services or of fire protection systems and communications systems (including telephone) which are indicated on drawings and which are not scheduled for discontinuance or abandonment.
- D. Expense of repairs to such utilities and systems not shown on drawings or locations of which are unknown will be covered by adjustment to contract time and price in accordance with clause entitled "CHANGES" (FAR 52.243 4 and VAAR 852.236 88) and "DIFFERING SITE CONDITIONS" (FAR 52.236 2).

1.10 USE OF ROADWAYS

- A. For hauling, use only established public roads and roads on Cemetery property and, when authorized by the COR, such temporary roads which are necessary in the performance of contract work. Temporary roads shall be constructed by the Contractor at Contractor's expense. When necessary to cross curbing, sidewalks, or similar construction, they must be protected by well constructed bridges.

1.11 TEMPORARY TOILETS

- A. Provide for use of all Contractor's workmen ample temporary sanitary toilet accommodations, i.e. provide suitable dry closets. Keep such places clean and free from flies and all connections and appliances connected therewith are to be removed prior to completion of contract, and premises left perfectly clean.

1.12 AVAILABILITY AND USE OF UTILITY SERVICES

- A. The Government shall make all reasonably required amounts of utilities available to the Contractor from existing outlets and supplies, as specified in the contract. The Contractor shall carefully conserve any utilities furnished without charge.
- B. The Contractor, at Contractor's expense and in a workmanlike manner satisfactory to the Contracting Officer, shall install and maintain all necessary temporary connections and distribution lines.
- C. Electricity:
 - 1. Electricity is available in vicinity of worksite for general-use equipment.
 - 2. Provide and utilize portable generators as needed for all welding operations.

D. Water:

1. Obtain water by connecting to the Cemetery water distribution system and shall be coordinated with the Cemetery Director. Provide reduced pressure backflow preventer at each connection. Water is available at no cost to the Contractor. Water is availability may be restricted and it is the contractor's responsibility to transport it to job locations as needed.
2. Maintain connections, pipe, fittings and fixtures and conserve water use so none is wasted.

1.13 HISTORIC PRESERVATION

Where the Contractor or any of the Contractor's employees, prior to, or during the construction work, are advised of or discover any possible archeological, historical and/or cultural resources, the Contractor shall immediately notify the COR and/or Cemetery Director verbally, and then with a written follow up.

E N D