



JLG Architects

Ryan M. Murphy, Assoc. AIA

214 Broadway

Minneapolis, MN 55401

p. 701.364.0237 f. 701.364.0228

rmurphy@jlgarchitects.com

Project Name: **Loading Dock Leveler Replacement**

Project Number: 11080C/437-13-119

May 23, 2013

Addendum No. 1

NOTICE TO CONTRACTORS

This Addendum is prepared to supplement information presented in the Drawings and Project Manual dated May 17, 2013 for the above referenced project. All additions, changes, omissions and conditions listed herein shall become an integral part of the Contract Documents.

SPECIFICATIONS

Section 00 01 10 – Table of Contents

1. Delete the following specification sections:
 - a. 01 32 16.15 – Project Schedules (Small Projects – Design/Bid/Build)
 - b. 01 42 19 – Reference Standards
2. Add the following specification section:
 - a. 03 30 00 – Cast-in-Place Concrete

Section 01 00 00 – General Conditions

Section 01 32 16.15 – Project Schedules (Small Projects – Design/Bid/Build)

1. Delete section in its entirety.

Section 01 33 23 – Shop Drawings, Product Data, and Samples

1. Paragraph 1-5: Change the words “Resident Engineer” to read “Architect-Engineer”.
2. Paragraph 1-7: Delete the last sentence.
3. Paragraph 1-9.B: Modify the second sentence to read in part “...name of Medical Center, VA Project Title, VA Project Number, name of Contractor...”
4. Paragraph 1-9.B.2: Modify the first sentence to read in part “...name of Medical Center, VA Project Title, VA Project Number, name of Contractor...”

Section 01 42 19 – Reference Standards

1. Delete section in its entirety.

Section 03 30 00 – Cast-in-Place Concrete

1. Delete paragraph 1.2 and subparagraph 1.2.A.

Section 05 50 00 – Metal Fabrications

1. Modify paragraph 3.2 with “3.2 Loading Dock Angles.”
2. Paragraphs 3.2.A and 3.2.B: Replace the word “frames” with the word “angles”.

Section 11 13 19.13 – Loading Dock Levelers

1. Delete paragraph 2.01.A.4.
2. Add the following to paragraph 2.02.A.1: “Provide hydraulic equipment and fluids rated for extreme cold weather (minimum-30 deg F).”

DRAWINGS

GI001 – TITLE SHEET

1. Add the following note to section “General Notes & Conditions”: The contractor shall provide construction fencing around all work areas as required to keep the general public out of the construction site and for the safety of VA employees. This shall also be provided at the interior side of Building 12 as the loading dock pit extends to the interior of the building.

GI001 – TITLE SHEET

1. Add the following note to section “General Notes & Conditions”: The contractor shall provide directional and safety signage for all project locations and entrances. Where a work location contains two levelers, signage shall be provided which directs activity to the open leveler as work is performed at the other.

AS201 – Architectural Elevations, Sections and Details:

1. Detail 9/AS201 (also reference detail 10/AS201): Add Keynote #17 to corner bumper shown at each side of the leveler pit. Keynote #17 shall read: “CORNER DOCK BUMPER”.

END OF ADDENDUM NO. 1