

# LEGEND

- SEED AND MULCH ALL DISTURBED AREAS
- PROPOSED 4" CONCRETE WALK
- PROPOSED CONCRETE PAVEMENT
- G.S. EXISTING GUTTER DOWNSPOUT
- PROPOSED PAVEMENT ELEVATION

- PROPOSED 4" CONCRETE WALK
- PROPOSED INTEGRAL CONCRETE CURB
- PROPOSED 8" CONCRETE APRON - WITHIN LIMITS OF EXISTING ROAD RIGHT OF WAY (ODOT ITEM 451 - REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT)
- PROPOSED 8" DIA. CONCRETE FILLED STEEL BOLLARDS
- PROPOSED 8" CONCRETE PAD (ODOT ITEM 451 - REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT)
- EXISTING RELOCATED DUMPSTERS
- PROPOSED 6' HIGH DOUBLE SWING GATE (INWARD) WITH 100% VISUAL SCREEN INFILL PANELS
- NOT USED
- EXISTING RELOCATED GRILLS
- PROPOSED CONCRETE PARKING BLOCK (SEE ODOT STANDARD CONSTRUCTION DRAWING RM-6.1)
- STRIPING FOR PARKING STALLS (ODOT CMS ITEM 642-TRAFFIC PAINT)
- PROPOSED GAS, WATER AND SANITARY SERVICE CONNECTIONS - SEE MECHANICAL PLANS FOR ADDITIONAL DETAILS
- RE-ERECT 16± LINEAR FEET OF WOOD FENCE
- PROPOSED 5" CONCRETE PAVEMENT - PARKING AREA AND DRIVE OUTSIDE THE LIMITS OF EXISTING ROAD RIGHT OF WAY (ODOT ITEM 451 - REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT)
- UNDERGROUND ELECTRIC CONDUITS FOR GENERATOR - COORDINATE PROPOSED WORK AS TO NOT DISTURB EXISTING CONDUITS.

## NOTES

- DEDUCT ALTERNATE NO. 2 BID ITEM IS THE CONCRETE WALK REMOVAL AND REPAIR ALONG LORAIN AVE. AND WEST 94TH STREET AS SHOWN ON THIS DRAWING. CONCRETE WALK REMOVAL AND REPLACEMENT THAT IS NECESSARY TO CONSTRUCT THE NEW DRIVE APRONS ARE NOT PART OF DEDUCT ALTERNATE NO. 2 BID ITEM.
- SEE SHEET C-3 FOR CONCRETE JOINT LAYOUT PLAN.
- CONTRACTOR SHALL MAINTAIN POSITIVE DRAINAGE DURING ALL PHASES OF CONSTRUCTION.
- CONTRACTOR SHALL FINISH GRADE ALL DISTURBED AREAS TO MAINTAIN POSITIVE DRAINAGE.
- PROVIDE 1.0% MINIMUM SLOPE ON ALL PAVED SURFACES.

## SOUTH EDGE OF DRIVE/PARKING AREA CURVE DATA

CURVE 1	CURVE 2	CURVE 3
Δ = 33° 51' 10"	Δ = 8° 15' 13"	Δ = 20° 24' 52"
CL = 32.03'	CL = 40.85'	CL = 24.81'
R = 55.00'	R = 283.86'	R = 70.00'
A = 32.50'	A = 40.89'	A = 24.94'


## BENCHMARK

MAG NAIL SET IN SIDEWALK AT SOUTHWEST CORNER OF LORAIN AVE. / WEST 94TH STREET INTERSECTION - ELEV. 98.69

MAG NAIL SET IN SIDEWALK ON THE EAST SIDE OF WEST 94TH STREET DIRECTLY ACROSS FROM VACATED HENLEY AVE. - ELEV. 100.00

FOR CONSTRUCTION

## CONSULTANTS:



**EUTHENAKIS INC.**  
CONSULTING ENGINEERS  
8235 KOWAR DR., TROBROOKVILLE, OHIO 44130  
PHONE: (440) 380-1350 • FAX: (440) 380-1344



## ARCHITECT/ENGINEERS:



**MAKOVICH & PUSTI**  
ARCHITECTS, INC.  
111 FRONT STREET, BUREAU, OHIO 44017  
(440) 891-0910 • FAX: (440) 891-0900

## Drawing Title

SITE PLAN

Approved: Project Director

## Project Title

VAMC WADE PARK CLEVELAND  
TR HOUSE IMPROVEMENTS

Location

9401 LORAIN AVE., CLEVELAND, OHIO 44102

Date

12/06/12

Checked By

RAB

Drawn By

ARP

## Project Number


541-12-125

Building Number

Drawing Number

C-2

Office of  
Construction  
and Facilities  
Management



10 0 10 20  
SCALE IN FEET

