


LEVEL ONE FLOOR PLAN

COMPONENT	REMOVAL METHOD
LEAD-BASED PAINT ON WINDOWS	2
LEAD-BASED PAINT ON WINDOWS	1
LEAD-BASED PAINT ON COLUMNS	1
LEAD-BASED PAINT GARAGE DOOR & FRAME	1
LEAD-BASED PAINT ON CORNER GUARDS	1
LEAD-BASED PAINT ON DOOR FRAME	1
LEAD-BASED PAINT ON DOOR	1
LEAD-BASED PAINT ON STAIR RAILING	1
LEAD-BASED PAINT ON RAMPS	1
LEAD-BASED PAINT FLOOR & WALLS	1
LEAD-BASED PAINT BRICK WALLS	2
LEAD-BASED PAINT WINDOWS & WALLS	2
LEAD-BASED PAINT ELEVATOR DOOR FRAME	1
LEAD-BASED PAINT CAGE SCREEN	3

**REMOVAL METHOD**  
 1. REMOVE LEAD-BASED PAINT UTILIZING CHEMICAL STRIPPING AND/OR ABRASIVE BLASTING METHODS THAT ARE COMPATIBLE WITH SUBSTRATE.  
 2. STABILIZE LEAD-BASED PAINT AND REPAINT BY OTHERS  
 3. REMOVE COMPONENT, WILL BE REPLACED BY OTHERS.  
 OUTSIDE OF WORK AREA



**Drawing Title**  
 LEAD-BASED PAINT REMEDIATION PLANS  
 LEVEL ONE FLOOR PLAN  
 Approved: Project Director

**Project Title**  
 LEAD ABATEMENT REMEDIATION PLAN

**Location**  
 FORT SNELLING, MINNEAPOLIS, MN

**Date**  
 3-08-2013

**Checked**  
 [Signature]

**Drawn**  
 [Signature]

**Project Number**  
 618-12-303

**Building Number**  
 222

**Drawing Number**  
 Dwg 2 of 15



No.	Revisions:	Date
	BID DOCUMENTS	3-08-2013