









three inches = one foot
one and one half inches = one foot
one inch = one foot
three quarters inch = one foot
one half inch = one foot
one eighth inch = one foot
one quarter inch = one foot
one eighth inch = one foot



KEYNOTES

- 3.003 EXISTING CONCRETE SLAB.
3.004 EXISTING CONCRETE DECK.
4.001 EXISTING MASONRY WALL.
7.203 INSULATION: THERMAL BATT; THICKNESS AS INDICATED.
7.260 VAPOR BARRIER.
7.841 FIRESTOPPING: SEALANT; REFER TO SPECIFICATIONS.
7.900 JOINT SEALANT: REFER TO SCHEDULE; PROVIDE BACKER ROD OR BOND BREAKER.
9.101 METAL STUD FRAMING: 1-5/8" STUD; 16" O.C. SPACING; 20 GAUGE UNLESS NOTED OTHERWISE; ANCHORAGE TO SUIT APPLICATION.
9.103 METAL STUD FRAMING: 3-5/8" STUD; 16" O.C. SPACING; 20 GAUGE UNLESS NOTED OTHERWISE; ANCHORAGE TO SUIT APPLICATION.
9.106 METAL STUD FRAMING: 6" STUD; 16" O.C. SPACING; 20 GAUGE UNLESS NOTED OTHERWISE; ANCHORAGE TO SUIT APPLICATION.
9.120 METAL STUD FRAMING: STUD RUNNER: SIZE TO MATCH METAL STUDS.
9.121 METAL STUD FRAMING: DOUBLE STUD RUNNER: FOR DEFLECTION RELIEF.
9.250 GYPSUM BOARD: 5/8" THICK; TYPE "X".
9.260 GYPSUM BOARD ACCESSORY: ACOUSTICAL INSULATION: SOUND ATTENUATION BATTS; THICKNESS AS SPECIFIED.
9.261 GYPSUM BOARD ACCESSORY: ACOUSTICAL INSULATION: SOUND ATTENUATION BATTS; THICKNESS AS SPECIFIED.
9.510 ACOUSTICAL CEILING PANELS AND GRID.



GENERAL NOTES

- REFER TO DRAWING G001 FOR PROJECT GENERAL NOTES
- REFER TO DRAWING G003 FOR KEYNOTE DESCRIPTIONS NOT APPEARING ON THIS DRAWING.
- REFER TO DRAWING A001, ROOM FINISH SCHEDULE, FOR B/CEILING ELEVATIONS AND DRAWING A401, REFLECTED CEILING PLANS, FOR B/SOFFIT ELEVATIONS.
- CONSTRUCT FIRE RATED ASSEMBLIES IN ACCORDANCE WITH UL DESIGN REQUIREMENTS.
- KEYNOTES TYPICALLY ARE NOT DUPLICATED WITHIN A GIVEN DETAIL. AN UN-KEYED ITEM IS THE SAME AS THE KEYNOTED ITEM WITHIN THE DETAIL.
- PROVIDE UL APPROVED FIRE STOPPING SYSTEMS AT JOINTS IN, PERIMETERS OF, AND PENETRATIONS THROUGH FIRE RATED ASSEMBLIES.
- WHERE TOPS OF NON-RATED WALLS OR PARTITIONS ARE EXPOSED TO VIEW, NEATLY PROVIDE PAINTABLE JOINT SEALANT THAT SEALS THE GAP BETWEEN TOP OF PARTITION AND THE UNDERSIDE OF DECK OR STRUCTURE ABOVE.
- REGARDLESS OF DRYWALL PARTITION TYPE DESCRIPTION, PROVIDE CEMENT BOARD IN LIEU OF GYPSUM BOARD AT LOCATIONS SCHEDULED TO RECEIVE PORCELAIN/CERAMIC WALL TILE.
- IN METAL STUD FRAMED PARTITIONS, PROVIDE 2x FIRE RETARDANT TREATED WOOD BLOCKING FOR WALL-MOUNTED ITEMS REQUIRING MECHANICAL ANCHORAGE.

NON-RATED PARTITION
SCALE: 3" = 1'-0"

NON-RATED PARTITION
SCALE: 3" = 1'-0"

NON-RATED PARTITION
SCALE: 3" = 1'-0"

1-HR RATED PARTITION
SCALE: 3" = 1'-0"

NO. CONSTRUCTION DOCUMENTS FOR BID	04-12-13
NO. CONSTRUCTION DOCUMENTS SUBMITTAL	03-12-13
NO. CONSTRUCTION DOCUMENTS SUBMITTAL	02-09-13
Revisions	Date

CONSULTANTS:

ARCHITECT/ENGINEERS:

Kluber, Inc.
10 South Shumway
Batavia, Illinois 60510
tel. 630.406.1213
fax 630.406.9472
www.kluberinc.com

Kluber
Architects - Engineers

Drawing Title

WALL TYPES

Approved: Project Director

Project Title

HINES BUILDING 37
O.I. AND T. FIELD OFFICES - PHASE 3
OFFICE AND RESTROOM RENOVATIONS

Location

VA OFFICE OF ACQUISITION AND LOGISTICS
HINES, ILLINOIS

Date
04-12-13

Checked
CJH

Drawn
CJH

Project Number

796-13-004

Building Number

37

Drawing Number

37 - A1101
Dwg. 12 of 32

Office of
Construction and Facilities
Management

Department of
Veterans Affairs